

UTAH OIL AN	ID GAS CONSERVATION COMMISSION	
REMARKS: WELL LOG ELECTRIC LOGS X	WATER SANDS LOCATION INSPECTED	SUB. REPORT/abd.
	٦	
DATE FILED JANUARY 5, 1996		
LAND: FEE & PATENTED STATE LEASE NO. ML - 38666	PUBLIC LEASE NO.	INDIAN
DRILLING APPROVED: FEBRUARY 14, 1996		
SPUDDED IN: FEBRUARY IT 1991		
COMPLETED: 10-11-CI (6 WIDM) PUT TO PRODUCING:		
INITIAL PRODUCTION:		
GRAVITY A.P.I.		
GOR:		
PRODUCING ZONES:		
TOTAL DEPTH: (05/0)		
WELL ELEVATION: 56911 GR		
DATE ABANDONED:		
FIELD: UNDESIGNATED		
UNIT: DRUNKARDS WASH		
COUNTY: CARBON		
WELL NO. UTAH D-3	API NO. 4	3-007-30290
LOCATION 1600 FSL FT. FROM (N) (S) LINE, 1126 F	WL FT. FROM (E) (W) LINE. N	W SW 1/4 = 1/4 SEC. 18
TWP. RGE SEC. OPERATOR	TWP. RGE.	SEC. OPERATOR

	1			UTAH OIL	AND GAS COI	NSERVATION C	OMMISSIO	N				
REMARKS:	WELL LOG	ELEC	CTRIC LOGS	X	WATER SANDS	LOCAT	ION INSPECTE	D_	SUE	3. REPORT/abd.		
******										-1-272		
DATE FILED	IAU	NUARY	5, 1996									
LAND: FEE & F		STATE L		8666		PUBLIC LEASE NO.				INDIAN		
DRILLING APPR	ROVED: FEE	BRUARY	14, 1996	1								
SPUDDED IN:	FEBRI	IARN	27 1996									
COMPLETED:	10-14-0	で か	PUT TO PRODUC	ING:								
INITIAL PRODU	JCTION:											
GRAVITY A.P.I.												
GOR:												
PRODUCING Z	ONES:											
TOTAL DEPTH	- 1	25/0))		**************************************							
WELL ELEVATI	-	-691	1 GR									
DATE ABANDO	NED:	,										
FIELD:	UNI	DESIGN	ATED							,		
UNIT:			S WASH									
COUNTY:		RBON										
WELL NO.		4H D-3				AP:	NO.	43-007	7-30290)		
LOCATION	1600 F	FSL F	T. FROM (N) (S) LINE,	1126	FWL	FT. FROM (E) (W		NW SW		1/4 - 1/4 SEC.	18	
TWP.	RGE.	SEC.	OPERATOR			TWP.	RGE.	SEC.	OPERATOR			
15S	10E	18	RIVER GA	C CODD							The state of the s	

GEOLOGIC TOPS:


7.74			
QUATERNARY	Star Point	Chinle	Molas
Alluvium	Wahweap	Shinarump	Manning Canyon
Lake beds	Maşuk	Moenkopi	Mississippian
Pleistocene	Colorado	Sinbad	Humbug
Lake beds	Sego	PERMIAN	Brazer
TERTIARY	Buck Tongue	Kaibab	Pilot Shale
Pliocene	Castlegate	Coconino	Madison
Salt Lake	Mancos	Cutler	Leadville
Oligocene	Upper	Hoskinnini	Redwall
Norwood	Middle	DeChelly	DEVONIAN
Eocene	Lower	White Rim	Upper
Duchesne River	Emery	Organ Rock	Middle
Uinta	Blue Gate	Cedar Mesa	Lower
Bridger	Ferron	Halgaite Tongue	Ouray
Green River	Frontier	Phosphoria	Elbert
	Dakota	Park City	McCracken
	Burro Canyon	Rico (Goodridge)	Aneth
	Cedar Mountain	Supai	Simonson Dolomite
	Buckhorn	Wolfcamp	Sevy Dolomite
	JURASSIC	CARBON I FEROUS	North Point
Wasatch	Morrison	Pennsylvanian	SILURIAN
Stone Cabin	Salt Wash	Oquirrh	Laketown Dolomite
Colton	San Rafeat Gr.	Weber	ORDOVICIAN
Flagstaff	Summerville	Morgan	Eureka Quartzite
North Horn	Bluff Sandstone	Hermosa	Pogonip Limestone
Almy	Curtis		CAMBRIAN
Paleocene	Entrada	Pardox	Lynch
Current Creek	Moab Tongue	Ismay	Bowman
North Horn	Carmel	Desert Creek	Tapeats
CRETACEOUS	Glen Canyon Gr.	Akah	Ophir
Montana	Navajo SandSpone 5550-59/6	J Barker Creek	Tintic
Mesaverde	Kayenta		PRE - CAMBRIAN
Price River	Wingate Science Coco - 6056	Cane Creek	
Bla, khawk	TRIASSIC		

ACME VISIBLE CROZET VIRGINIA 100730

STATE OF UTAH DIVISION OF OIL, GAS AND MINING

		DIL, GAS AND MI			3. Lease Designation :	and Serial No.
					ML-38666	
APPLICATION	FOR PERMIT T	O DRILL, DEEP	EN, OR PLUC	3 BACK	6. If Indian, Allotted	or Tribe Name
Type of Work DRILL	X	DEEPEN [PLUG	BACK [7. Unit Agreement Nar	ne
Type of Well Oil Gas	_				UTU67921x	
Well Well	Other Wa	ter Disposal	Single Zone	Multiple Zone	3. Farm or Lease Nun	ie
Name of Operator	_				Utah	
River Gas Address of Operator	Corporation				9. Weil No.	
	r contou Doule		h		D-3 10. Field and Pool, or	IV:11
ocation of Weil (Report	location clearly and in a	vard Northport	requirements *1			
se sarrack		Sec. 18, T15S,			Drunkards V	
lt proposed prod. zone	•	, ,	,		and Survey or Area	
Distance in miles and dire	petion from nearest lowe	on part office			NW/SW Sec.	18, T15S,
		outhwest of Pri	ice		12. County or Parrish	13. State
Distance from proposed*	maroo boath b		o. of acres in leaze	17 Ya a	Carbon	Ut.
location to nearest property or lease line, ft.				to this		
(Also to newest drig. line, Distance from proposed to	ocation.	19. P-	921.98		N/A	
to nearest well, drilling, cor applied for, on this less	completed.		5300 '			
Elevations (Show whether	DF, RT, GR, etc.)		3300	rota	22. Approx. date work	will sture
GR 5691'					February	
	P	ROPOSED CASING AND	CEMENTING PROGE	MAS	TODIAGE	,,100
Size of Hole	Size of Casing	Weight per Foot	Setting Depth		Quantity of Cement	
12 174"		0.6.11				
8 1/2"	9 5/8"	36# 26#	500'	·		
			6300'	 :	See Attach	ment 5
				•	,	


						r V K. b
				5.		W B
						W 15
					JAN 5	1996
				Section 1997 and 1997	JAN 5	1996
	,				JAN 5	1996 S & RENGIA



	DIVISION OF	OIL, GAS AND I	MINING			ML 386	66
	INDRY NOTICES						
Ua nortise this form for	proposals to drill new welfard Use APPLICATION F	one permit — fursich Or. PERMIT — fursich	r proposels	plugged and abur	coned wells.	8. Unit of Com	munitization Agreement
1. Type of Well Cit Weil	☐ Gas 🔯	Other (specify)	trom Dá			\$. Well Name a	nd Number
2. Name of Operator		Wa	ter Di	sposal Well		Utah D- 10. AFI Well Nur	_
River Gas Con 3. Address of Operator	poration			4. Telephone Nu	nper	Not yet	assigned
511 Energy Ce	enter Blvd.; Nort	hport, AL 354	76	(205) 759-	· · · · · · · · · · · · · · · · · · ·		rds Wash
Foolage QQ, Sec, T., R., M.		riss, Rice			County :	: UTAH	
12. CHECK	APPROPRIATE 60	ES#TO INDICAT	ENATU	REOFMOTI		The state of the s	
	NOTICE OF INTENT (Submit in Duplicate)				SUBSEC (Submit 0	NUENT REPOR	ST
Abandonment Casing Repair Change of Plant Conversion to in Fracture Treat Multiple Comple	Pull of Reconsider Shoot Vent of Water	Construction r Alter Casing mpletion or Acidize or Flare Shut-Off		Abandonmen Casing Repai Change of Pla Conversion to Fracture Trea Other	ns njection	Pull o	Construction or Alter Casing t or Acidize or Flare or Shut-Off
M Other Revis	ion of Casing De	sign	- Da	ite of Work Com	pletion		1
Approximate Date V	Vork Will Start <u>ASAP</u>		1 00	port results of Muli WELL COMPLET! Must be accompan	div on vecoi	MPLETION AND I	etions to different reservoirs
THE RESERVE TO SERVE	DOR COMPLETED OPERAT ed and true vertical depths for copy of the sche TING PROGRAM:	# (!!@(VBI9 @TIP \$01163	bermanr m	mis work.)			my dimed, give subsettles
Hole Size	Casing Size	Wght/ft, 48 lbs		ing Depth	Cen	ment Quant	ity (est.)
12 1/4"	9 5/8"	36 1bs		500'	. 2	280 sx Hi-	ss G, 15.8ppg Lift, 11 ppg plus
8 3/4 "	7"	26 lbs	6	300'	1	Stage 1(bó 50/50 Poz. 100 sx RFC	ss G, 15.8 ppg ttom): 225 sx 12.5 ppg, and , 14.2 ppg op): 190 sx 50/50 RFC
14 I hargby Gently that the	foregoing is true and agfrage						
trame & Signature Deni	(,)	nnis Pla	umo	t m Title	Reservoi	Ir Technic	ian _{Oate} 02/08/96
(State Ush Crity)	Nathbeur 1-30290	Petrole		Eugmee		a,	114/96
90,00	, ,	Post-it [™] Fax	.::	7671 Date 2	12-96 pe	of ages •	
(3.50)		Co./Dept.	vis," M. H	EBERISA From T	13		
	•	Phone #	,	Phone	G-C		
		Fax # 801-	359-39	Fax#			
					B		

PROPOSED DISPOSAL WELL D-3

SEC. 18, T 15 S, R 10 E (1600' FSL, 1126 FWL) CARBON COUNTY, UTAH



STATE OF UTAH DIVISION OF OIL, GAS AND MINING


	DIAIZION OF	OIL, GAS AND M	INING				_
•					5. Lease Designation ML-38666	and Serial No.	
APPLICATION	EOD DEDAUT	C DOUL DEED	TN 00 DU	10 0 1 614	6. If Indian, Allottee	or Tribe Name	-
	FOR PERMIT	O DRILL, DEEP	EN, OR PLL	JG BACK			
la. Type of Work DRILL	וציז	OEEDENI (T	Ditt	C P. CV .	7. Unit Agreement Na	me	-
b. Type of Well	وعق	DEEPEN [PLU	G BACK [UTU67921x		
Oil Gas Well Wel	Other Wa	ater Disposal	Single Zone	Multiple	3. Farm or Lease Nar	me	
2. Name of Operator			20110	Zuite —	Utah		
	Corporation				9. Weil No.		
5. Address of Operator					D-3		
511 Energ	y center Boule	evard Northpor	t, A1. 35476)	10. Field and Pool, or	Wildent	-
4. Location of Weil (Report At surface	location clearly and in	accordance with any Stat	e requirements.*)		Drunkards		_
1600' F	SL, 1126' FWL	Sec. 18, T15S	, R10E		11. QQ, Sec., T., R., H. and Survey or Area	, or Bik.	_
At proposed prod. zone			·				
14. Distance in miles and d	irection from neurest tox	in or nost office*			NW/SW Sec.	18, T15S,	_R10E
		southwest of Pr	ice		1		
15. Distance from proposed			No. of acres in lease	17. No. o	Carbon	l Ut.	•
location to nearest property or lease line, f	t		001 00	to thi	is well		
(Also to nearest drig. lin 13. Distance from proposed	location*	19. P	921.98		N/A		•
or applied for, on this le	completed,		6300'				
21. Elevations (Show whethe			0300_	rota	22. Approx. date wor	k will start*	•
GR 5691'					Februar	v 1996	
23.		PROPOSED CASING AN	D CEMENTING PRO	GRAM	Toplati	<i>y</i> , 2000	•
Size of Hole	Size of Casing	Weight per Foat	Setting Depth	1	Quantity of Cemen	ıt	. •
12 174"	0. 5/04	26.11	F00!				
8 1/2"	9 5/8"	36# 26#	500' 6300'		Coo Attoo	hmant 5	
OL/		∠5#	- 63UU'		See Attac	ment 5	
			····				



IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24. I hereby certify that this report is been and complete the the true and complete the true

Signed Terry D. Burns Luy O. Burn Title Geologist	Date 01-04-96
(This space for Federal or State office ye)	
AFT NO. 43-007-30290 APPROVAL BALE	
Approved by TAN allkeit Titl Tetroleum Engineer	Date 2/14/96
Conditions of approval, if any:	•





- FOUND BRASS CAP
- SEARCHED FOR BUT NOT FOUND
- FOUND ROCK CORNER

BASIS OF BEARING

BASIS OF BEARING N 88'57'03' E MEASURED BETWEEN THE NW CORNER AND THE N1/4 CORNER OF SECTION 19, TOWNSHIP 15 SOUTH, RANGE 10 EAST, SALT LAKE BASE AND MERIDIAN.

ENGINEER'S CERTIFICATE

I, EVAN E. HANSEN, DO HERBY CERTIFY THAT I AM A REGEISTERED LAND SURVEYOR AND PROFESSIONAL ENGINEER HOLDING CERTIFICATE NUMBER 145656 AS PRESCRIBED UNDER THE LAWS OF THE STATE OF UTAH. I FURTHER CERTIFY THAT I HAVE MADE A SURVEY OF THE TRACT OF GROUND SHOWN AND THAT IT IS TRUE AND CURRECT TO THE BEST OF MY KNOWLEDGE.

EVEN E. HANSEN DATE

SW1/4 SEC. 18, T 15 S, R 10 E, S.L.B.& M.

Empire Engineering

1665 E. Sagewood Rd. Price, Utah 84501

RIVER GAS CORP. WELL #D-3

Drawn By: TLH	Approved By: EEH	
Date: 12/20/95	Scale: 1'=1000'	EEOG-9472A




RIVER GAS CORPORATION

511 Energy Center Blvd. Northport, Alabama 35476 Phone (205) 759-3282 Fax (205) 759-3188 (Accounting) Fax (205) 758-5309 (Corporate)

January 4, 1996

Mr. Michael Hebertson Utah Board of Oil, Gas, and Mining Suite 350, 3 Triad Center 355 West North Temple Salt Lake City, Utah 84180-1203



Application for Permit to Drill -RE: D-3, NW 1/4 of SW 1/4 of Sec. 18, T15S, R10E S.L.B. & M., Carbon County, Utah

Dear Mr. Hebertson:

Enclosed is an original and one copy of an "Application for Permit to Drill" the well described above. Attached to the APD is the following information:

Attachment #1 Copy of survey plat of proposed well site

Attachment #2 Information regarding use of water at the site

Attachment #3 Schematic of B.O.P.

Portion of topographic map indicating Attachment #4

proposed well site

Attachment #5 Additional drilling information furnished

according to State regulations

Attachment #6 Typical road cross-section

Attachment #7 Evidence of bond sent to State Lands and

Forestry Division

Attachment # 8 Selected Points to be Addressed at On-Site

Pre-Drill Evaluation

Attachment #9 Drilling Layout

Attachment # 10 - Well Disposal Site Layout

Page Two

An archaelogical/paleontological survey is scheduled to be conducted during the 2nd week of this month, and will be submitted to you.

Also, please accept this letter as our request that all information regarding this permit be kept confidential, if said information is eligible for such consideration. This request is made in accordance with State of Utah Oil and Gas rule # R649-2-11.

Thank you for your assistance. Please feel free to contact me if you have questions.

Sincerely,

Lowy D. Burns

Terry D. Burns

Geologist

cc: Mr. Edward W. Bonner, Utah Department of Natural Resources

Mr. Eric Jones, BLM in Moab, Utah

Mr. Dean Nyffler, BLM in Price, Utah

Mr. Robert A. Hendricks, BLM in Salt Lake City, Utah


Mr. J.R. French, Texaco Mr. R.A. Lamarre, Texaco


Mr. Gee Lake, Jr., Dominion Reserves

EIVER GAS OF UTAH, INC. ATTACHMENT #2

RE: Use of Water During Drilling Operations

As stated, water which we will be using is to be purchased from the Price River Water Improvement District (Tel. 801-637-6350). This has been arranged by Mr. Michael J. Farrens, Drilling Supervisor for River Gas of Utah, Inc. He has been in contact with Mr. Phillip Palmer. Mr. Farrens has discussed this arrangement with Mark Page of the Division of Water Rights (Tel. 801-637-1303) over the telephone. The Division of Water Rights is to furnish the Oil & Gas Division with a letter of approval concerning this matter.





RIVER GAS CORPORATION

Additional Drilling Information

D-3 1600' FSL & 1126 ' FWL Section 18, Township 15 South, Range 10 East

R649-3-4 Permitting of Wells to be Drilled, Deepened or Plugged Back

2.1 Telephone numbers for additional information:

	Billy Stacy Operations Manager	(801)637-8876 Office (801)636-5660
	Steven L. Prince Asst. Operations Manager	(801)637-8876 Office (801)636-5256 Mobile
	Fred Passarella Pumper	(801)637-8876 Office (801)636-5257 Mobile
	Randy Nairemore	(801)637-8876 Office (801)636-5259 Mobile
	Michael J. Farrens Vice President	(205)759-3282 Office (205)758-8535 Home
2.2	Lease: State of Utah ML-38666	
2.3	This gas well will be drilled within Unit No. is UTU 67921X.	the Drunkards Wash Unit. The
2.4	Survey Plat: See Attachment #1	
2.5	Water will be purchased from Price See Attachment #2.	e River Water Improvement District:

- 2.6 **Drilling program**.
- 2.6.1 The following geologic units are expected to be penetrated in the well.

Formation/Unit	Est. Depth (top)
Upper Mancos Shale	Surface
Ferron Sandstone	1750
Tununk Shale	2000
Dakota Sandstone	2350
Morrison	3200
Summerville	3700
Curtis	4100
Entrada	4250
Carmel	4900
Navajo Sandstone	5600
Kayenta Sandstone	5900
T.D.	6300

- 2.6.2 This well is being drilled strictly for the injection of produced waters from RGC's surrounding coalbed methane operations. Zones which are expected to be gas & water-bearing are the coals and sandstones of the Ferron Formation. Other water-bearing zones to be penetrated are the Entrada and Navajo. No near surface groundwater is expected to be encountered.
- 2.6.3 A double gate 3000 psi BOPE will be used with a rotating head. This equipment will be tested to 2100 psi or 70% of the minimum internal yield pressure. All tests will be recorded in a Driller's Report Book. Physical operation of BOP's will be checked on each trip. See Attachment #3 for Schematic.
- 2.6.4 Casing Program 12 3/4" conductor pipe will be set to approx. 20'. 9 5/8", 36 lb/ft surface casing will be set to 500' and cemented with approx. 155 sacks of class "G" cement with 2% CaCl2, which has a density of 15.80 lb/gal. 7", 26 lb/ft LT&C production casing will be run and cemented with approximately 390 sacks 50/50 Pozmix cement and tail-in with approx. 130 sacks "RFC". Cement volumes may vary depending on hole conditions.

2.6.5 Mud Program:

<u>Depth</u>

0-500

12 1/4" hole

Drill with air, will mud-up if

necessary.

500-6300

8-1/2" hole

Drill with air.

400 psi @ 1500-1800 Scf.

2.6.6 Logging and Testing Program:

Depth

0-300

Gamma Ray

300-6300

Gamma Ray, SP, Neutron-Density, Bulk Density,


Induction, Caliper,

Sidewall cores, 7/8" diameter, 2" in length, will be obtained from selected zones within the Navajo and possibly Entrada Formations.

As requested by the DOGM, DST's will be conducted from Entrada and Navajo Formations.

2.6.7 We expect 2830 psi for bottom hole pressure. No hazards are expected.

RIVER GAS CORPORATION



TYPICAL ROAD CROSS-SECTION

NOT TO SCALE



Michael O. Leavitt Governor Ted Stewart Executive Director Robert L. Morgan State Engineer | 801-637-1303

Southeastern Area 453 South Carbon Avenue P.O. Box 718 Price, Utah 84501-0718

November 29, 1995

River Gas of Utah Attn: Steven Prince 290 South Highway 55 Price, Utah 84501

Re: Stream Channel Permit Applications

Dear Mr. Prince:

On several occasions, we have discussed when a Permit Application should be filed in conjunction with your gas development project west of Price. A permit must be filed if the following working definition applies: "Any natural waterway in the State which has flows of sufficient frequency and duration that it develops a characteristic ecosystem distinguishing it from the surrounding environment."

I hope this information is helpful. If at any particular location you are uncertain how to apply this definition, please call and I would be happy to meet with you and make the determination.

If I can provide any additional information, please do not hesitate to call or stop by my office.

Sincerely,

Mark P. Page Regional Engineer

MPP/mjk



AmSouth Bank

ATTACHMENT 7

FMSÓUTH BANK OF ALABAMA
1900-FIFTH AVENUE NORTH
BIRMINGHAM, ALABAMA 35203 USA
OUR RÉFÉRÈNCE NUMBER: S304606

International Services

Birmingham:

TELEX: 6827189 Cable: AMSOUBKBHM

S.W.I.F.T. AMSB US 44

Mobile:

TELEX: 6821116 Cable: AMSOMBL S.W.I.F.T. AMSB US 44

AMENDMENT NUMBER: 005

TO LETTER OF CREDIT NUMBER: \$304606

DATE: NOVEMBER 13, 1995

BENEFICIARY:
STATE OF UTAH, DEPARTMENT OF
NATURAL RESOURCES, DIVISION OF
STATE LANDS AND FORESTRY
#3 TRIAD CENTER SUITE 400
255 WEST TEMPLE
SALT LAKE CITY, UTAH 84180-1204

AT THE REQUEST OF RIVER GAS CORPORATION 511 ENERGY CENTER BLVD NORTHPORT, ALABAMA 35476

WE HEREBY AMEND OUR LETTER OF CREDIT NUMBER \$304606 DATED DECEMBER 14, 1990 OPENED IN YOUR FAVOR AS FOLLOWS:

-ACCOUNT PARTY'S ADDRESS IS CHANGES TO: 511 ENERGY CENTER BLVD.
NORTHPORT, ALABAMA 35476

REFERENCES HEREIN TO AMSOUTH BANK N.A. SHALL BE DEEMED TO REFER TO AMSOUTH BANK OF ALABAMA.

ALL OTHER TERMS AND CONDITIONS REMAIN UNCHANGED.
THIS AMENDMENT BECOMES AN INTEGRAL PART OF THE ORIGINAL LETTER OF CREDIT AND IS TO BE ATTACHED THERETO.

UTHORIZED SIGNATURE

A . 15

AmSouth Bank

1.5

AMSOUTH BEANK OF ALABAMA
1900 FIFTH AVENUE NORTH
BIRMINGHAM, ALABAMA 35203 USA
OUR REFERENCE NUMBER: S308586

International Services

Birmingham:

TELEX: 6827189 Cable: AMSOUBKBHM S.W.I.F.T. AMSB US 44

Mobile:

TELEX: 6821116 Cable: AMSOMBL S.W.I.F.T. AMSB US 44

AMENDMENT NUMBER: 002

TO LETTER OF CREDIT NUMBER: \$308586

DATE: NOVEMBER 13, 1995

BENEFICIARY:
STATE OF UTAH

DEPT. OF NATURAL RESOURCES
DIV. OF OIL, GAS AND MINING
355 WEST TEMPLE 3 TRIAD CENTER ...
SUITE 350
SALT LAKE CITY, UTAH 84180-1203

AT THE REQUEST OF RIVER GAS CORPORATION 3600 WATERMELON ROAD SUITE 204 NORTHPORT, ALABAMA 35476 AND FOR THE ACCOUNT OF SAME

WE HEREBY AMEND OUR LETTER OF CREDIT NUMBER \$308586 DATED DECEMBER 3, 1993 OPENED IN YOUR FAVOR AS FOLLOWS:

-ACCOUNT PARTY'S ADDRESS IS CHANGED TO: 511 ENERGY CENTER BLVD NORTHPORT, ALABAMA 35476

**REFERENCES HEREIN TO AMSOUTH BANK N.A. SHALL BE DEEMED TO REFER TO AMSOUTH BANK OF ALABAMA. **

ALL OTHER TERMS AND CONDITIONS REMAIN UNCHANGED.
THIS AMENDMENT BECOMES AN INTEGRAL PART OF THE ORIGINAL LETTER OF
CREDIT AND IS TO BE ATTACHED THERETO.

AUTHORIZED SIGNATURE

Attachment 8

D-3 1600' FSL, 1126 ' FWL, SEC. 18, T15S, R10E

Selected Points to be Addressed in On-site Predrill Evaluation

Surface Owner:

S.I.T.L.A

3 Triad Center, Suite 400 Salt Lake City, UT. 84180-1204

Surface Use Plan

Current Surface Use - Grazing. Lessee: Boyd Marsing P.O. Box 806 Price, Utah 84501

- Point #2 Location Access From Price Fairgrounds, follow project road westward through gate. Continue for approx. 1.7 miles to 4-way intersection. Turn left and head south for approx. 4.2 miles. Turn left, go by well #13-66, then 13-65. Turn right at intersection and head south for .40 miles. Turn left to well # 18-72. A new access road to subject well D-3 will be constructed from west side of 18-72 pad. (see Attachment #4)
- Point #3 Wells within 1-mile radius of proposed location See Attachment #4
- Point #4 Location of Production Facilities and Pipelines This well will be drilled strictly for water disposal. As shown on Attachment 10, a 225' x 175' well pad will be constructed. Just west of the pad will be a pump building, tanks, and a separator. Approximately 300' west of the drill pad, a 320' x 320' pond will be constructed. Total estimated surface disturbance: 7.80 acres.
- Point #6 Source of Construction Material In-place residual of Mancos Shale. Gravel will be purchased from a local contractor.
- Point #7 Waste Management Plan All drill cuttings will be diverted to pit, as well as fluids encountered. Afterwards, the fluids will be allowed to evaporate and cuttings will be buried. Also, a portable bathroom facility will be provided during drilling operations

DRLLING CAPACITY: 4,000' - 7.5

DRAWWORKS:

Franks 600

MAIN POWER:

CAT 3412TA

MAST:

Franks 112', 400,000# GNC

SUBSTRUCTURE:

12' or 15' high

PUMPS:

#1 Gardner Denver PZ7

#2 Gardner Denver PY7

PUMP POWER:

#1 CAT 3412 TA #2 CAT D-379

GENERATORS:

(2) CAT 3406, 200 kW and 175 kW

ROTARY TABLE:

Ideco 17.5*

SWIVEL:


Oliwell 150 ton

HOOK/BLOCK:


Ideco 160 ton, unitized

FUEL STORAGE:

10,000 gals




PROPOSED DISPOSAL WELL D-3



DISTURBED AREA - 278,050 SQ.FT. (6.38 Ac.)

RIVER GAS CORP. 2/6/96

PROPOSED DISPOSAL WELL D-3



DISTURBED AREA - 340,200 SQ. FT. (7.8 AC.)

ATTACHMENT 10

RIVER GAS CORP. 1/3/96

BASELINE DATA, INC.

1053 SOUTH STATE STREET OREM, UTAH 84058 (801) 224-5288 MN . 8 1996

January 12, 1996

Terry Burns River Gas of Utah 511 Energy Center Blvd. Northport, AL 35476

Re: Cultural report on Well #D-3

Dear Mr. Burns:

Due to the negative nature (no cultural resources were located) of this well survey, I am expediting the report to you in a letter format. Copies of this letter and attachments will be forwarded to the respective government review agencies; Division of Oil Gas and Mining (DOGM); State Institutional Trust Lands; and Utah State Historic Preservation Office (USHPO).

During the month of January, 1996, Baseline Data Inc. completed a cultural resource inventory of the proposed River Gas of Utah, Well #D-3. This well is located southwest of Price, Utah. The inventory was conducted by James R. Allison, Principal Investigator for Baseline. The inventory was requested by Terry Burns of River Gas of Utah, in Northport, Alabama. Ground visibility in January was excellent due to the warm weather and lack of snow cover preceding the survey. The inventory was carried out under Utah State Project Authorization No. U-96-BS-002s.

The survey area is located about 6 miles south of Price, Utah along SR 10, just north of Miller Creek. The well is located in Section 18, T. 15S, R. 10E, on the Price 7.5" Quad.

The survey area is within the Mancos Shale Lowlands Subsection of the Colorado Plateau Province (Stokes 1977). The area is dominated by eroded residual Mancos Shale Clay or alluvium and colluvium derived from the Mancos Shale. Soils in the surveyed area are very light brown silty sands. Vegetation in the surveyed area includes greasewood, snakeweed, saltbush, shadscale, lowsage, prickly pear, Indian rice grass. No wildlife was observed during the survey, but rabbit droppings are abundant and some coyote droppings were present as well.

The well location (survey area) was clearly marked by a large survey stake which marked the center of the proposed well pad. The access road was marked with pin-flags about 15 - 20 m

ARCHAEOLOGICAL HISTORICAL ENVIRONMENTAL

Terry Burns January 12, 1996 page 2

apart. A 150 m diameter circular area around the large center survey stake was examined by walking a series of concentric circles spaced approximately 10 m apart. The access road was surveyed by walking one transect on either side of the pin-flagging. A corridor with a total width of approximately 30 m was examined.

Baseline completed a Class I file search of the project area which included both historic and prehistoric cultural resources, at the State Historical Preservation Office. Martha Hayden, assistant State Paleontologist, was consulted regarding the necessity of a paleontological survey; she felt that the area in question had a very low probability for paleontological resources, and no paleontological survey was needed. There are no records of any cultural or paleontological sites within the survey area. Cultural resource inventories completed in the general project are summarized in a previous report completed for River Gas by Baseline (Norman et al. 1995). The National Register (January 5, 1995) was also examined. There are no sites currently listed on the National Register or sites being considered for nomination to the Register within the proposed project area.

No cultural resources of any kind (historic or prehistoric) were observed during this survey. It is the opinion of Baseline Data that this new well and access road will have no impact on the region's cultural or paleontological resource inventory. No further research or mitigation is recommended.

References noted in this letter include:

Norman, V. Garth, Asa S. Nielson, and Shane R. Sulz

1995 A Cultural Resource Inventory of the River Gas Corporation 1995 Drilling Season in Emery and Carbon County, Utah, on State, Private and Federal Land. Research Report No. U95-13, Baseline Data, Inc., Salt Lake City.

Stokes, William Lee

1977 Subdivisions of the Major Physiographic Provinces in Utah. *Utah Geology* Vol. 4
No. 1. Utah Geological and Mineral Survey, Department of Natural Resources, Salt Lake City, Utah.

Sincerely

Charles E. Hughes


President

cc: James Dykman, Utah Division of State History

Kenneth L. Wintch, State Institutional Trust Lands Administration

Mike Hebertson, Division of Oil, Gas, and Mining

Steven Prince, River Gas, Price, Utah



Project Location (Price 7.5 minute USGS quad map).

MUST ACCOMPANY ALL PROJECT REPORTS SUBMITTED TO UTAH SHPO

PROJECT NAME: River Gas Well Number D-3 **STATE PROJ. NO.:** U96-BS-002s PRINCIPAL INVESTIGATOR: James R. Allison FIELD SUPERVISOR(S) James R. Allison ACREAGE SURVEYED INTENSIVE: 5.1 ACRES RECON/INTUITIVE: 0 ACRES 7.5' SERIES USGS MAP REFERENCE(S): Price ARCHAEOLOGICAL SITES REVISITS (NO INVENTORY UPDATE) _0 **REVISITS (UPDATED IMACS ATTACHED)** 0 **NEW RECORDINGS (IMACS ATTACHED)** 0 TOTAL ARCHAEOLOGICAL SITES HISTORIC STRUCTURES (106 SITE INFO ATTACHED) 0 TOTAL NATIONAL REGISTER ELIGIBLE SITES **CHECKLIST OF REQUIRED ITEMS** 1. X 1 COPY OF THE FINAL REPORT 2. X 7.5' SERIES USGS MAP W/ SURVEY/EXCAVATION AREA MARKED 3. COMPLETED IMACS SITE INVENTORY FORMS, INCLUDING _ PARTS A AND B OR C. _ IMACS ENCODING FORM. __ SITE SKETCH MAP. __ PHOTOGRAPHS, AND __ 7.5' SERIES USGS MAP W/ SITE LOCATION MARKED AND LABELLED W/ SMITHSONIAN SITE NUMBER

4. X COMPLETED "COVER SHEET" W/ FINAL REPORT AND FORMS

STATE OF UTAH
DIVISION OF OIL. GAS AND MINING

APPLICATION FOR INJECTION WELL - UIC FORM 1

<u> </u>	E				
JAN	hid	199	3	المحتد	
;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;	1., G/	SE		NG	Section 12 Control

OPERATOR .	River Gas Corporation
	511 Energy Center Blvd.
	Northport, AL 35476

Well name and number:Utah_D-3	
Field or Unit name: Drunkards Wash Lease no.ML-38666	
Well location: QQ NW/SW section 18 township 158 range 10E county Carbon	
Is this application for expansion of an existing project? Yes 🗱 No []	
Will the proposed well be used for: Enhanced Recovery? Yes [] No [] Disposal? Yes [X No [] Storage? Yes [] No []	
Is this application for a new well to be drilled? Yes 🔀 No []	
If this application is for an existing well, has a casing test been performed on the well? Yes [] No [] Date of test: API number:	
Proposed injection interval: from $\frac{4,300}{5,600}$ to $\frac{5,000}{6,100}$	
Proposed maximum injection: rate pressure psig	
Proposed injection zone contains [] oil, [] gas, and/or [] fresh water within $\%$ mile of the well.	
IMPORTANT: Additional information as required by R615-5-2 should accompany this form.	
List of Attachments:	
I certify that this report is true and complete to the best of my knowledge.	
Name Charles Willis, P.E. Signature MM Title Vice President, Special Projects Date 1/9/96 Phone No. (205) 759-3282	
(State use only) Application approved by TitleApproval Date	

Comments: ** Eximum injection will be submitted at a later date

Disposal Well Application: Utah D-3

R649-5-2.2.13 To be submitted at a later date.

R649-5-2.	Requirements For Class II Injection Wells Including Water Disposal, Storage And Enhanced Recovery Wells.
R649-5-2.2	See attached.
R649-5-2.2.1	To be submitted at a later date.
R649-5-2.2.2	To be submitted at a later date.
R649-5-2.2.3	To be submitted at a later date.
R649-5-2.2.4	Logs will be referenced when applicable.
R649-5-2.2.5	To be submitted at a later date.
R649-5-2.2.6	To be submitted at a later date.
R649-5-2.2.7	To be submitted at a later date.
R649-5-2.2.8	To be submitted at a later date.
R649-5-2.2.9	To be submitted at a later date. JAN 1 1996
R649-5-2.2.10	To be submitted at a later date.
R649-5-2.2.11	See attached.
R649-5-2.2.12	To be submitted at a later date.

Utah D-3

Requirement R649-5-2.2.11

Review of Mechanical Integrity of Surrounding Wells

Utah 13-67 (RGU) - T.D. - 2,295'. 5-1/2" casing set at 2,231.0'. Circulated cement to surface.

Utah 18-69 (RGU) - T.D. - 2,095'. 5-1/2" casing set at 2,054.0'.
Circulated cement to surface.

Utah 18-71 (RGU) - T.D. - 1,945'. 5-1/2" casing set at 1,927.0'. Circulated cement to surface.

Utah 18-72 (RGU) - T.D. - 2,120'. 5-1/2" casing set at 2,086.0'.
Circulated cement to surface.

IAN 1 1 1996

医环状性髓膜 机氯化银矿

January 12, 1996

To: Charles Willis, River Gas Corp.

From: Gil Hunt, Utah Div. Of Oil, Gas & Mining

Subject: <u>Injection Application #D-3 Well</u>

If you would please provide the following additional information we will proceed with a public notice for this application.

- plat showing wells and ownership within $\frac{1}{2}$ mile
- proposed casing program
- a statement as to fluid source and copy of water analysis of produced water, injection zone water can come later
- general geologic information on target formations, specific info can come later after drilling well
- affidavit that at least notice has been given to owners and surface owners in area

This info can all be supplemented later if need be. This much will allow us to publish notice asap.

Thanks.



RIVER GAS CORPORATION


511 Energy Center Blvd.
Northport, Alabama 35476
Phone (205) 759-3282
Fax (205) 759-3188 (Accounting)
Fax (205) 758-5309 (Corporate)

January 9, 1996

Mr. Gil Hunt State of Utah Department of Natural Resources Division of Oil, Gas, and Mining 3 Triad Center, Suite 350 Salt Lake City, UT 84180-1203

RE: Utah D-3

Dear Mr. Hunt:



As we discussed, I am submitting an injection application for the above referenced well. Much of the information has yet to be determined and will be submitted as soon as possible. Please proceed with publishing the announcement of the proposal for public comment.

Please contact me at your convenience if I may be of any assistance.

Best regards,

Charles P. Willis, P.E.

Vice President, Special Projects

cc:

Mike Chambers

Mike Farrens

Randy Allen

Joey Stephenson

Callen Hurtt

Terry Burns

Dennis Plowman

Dil,

Os you con see, there isn't much control available. He faults shown are present in the Moncos + Ferron, but I'm not sure if all 3 of them penetrate the Marajo.

Call me if you have questions,

Sincorely,

Terry Burns

determined



JAN 1 6 1996

RIVER GAS CORPORATION

511 Energy Center Blvd.
Northport, Alabama 35476
Phone (205) 759-3282
Fax (205) 759-3188 (Accounting)
Fax (205) 758-5309 (Corporate)

January 11, 1996

Mr. Gil Hunt State of Utah Department of Natural Resources Division of Oil, Gas, and Mining 3 Triad Center, Suite 350 Salt Lake City, UT 84180-1203

RE: Utah D-3

Dear Mr. Hunt:

I believe you should have already received requirements: R649-5-2.2 and R649-5-2.11 for the Utah D-3 in a letter sent by Charles Willis on Jan. 9, 1996.

The following items may be added to the Utah D-3 injection application. The first enclosed requirement is R649-5-2.2.1. The second addition is a structure map fulfilling R649-5-2.2.10. As additional information is determined we it will be submitted as rapidly as possible.

If I may be of assistance please contact me.

Sincerely,

Callen Hurtt

Callen Wwett


cc:

Mike Chambers
Mike Farrens
Randy Allen
Charles Willis
Joey Stephenson
Terry Burns
Dennis Plowman

T 13 S R AMI BOUNDARY T 13 S WALLSTON IN +996 PRICE +796 T 14 S T 15 S +800 J +1600 0 -257 ₂₀ EMERY COUNTY T 16 S 1 14 n 17 RIVER GAS CORPORATION 19 GENERALIZED STRUCTURE MAP DATUM: TOP OF NAVAJO SANDSTONE R 9 E ⊼ 0< 00 00 ⊓ ⊓ α α '' 12/11/95

AM

BOUNDARY



River Gas Corporation

Proposed Well D-3

NW/SW, Section 18, T15S, R10E, SLM

Carbon County, Utah

Operators, Owners, Surface Owners Within 1/2 Mile Radius

TRACT 1

Surface Owner: School and Institutional Trust Lands Administration

Mineral Owner: School and Institutional Trust Lands Administration

all minerals

Oil & Gas Lease: ML-39865

Oil & Gas Lessee: River Gas Corporation, Texaco Exploration and

Production Inc., Dominion Reserves-Utah, Inc.

Coal Lease: ML-43170

Coal Lessee: Arjay Oil Company

Other Minerals Lessee: None

TRACT 2

Surface Owner: School and Institutional Trust Lands Administration

Mineral Owner: School and Institutional Trust Lands Administration

all minerals

Oil & Gas Lease: ML-45691

Oil & Gas Lessee: River Gas Corporation, Texaco Exploration and

Production Inc., Dominion Reserves-Utah, Inc.

Coal Lease: ML-43170

Coal Lessee: Arjay Oil Company

Other Minerals Lessee: None

TRACT 3

Surface Owner: United States of America

Mineral Owner: United States of America all minerals

Oil & Gas Lease: UTU-70219

Oil & Gas Lessee: River Gas Corporation, Texaco Exploration and

Production Inc.

Coal Lease: Not leased

Coal Lessee: Not applicable

Other Minerals Lessee: None

TRACT 4

Surface Owner: Carbon County

Mineral Owner: Carbon County mineral less oil and gas; United

States of America oil and gas only.

Oil & Gas Lease: UTU-72470

Oil & Gas Lessee: River Gas Corporation, Texaco Exploration and

Production Inc., Dominion Reserves-Utah, Inc.

Coal Lease: Not leased Coal Lessee: Not applicable

Other Minerals Lessee: None

TRACT 5

Surface Owner: United States of America

Mineral Owner: United States of America all minerals

Oil & Gas Lease: UTU-72470

Oil & Gas Lessee: River Gas Corporation, Texaco Exploration and

Production Inc.

Coal Lease: Not leased Coal Lessee: Not applicable

Other Minerals Lessee: None

TRACT 6

Surface Owner: Harvey Clayton Smith

Mineral Owner: Harvey Clayton Smith coal rights only; United

States of America oil and gas only; Carbon County

all other minerals

UTU-72377 Oil & Gas Lease:

Oil & Gas Lessee: River Gas Corporation, Texaco Exploration and

Production Inc., Dominion Reserves-Utah, Inc.

Coal Lease: Not leased

Coal Lessee: Not applicable

Other Minerals Lessee: None

TRACT 7

Surface Owner: Harvey Clayton Smith

Harvey Clayton Smith coal rights only; United Mineral Owner:

States of America oil and gas only; Carbon County

all other minerals

UTU-72470 Oil & Gas Lease:

Oil & Gas Lessee: River Gas Corporation, Texaco Exploration

Production Inc., Dominion Reserves-Utah, Inc.

Coal Lease: Not leased

Coal Lessee: Not applicable

Other Minerals Lessee: None

TRACT 8

School and Institutional Trust Lands Administration Surface Owner: Mineral Owner:

School and Institutional Trust Lands Administration

all minerals

ML-38666 Oil & Gas Lease:


Oil & Gas Lessee: River Gas Corporation, Texaco Exploration

Production Inc., Dominion Reserves-Utah, Inc.

ML-43171 Coal Lease:

Coal Lessee: Arjay Oil Company

Other Minerals Lessee: None





State of Utah Division of Oil, Gas & Mining (OGM)

ON-SITE PREDRILL EVALUATION AND REVIEW FOR APPLICATION FOR PERMIT TO DRILL (APD)

	RATOR:						
Riv	ver Gas Corporation						
WEL	L NO:		LEASE NO:				
Uta	ah D - 3		ML - 38666				
API	No:		LEASE TYPE:	ı			
43-	-007-30290		State X		Fee		
PRO	POSED LOCATION						
	1/4/1/4:	SECTION:	TOWNSHIP:	RANGE:			
	NW SW	18	15 S	10 E	·····		
	COUNTY:		FIELD:				
	Carbon		Drunkards Wash	(048)			
	SURFACE:						
	1.000 ECT 1126 FWI.						
	BOTTOM HOLE:		NAVA				
,	Same as above		<u> </u>	_			
	GPS COORDINATES:						
	<u>513009</u> E	<u>4374074</u> N		-			
SUR	FACE OWNER:						
	State of Utah						
SUF	RFACE AGREEMENT: Yes	X No	CONFIDENTIAL:	Yes 🗙	No		
T.OC	CATING AND SITING:						
	X UAC R649-2-3. Unit Drunkards Wash						
	UAC R649-3-2. General						
	UAC R649-3-3.						
	UCA 40-6-6.		Cause No.				
	OCN 40 0 0.						

DRILLING PROGRAM:

The following information is included in the Application for Permit to Drill submitted.

- 1. Surface Formation and Estimated Tops/Geologic Markers
- 2. Estimated Depths and Names of Anticipated Water, Oil, Gas or other Mineral Bearing Formations

(All fresh water sands encountered during drilling shall be recorded and reported to the Division on Form 7.)

- 3. Well Control Equipment & Testing Procedures
- 4. Proposed Casing and Cementing Program
- 5. Mud Program, Circulating Medium, and Monitoring equipment
- 6. Coring, Testing, and Logging Program
- 7. Expected Bottom Hole Pressures and any anticipated Abnormal Pressures, Temperatures or Potential Hazards such as hydrogen sulfide, expectations and contingency plans for mitigating identified hazards
- 8. Any other information relative to the proposed operation.

Onsite Participants:

Larry Jensen, Steve Prince, Billy Stacy, Randy Nairemore, Jim Thompson, Mike
Hebertson

Regional Setting/Topography:

This area is in the valley area of the East Central WASATCH Thrust Belt Uplift and the Northwest side of the San Rafael Swell. There are moderately incised stream channels, flat mesas with steep talus slopes and high sandstone cliffs.

SURFACE USE PLAN:

Current Surface Use: .Livestock grazing.

Proposed Surface Disturbance: Location and access road approximately 6.8 acres

- 1. Existing Roads <u>State Highway 10 south of Price, about three miles. West</u>
 <u>about 1 mile. The well is located on the south of the existing field road.</u>
- Planned Access Roads include length of new road, length of existing road to be upgraded, maximum disturbed and travel surface widths, maximum grades, turnouts, surface materials, drainage, cattleguards. The road will be about 175 feet long and run in a southerly direction from the main field access road.
- 3. Location of existing wells within one-mile radius of proposed location, include water, injection, producing, drilling with present status of each well See the attached map made part of the APD.
- 4. Location of Production Facilities and Pipelines see the map attached as part of the APD.
- 5. Location and Type of Water Supply (include Division of Water Rights approval or identifying number) City of Price
- 6. Source of Construction Material. Natural spoil and borrow from the location
- 7. Waste Management Plan. See the plan attached to the APD.
- 8. Ancillary Facilities. None
- 9. Well Site Layout. See the plat submitted as part of the APD.
- 10. Surface Restoration Plans. The surface will be restored as stipulated by the

 State of Utah at the time of abandonment.

ENVIRONMENTAL PARAMETERS:

Affected Floodplain and/or Wetlands:

A 404 dredge and fill permit may be required if this site is in or adjacent to a
wetland or other established drainage or floodplain. (Contact the Army Corps of
Engineers if there are concerns of this nature). Yes. See the attached letter from
the regional engineer. No permit required.

Flora/Fauna:

Briefly describe the flora found on the proposed site and the fauna evidenced or sighted on or near the proposed location. Deer, rabbits, coyote, cattle, possible raptor hunting area, cactus, greasewood, sagebrush.

SURFACE GEOLOGY

SURFACE GROUNDS
Soil Type and Characteristics: Clay and sand with possible gravel lenses.
boll Type and one of the second of the secon
Surface Formation & Characteristics: Mancos shale weathering to a light tan to
reddish brown. Degrades to clay with sand and gravel from the overlying sandstone.
Tenatell Mount Degrade 33 524
Erosion/Sedimentation/Stability: . A small tertiary drainage will be rerouted to
The south and joined with the main wash. The required cut will be about 10 feet
and will run along the west edge of the location.
Paleontological Potential Observed: None.
Paleontological rotential observed.

RESERVE PIT


Characteristics: 75 X 75 X 8 and will be placed on the East side of the location.
A second pit 220' X 220' will be used for emergency water production.
Lining (Site ranking form attached): A liner will be required.
OTHER OBSERVATIONS
Cultural Resources/Archaeology (if proposed location is on State land, has an
archaeology clearance been obtained?): The archaeology report has been filed.
Comments: The rerouted drainage was discussed and the position of the actual pad
was shifted 150 East and 200 feet North to give greater stability to the West side
of the location.

M. Hebertson & J. Thompson OGM Representative	Date and Time
W Hobowtson S. I. Thompson	6-Feb-1996 10;00 AM

STATEMENTS OF BASIS

OGM Review of Application for Permit to Drill (APD)

Company: River Gas Corporation Well Name: Utan D-3
ENGINEERING/LOCATING and SITING:
The proposed location meets the location and siting requirements of R649-2-3. The
application and proposed casing program, cementing program, drilling program.
blowout preventer and monitoring and cement engineering plans appear to be
consistent with accepted industry standards of practice and sound engineering
design. A casing design safety check is attached.
Signature: F. R. Matthews Date: 02/14/96
GEOLOGY/GROUND WATER:
The well is being drilled for injection of produced water. It will be spud in the
Cretaceous Mancos and be drilled through the Jurassic Kayenta Formation. The
proposed zone for injection is the Navajo Formation. Water of various quality may
be encountered in the Ferron Sandstone and the Kayenta, Formation. The proposed
casing and cement program will adequately protect any water encountered.
Signature: D. Jarvis Date: 2/14/96
SURFACE:
The onsite inspection was conducted in accordance with Division procedures. The
position of the pad was shifted to accommodate better stability on the west and
south sides of the location due to the proximity of the natural drainage system. A
berm will be placed at the base of the location pad to prevent runoff from the
location to the Natural drainage on the West and South of the pad. The access road
was changed from the northwest corner of the location to the northeast corner of
the location. A pit liner for the drilling pit will be required due to the nature
of the soils and produced fluids.
Signature: M.Hebertson and J. Thompson Date: 7-Feb-1996
STIPULATIONS for APD Approval:
1. The location will be shifted 200' North and 150 East, to accommodate the natural
Drainage system.
2. A berm will be constructed at the toe of the cut and fill slopes on the west and
south to prevent runoff from the location to the adjacent drainages.
3. The access road will enter location from the Northeast corner.
4. A liner will be required for the reserve pit.
ATTACHMENTS:
1. Photos will be placed on file.



Site-Specific Factors	Ranking Score	Final Ranking Score
		0
Distance to Groundwater		
(feet)		
>200	0	
100 to 200	5	
75 to 100	10	
25 to 75	15	
<25 or recharge area	20	
Distance to Surf. Water		10
(feet)		
>1000	0	
300 to 1000	2	
200 to 300	10	
100 to 200	15	
< 100	20	
Distance to Nearest		0
Municipal Well (feet)		
>5280	0	
1320 to 5280	5	
500 to 1320	10	
<500	20	
Distance to		10
Other Wells (feet)		
>1320	0	
300 to 1320	10	
<300 to 1320	20	
<300		
Native Soil Type		0
Low permeability	0	
Mod. permeability	10	
High permeability	20	

	1	
Fluid Type		o
Air/mist	0	_
Fresh Water	5	
TDS >5000 and <10000	10	
TDS >10000 or	15	
Oil Base Mud		
Fluid containing		
significant levels of	20	
hazardous constituents		
nazardous conscretenos		
Duill Cuttings		0
Drill Cuttings Normal Rock	o	
Normal Rock Salt or detrimental	10	
Sait or detrimental	10	
Annual Precipitation (inches)		0
<10		
10 to 20	o	
>20	5	
>20	10	
Affected Populations		0
<10	0	
10 to 30	6	
30 to 50	8	
>50 >50	10	
		10
Presence of Nearby		10
Utility Conduits		
Not Present	0	
Unknown	10	
Present	15	

The summation of all of the above ranking scores will yield one value which shall be used to determine the appropriate type of containment, on a case-by-case basis. The sensitivity levels are as follows:

Level I Sensitivity: For scores totaling ≥ 20

Level II Sensitivity: For scores totaling 15 to 19

Level III Sensitivity: For scores totaling <15

Containment Requirements According to Sensitivity Level

Level I: Requires total containment by synthetic liner, concrete structure or other type of total containment structure or material.

Level II: Bentonite or other compatible lining is discretionary depending on the fluid to be contained and environmental sensitivity.

Level III: No specific lining requirements.

OTHER GUIDELINES FOR PITS

- 1. Unlined pits shall not be constructed on areas of fill materials.
- A pit shall not be constructed in a drainages or floodplain of flowing or intermittent streams.
- 3. Synthetic liners used for lining reserve pits, shall be of 12 mil thickness or greater and shall be compatible with the fluid to be contained. Synthetic liners used for lining onsite pits with a longer expected life shall be a minimum of 30 mil thickness or as approved by the Division.
- 4. Synthetic liners shall be installed over smooth fill material which is free of pockets, loose rocks or other materials which could damage the liner.
- Monitoring systems for pits or closed mud systems may be required for drilling in sensitive areas.

DIVISION OF , GAS AND MINI		6. Lease Designation and Serial Number ML-38666
SUNDRY NOTICES AND REPORTS O		7. Indian Allottee or Tribe Name
Do not use this form for proposals to drill new wells; deepen existing wells; or to re Use APPLICATION FOR PERMIT—for such propo		8. Unit or Communitization Agreement
	Disposal Well	9. Well Name and Number Utah D-3
2. Name of Operator River Gas Corporation		Not yet assigned
3. Address of Operator 511 Energy Center Blvd. Northport, Al. 354 5. Location of Well	476 205-759-3282 2 19	11. Field and Pool, or Wildcat Drunkards Wash
Footage : 1600' FSL, 1126' FWL CC. Sec. T., R., M. : NW/SW Sec 18, T15S, R10E	State	
12. CHECK APPROPRIATE BOXES TO INDICATE NA		
NOTICE OF INTENT (Submit in Duplicate)	SUBSEC (Submit C	QUENT REPORT Original Form Only)
Abandonment New Construction Casing Repair Pull or Alter Casing Change of Plans Recompletion Conversion to Injection Shoot or Acidize Fracture Treat Vent or Flare Multiple Completion Water Shut-Off Other Revision of Surface Facility Layout Approximate Date Work Will Start ASAP	Abandonment Casing Repair Change of Plans Conversion to Injection Fracture Treat Other Date of Work Completion Report results of Multiple Completion WELL COMPLETION OR RECORD Must be accompanied by a treme	
13. DESCRISE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertin locations and measured and true vertical depths for all markers and zones pertin	ent details, and give pertinent dates. It	f well is directionally drilled, give subsurface
resultation and medicated and tide voltical deputs for an markets and zones pertur	ent to ans work.)	
14. I hereby centify that the foregoing is true and correct		
Name & Signature Terry D. Burns Long D. Burns	Title Geolog	ist Case 02-06-96
(State Use Crity) IRM pattheus Letholei	um Engmer	2/4/96

DEPARTMENT OF NATURAL RESOURCES

Injection Application

State of Utah #D-3 Well

R649-5-2.2.6

The source of the water to be injected will be the coalbed methane wells currently operated in the Drunkards Wash field by River Gas Corporation. The estimated amount of water to be injected daily will be submitted once well analysis has been conducted.

Ø 001

A Division of BJ Services

P.O. Box 217 Roosevelt, Utah 84086

Office (801) 722-5066 Fax (801) 722-5727

WATER ANALYSIS REPORT

COMPANY RIVER GAS		ADDRESS			DATE	1-17-9
SOURCE American Quasar	<u> </u>	DATE SAMPLED	1-16-96	ANALYSIS A		
31-01-DI Dispos	well Austra	ia .	Markinson	~~~~	CO	
1. PH	7.	6				
2. H _s S (Qualitative)	1.	0				
3. Specific Gravity	1.	004	,			
4. Dissolved Solids	•	· · ·	8,025			•
5. Buspended Bolids	0.7		•			
S. Annerobic Bucterial Count	GI	CA4				
7, Methyl Orange Alkelinity (CaCC	4)					
8. Bicarbonate (HCO _s)		HCCs	5,300	+61	87	HCOs
9. Chiorides (Ci)		a	3,500	+25.5	99	a
10. Sulfates (SC ₄)		80	0	+46	0	90,
11. Calcium (Ca)		~	64	+20	3	Ca
12. Magnesium (Mg)		Mg	22	+122_	2	Mg
12. Total Hardness (CeCO ₂)			250			
14. Total Iron (Fe)			4.1			
16. Barium (Qualitative)		******	·			
16. Phosphete Residuels		-				
'Milli equivalents per liter		•		-		

PROBABLE MINERAL COMPOSITION

		Compound	Marin. Wit.	X Mags	≥ · Moff
3 Ca 4	ноо 87	Ca(HCOs)s	81.04	3	243
		Ca9Q ₄	58.07		
2 Mg	50, 0	CaCle	56.50		
181 14	3 00	Mg(HCOs)s	72.17	2	146
202	99	MgSO.	60.19		
Saturation Values	Distilled Water 25°C	MgCl ₁	47.Æ		
CaCO ₂	13 Mg/1	NaHCOs	84.00	82	1,848
Ca60. • 2H60	2,090 Mg/l	New9Co	71.03	-	
MgCO ₈	103 Mg/I	NeCt	58.46	99	5,788
WARKS Resistivit	y = .88 ohms/ cm (71" 8			

CAL	
NATURE SAVER™ FAX MEMO 8181	6 Date 18 Au pages >
Calles Hur	Probable Craftee
Co./Dept.	C. 111
Phone # 116 CO 47	Pridne
Fax / 758-5269	Fax 1637-8624



RIVER GAS CORPORATION

511 Energy Center Blvd.
Northport, Alabama 35476
Phone (205) 759-3282
Fax (205) 759-3188 (Accounting)
Fax (205) 758-5309 (Corporate)

February 8, 1996

Mr. Gil Hunt State of Utah Department of Natural Resources Division of Oil, Gas, and Mining 3 Triad Center, Suite 350 Salt Lake City, UT 84180-1203

RE: Injection Application #D-3 Well

Dear Mr. Hunt:

Enclosed please find a schematic of the proposed D-3 casing program and a water analysis report as requested in your letter of Jan. 12, 1996.

I had hoped to be able to send along the affidavit of notice to owners and surface owners in the area at this time, but we have not completed the process. With luck I should be able to send that along sometime next week.

If I may be of assistance please do not hesitate to call.

Sincerely, Callen Hurt

Callen Hurtt

STATE OF UTAH, DIV OF OIL, GAS & MINERALS

Operator: RIVER GAS CORP | Well Name: UTAH D-3

Project ID: 43-007-30290 | Location: SEC. 18 - T15S - R10E

<u>Design Parameters:</u>

Design Factors:

: 1.125 Mud weight (8.33 ppg) : 0.433 psi/ft Collapse : 1.00 Burst Shut in surface pressure : 1844 psi : 1.80 Internal gradient (burst): 0.140 psi/ft 8 Round **(J)** Buttress : 1.60 (J) : 0.000 Annular gradient (burst) psi/ft : 1.50 (J) Other Tensile load is determined using air weight : 1.50 (B) Body Yield Service rating is "Sweet"

	Length (feet)	Size (in.)	Weight (lb/ft)	Grade	e Joi		Depth (feet)	Drift (in.)	Cost
1	6,300	7.000	26.00	K-5	5 ST&0	C	6,300	6.151	
	Load (psi)	Collapse Strgth (psi)		Burst Load (psi)	Min Int Strgth (psi)	Yield S.F.	Load (kips)	Tension Strgth (kips)	s.F.
1	2726	4320	1.585	2726	4980	1.83	163.80	364	2.22 J

Prepared by : MATTHEWS, Salt Lake City, Utah

Date : 02-14-1996

Remarks

Minimum segment length for the 6,300 foot well is 1,500 feet.

SICP is based on the ideal gas law, a gas gravity of 0.69, and a mean gas

temperature of 118°F (Surface 74°F , BHT 162°F & temp. gradient 1.400°/100 ft.)

String type: Production

The mud gradient and bottom hole pressures (for burst) are 0.433 psi/ft and

2,726 psi, respectively.

NOTE:

The design factors used in this casing string design are as shown above. As a general guideline, Lone Star Steel recommends using minimum design factors of 1.125 - collapse (with evacuated casing), 1.0 - (uniaxial) burst, 1.8 - API 8rd tension, 1.6 - buttress tension, 1.5 - body yield tension, and 1.6 - EUE 8rd tension. Collapse strength under axial tension was calculated based on the Westcott, Dunlop and Kemler curve. Engineering responsibility for use of this design will be that of the purchaser.

Costs for this design are based on a 1987 pricing model. (Version 1.07)

STATE OF UTAH, DIV OF OIL, GAS & MINERALS

Operator: RIVER GAS CORP | Well Name: UTAH D-3

Project ID: | Location: SEC. 18 - T15S - R10E

Design Factors: Design Parameters: : 1.125 Collapse Mud weight (8.33 ppg) : 0.433 psi/ft : 1.00 Burst psi Shut in surface pressure : 2533 8 Round : 1.80 (J) Internal gradient (burst): 0.065 psi/ft : 1.60 (J) Buttress Annular gradient (burst) : 0.000 psi/ft : 1.50 (J) Other Tensile load is determined using air weight : 1.50 (B) Body Yield Service rating is "Sweet"

	Length (feet)	Size (in.)	Weight (lb/ft)	Grade	e Joir		Depth (feet)	Drift (in.)	Cost
1	3,500	9.625	36.00	J-5!	5 ST&C	>	3,500	8.765	
	Load (psi)	Collapse Strgth (psi)	S.F.	Burst Load (psi)	Min Int Strgth (psi)	Yield S.F.	Load	Tension Strgth (kips)	S.F.
1	1515	2020	1.333	2762	3520	1.27	126.00	394	3.13 J

Prepared by : MATTHEWS, Salt Lake City, Utah

Date : 02-14-1996

Remarks

Minimum segment length for the 3,500 foot well is 1,500 feet.

SICP is based on the ideal gas law, a gas gravity of 0.69, and a mean gas

temperature of 118°F (Surface 74°F , BHT 162°F & temp. gradient 1.400°/100 ft.)

String type: Intermediate - Drlg

Next string will set at 6,300 ft. with 9.00 ppg mud (pore pressure of 2,945

psi.) The frac gradient of 1.000 psi/ft at 3,500 feet results in an injection

pressure of 3,500 psi Effective BHP (for burst) is 2,762 psi.

The minimum specified drift diameter is 8.750 in.

NOTE:

The design factors used in this casing string design are as shown above. As a general guideline, Lone Star Steel recommends using minimum design factors of 1.125 - collapse (with evacuated casing), 1.0 - (uniaxial) burst, 1.8 - API 8rd tension, 1.6 - buttress tension, 1.5 - body yield tension, and 1.6 - EUE 8rd tension. Collapse strength under axial tension was calculated based on the Westcott, Dunlop and Kemler curve. Engineering responsibility for use of this design will be that of the purchaser.

Costs for this design are based on a 1987 pricing model. (Version 1.07)


RIVER GAS CORP. DRUNKARD'S WASH D-3 WEL

Figure 5206 shows the base of an upper anhydrite and the top of a chaotic zone below, which has the borehole broke out beyond caliper determination, and therefore unreliable FMI images.

object is out of range

Image from Flip

Set Manipulation



Overview

Stereonet


Fracture Logs


Read Dips

RIVER GAS CORP. DRUNKARD'S WASH D-3 WEL

Figure 5254 shows a somewhat near gauge interval below the broke-out and chaotic zone above. Large fracture gashes appear in the NE and SW portions and E and W portions of the hole which may not correspond to the same fractures. If they did, they would fit parallel NE-SW a striking fracture trend, which is consistent with the overall trend. On the continuous printout, rough fracture fits can be seen that approximate the NE-SW striking model. One posted at 5252 feet is a dip of 84 @ 160. Another posted at 5263.8 feet fits 78 @ 164 and just below 74 @ 203 degrees. An unpicked one bottoming at 5270 feet in another anhydrite suggests south dips and E-W strikes.

LOG EXPERTS Page No. 54







DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt Governor Ted Stewart Executive Director James W. Carter Division Director 801-359-3940 (Fax) 801-538-5319 (TDD)

355 West North Temple 3 Triad Center, Suite 350 Salt Lake City, Utah 84180-1203 801-538-5340 801-359-3940 (Fax)

February 14, 1996

River Gas Corporation 511 Energy Center Blv. Northport, Alabama 35476

Utah D-3 Well, 1600' FSL, 1126' FWL, NW SW, Sec. 18, T. 15 S., R. 10 E., Re:

Carbon County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. 40-6-1 et seq., Utah Administrative Code R649-3-1 et seq., and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-007-30290.

Sincerely,

Associate Director

lwp

Enclosures

Carbon County Assessor

Bureau of Land Management, Moab District Office

WAPD



Operator:		River Gas Corpotation							
Well Name &	<u>Utah D-3</u> 43-007-30290								
API Number:									
Lease:	ML-38666								
Location:	NW SW	_ Sec	18	_ T	15 S.	_ R	10 E.		

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for Permit to Drill.

2. Notification Requirements

Notify the Division within 24 hours following spudding the well or commencing drilling operations. Contact Jimmie Thompson at (801)538-5340.

Notify the Division prior to commencing operations to plug and abandon the well. Contact Frank Matthews or Mike Hebertson at (801)538-5340.


3. Reporting Requirements

All required reports, forms and submittals shall be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. On-site Predrill Evaluation and Review

Compliance with all requirements and stipulations developed during the onsite evaluation and review.

RIVER GAS CORPORATION UTAH D-3 INJECTION WELL CARBON COUNTY UAC R649-2-3




SPACING: UAC R649-2-3 PREPARED: DATE: 16-FEB-96

·	DEPARTMENT (OF NATURAL RES	OURCES	6. Lease Designation and Serial Number
4 2	DIVISION OF	GAS AND	MINING	ML 38666
·		V		7. Indian Allottee or Tribe Name
S	UNDRY NOTICES	AND REPORT	TS ON WELLS	
			ir to reenter plugged and abandoned w	elts. 8. Unit or Communitization Agreement
	Use APPLICATION F	OR PERMIT— for such	proposals	
				UTU67921X
1. Type of Well Oil Well	☐ Gas 🙀	Other (specify)	tor Dianogol Holl	9. Well Name and Number
2. Name of Operator	— Well — A	wa	ter Disposal Well	Utah D-3 43-007-36
River Gas Co	rporation			Not yet assigned
3. Address of Operator			4. Telephone Number	11. Field and Pool, or Wildcat
	Center Blvd.; Nort	hport, AL 354	76 (205) 759–3282	Drunkards Wash
5. Location of Well				
Footage	: 1600' FSL & 11	26' FWL	Cou	unty: Carbon
QQ, Sec, T., R., M.	<u></u>	·		te : UTAH
12. CHEC	NOTICE OF INTENT		ENATURE OF NOTICE RE	
	(Submit in Duplicate)		SUE (Sub	SEQUENT REPORT mit Original Form Only)
Abandonment	☐ New	Construction	Abandonment * .	
Casing Repair		or Alter Casing	Casing Repair	Pull or Alter Casing
Change of Plan	· 🗀	mpletion	Change of Plans	Shoot or Acidize
Conversion to	٠ ا	t or Acidize	Conversion to Injection	n Vent or Flare
Fracture Treat		or Flare	Fracture Treat	☐ Water Shut-Off
Multiple Comp		r Shut-Off	Other	
X Other <u>Revi</u>	sion of Casing De	sign	Date of Work Completion	
Approximate Date	Work Will Start ASAP		Date of Work Completion	
			Report results of Multiple Com	pletions and Recompletions to different reservoirs
			on WELL COMPLETION OR R	ECOMPLETION AND LOG form.
13 DESCRIBE PROPOS	SED OR COMPLETED OPERAT	IONS (Classly state all		tes. If well is directionally drilled, give subsurface
locations and measu	red and true vertical depths for	all markers and zones	pertinent details, and give pertinent da pertinent to this work.)	tes. It well is directionally drilled, give subsurface
Attached is	a copy of the sch	ematic of the	revised well casing d	esion (
1100001100 110	a copy of the bene	emacic of the	revised well easing d	cordi.
REVICED CEMEN	NTING PROGRAM:			
KEVISED CEREI	ATTING TROGRAM.			
Hole Size	Casing Size	Wght/ft	Setting Depth	Cement Quantity (est.)
17 1/2"	13 3/8"	48 1bs	500'	380 sx Class G, 15.8ppg
12 1/4"	9 5/8"	36 lbs	3500 '	280 sx Hi-Lift, 11 ppg plus
0 - 1/11	_,,			100 sx Class G, 15.8 ppg
8 3/4"	7"	26 1bs	6300 '	Stage 1(bottom): 225 sx
				50/50 Poz, 12.5 ppg, and
				100 sx RFC, 14.2 ppg
				Stage 2 (Top): 190 sx 50/50 Poz, 100sx RFC
			П.Б. 1 9 1996	102, 1005X RFC
•				
14. I hereby certily that the	e foregoing is true and correct	7.		
Name & Signature Det	ania Plarman	\mathcal{M}_{-}		erroim Toohmisiss 00/00/00
Traine & Signature DET	mis Flowman Wy	nns / re	ruman Title Keser	cvoir Technician _{Oate} 02/08/96

(State Use Cnly)

PROPOSED DISPOSAL WELL D-3

SEC. 18, T 15 S, R 10 E (1600' FSL, 1126 FWL) CARBON COUNTY, UTAH





RIVER GAS CORPORATION

511 Energy Center Blvd.
Northport, Alabama 35476
Phone (205) 759-3282
Fax (205) 759-3188 (Accounting)
Fax (205) 758-5309 (Corporate)

February 14, 1996

Mr. Gil Hunt State of Utah Department of Natural Resources Division of Oil, Gas, and Mining 3 Triad Center, Suite 350 Salt Lake City, UT 84180-1203

RE: Injection Application D-3 Well

Dear Mr. Hunt:

Enclosed please find the affidavit of notice to owners and surface owners in the area of the D-3 well. I believe the affidavit is the last item required to proceed with the public notice for this application.

If any previously submitted item is insufficient in any way I would be happy to supplement what we have supplied to you.

Please do not hesitate to call if I may be of any assistance .

Sincerely,

Callen Hurtt

Callen Hurth

STATE OF ALABAMA) :ss.
COUNTY OF TUSCALOOSA)

AFFIDAVIT OF NOTIFICATIONS MAILED REGARDING PROPOSED DRILLING OF A WELL AND TESTING FOR POSSIBLE USE AS AN INJECTION WELL

JOSEPH L. STEPHENSON, being first duly sworn upon his oath, deposes and states:

- 1. I am Vice President Land of River Gas Corporation ("RGC"), an Alabama corporation duly authorized to transact business in the State of Utah, and am authorized to execute this Affidavit on behalf of said corporation.
- 2. As Vice President Land, I am responsible for supervision of lease records, reviewing title records and legal opinions affecting lands where RGC proposes to conduct operations, and providing notice to certain parties that may be affected by proposed operations.
- 3. RGC proposes to drill a well on land owned by Utah's School and Institutional Trust Lands Administration in the NW1/4 of SW1/4 of Section 18, T15S, R10E, SLM, Carbon County, Utah. Upon completion of drilling the well, tests will be conducted to determine if the well can be utilized as an injection (water disposal) well.
- 4. Attached hereto as EXHIBIT "A" is a map showing the location of the proposed well, a 1/2 mile radius drawn around the proposed well, and the identification of ownership of the tracts within that 1/2 mile radius.
- 5. Attached hereto as EXHIBIT "B" is a listing of parties that received notice of the permit application which RGC submitted to the Division of Oil, Gas and Mining ("DOGM"), such notice sent by certified mail return receipt, receipt of such notice being evidenced on return receipt cards. The letters sent to the parties on said list identified the tract(s) within the 1/2 mile radius of the proposed well in which said party owned an interest, the purpose of RGC drilling the well was stated, a copy of the Application for Injection Well was provided, the address and telephone number for the DOGM was provided in the event the party had a question on the permitting of the well, and RGC offered to provide said parties with additional information associated with the Application for Injection Well if the party made a written request to RGC.
- 6. The matters stated herein are true of my own knowledge, except to any matters stated herein upon information and belief, and, as to those matters, I believe them to be true.

DATED this 14th day of February, 1996.

SEPH L. STEPHENSON

Subscribed, sworn and acknowledged to and by Joseph L. Stephenson before me this 14th day of February, 1996.

NOTARY PUBLIC Residing at:

1429 20th Avenue East Tuscaloosa, AL 35404

(SEAL)

My Commission Expires: 3/8/98




EXHIBIT "A" Page 2 of 4

River Gas Corporation Proposed Well D-3 NW/SW, Section 18, T15S, R10E, SLM Carbon County, Utah

Operators, Owners, Surface Owners Within 1/2 Mile Radius

TRACT 1

Surface Owner: School and Institutional Trust Lands Administration

Mineral Owner: School and Institutional Trust Lands Administration

all minerals

Oil & Gas Lease: ML-39865

Oil & Gas Lessee: River Gas Corporation, Texaco Exploration and

Production Inc., Dominion Reserves-Utah, Inc.

Coal Lease: ML-43170

Coal Lessee: Arjay Oil Company Other Minerals Lessee: None of record

Grazing Permittee: Steve Stamatakis, et al (GP-21727)

Oil & Gas Operator: River Gas Corporation

TRACT 2

Surface Owner: School and Institutional Trust Lands Administration

Mineral Owner: School and Institutional Trust Lands Administration

all minerals

Oil & Gas Lease: ML-45691

Oil & Gas Lessee: River Gas Corporation, Texaco Exploration and

Production Inc., Dominion Reserves-Utah, Inc.

Coal Lease: ML-43170

Coal Lessee: Arjay Oil Company
Other Minerals Lessee: None of record

Other Minerals Lessee: None of record

Grazing Permittee: Boyd Marsing (GP-21308)
Oil & Gas Operator: River Gas Corporation

TRACT 3

Surface Owner: United States of America

Mineral Owner: United States of America all minerals

Oil & Gas Lease: UTU-70219

Oil & Gas Lessee: River Gas Corporation, Texaco Exploration and

Production Inc.

Coal Lease: Not leased
Coal Lessee: Not applicable
Other Minerals Lessee: None of record

Grazing Permittee: None of record

Oil & Gas Operator: River Gas Corporation

EXHIBIT "A" Page 3 of 4

TRACT 4

Surface Owner: Carbon County

Mineral Owner: Carbon County mineral less oil and gas; United

States of America oil and gas only.

Oil & Gas Lease: UTU-72470

Oil & Gas Lessee: River Gas Corporation, Texaco Exploration

Production Inc., Dominion Reserves-Utah, Inc.

Coal Lease: Not leased Coal Lessee: Not applicable

None of record Other Minerals Lessee: Grazing Permittee: None of record

Oil & Gas Operator: River Gas Corporation

TRACT 5

Surface Owner: United States of America

Mineral Owner: United States of America all minerals

UTU-72470 Oil & Gas Lease:

Oil & Gas Lessee: River Gas Corporation, Texaco Exploration and

Production Inc.

Coal Lease: Not leased Coal Lessee: Not applicable None of record Other Minerals Lessee:

Grazing Permittee: None of record

Oil & Gas Operator: River Gas Corporation

TRACT 6

Surface Owner: Harvey Clayton Smith

Harvey Clayton Smith coal rights only; United Mineral Owner:

States of America oil and gas only; Carbon County

all other minerals

Oil & Gas Lease: UTU-72377

Oil & Gas Lessee: River Gas Corporation, Texaco Exploration and

Production Inc., Dominion Reserves-Utah, Inc.

Coal Lease: Not leased Not applicable Coal Lessee: None of record

Other Minerals Lessee: Grazing Permittee: None of record

Oil & Gas Operator: River Gas Corporation

EXHIBIT "A" Page 4 of 4

TRACT 7

Surface Owner: Harvey Clayton Smith

Mineral Owner: Harvey Clayton Smith coal rights only; United

States of America oil and gas only; Carbon County

all other minerals

Oil & Gas Lease: UTU-72470

Texaco Exploration Oil & Gas Lessee: River Gas Corporation,

Production Inc., Dominion Reserves-Utah, Inc.

Coal Lease: Not leased

Coal Lessee: Not applicable None of record Other Minerals Lessee: None of record Grazing Permittee:

Oil & Gas Operator: River Gas Corporation

TRACT 8

Surface Owner: School and Institutional Trust Lands Administration Mineral Owner:

School and Institutional Trust Lands Administration

all minerals

Oil & Gas Lease: ML-38666


Oil & Gas Lessee: River Gas Corporation, Texaco Exploration

Production Inc., Dominion Reserves-Utah, Inc.

Coal Lease: ML-43171

Coal Lessee: Arjay Oil Company None of record Other Minerals Lessee:

Boyd Marsing (GP-22930) Grazing Permittee: River Gas Corporation Oil & Gas Operator:



River Gas Corporation Proposed Well D-3 NW/SW, Section 18, T15S, R10E, SLM Carbon County, Utah Notification to Parties Within 1/2 Mile Radius Page 1 of 2

Arjay Oil Company

ATTENTION: Mr. R. J. Hollberg, Jr.

President

P. O. Box 904

Salt Lake City, UT 84110

LETTER DATED JANUARY 12, 1996 RECEIVED: 1/26/96

CERTIFIED MAIL P-521-852-893

Carbon County

ATTENTION: Carbon County Commission

Carbon County Courthouse

100 East Main Street

Price, UT 84501

CERTIFIED MAIL P-521-852-894 LETTER DATED JANUARY 12, 1996 RECEIVED: 1/24/96

Mr. Boyd Marsing P. O. Box 806 Price, UT 84501

Dominion Reserves-Utah, Inc.

ATTENTION: Mr. G. E. Lake, Jr. Vice President

Riverfront Plaza, West Tower

901 E. Byrd Street Richmond, VA 23261

CERTIFIED MAIL P 521 852 717 LETTER DATED JANUARY 24, 1996 RECEIVED: 1/29/96

CERTIFIED MAIL P-521-852-895 LETTER DATED JANUARY 12, 1996

RECEIVED: 1/22/96

River Gas Corporation

ATTENTION: Joseph L. Stephenson

Vice President - Land 511 Energy Center Blvd.

Northport, AL 35476

NOT APPLICABLE...RGC ORIGINATED NOTICES TO THE

OTHER PARTIES

Harvey Clayton Smith 3570 South 3310 West

Salt Lake City, UT 84119

Mr. Steve Stamatakis 2676 Gordon Creek Road

Price, UT 84501

CERTIFIED MAIL P-521-852-892 LETTER DATED JANUARY 12, 1996 RECEIVED: 1/24/96

CERTIFIED MAIL P 521 852 718 LETTER DATED JANUARY 24, 1996

RECEIVED: 1/29/96

Texaco Exploration and Production Inc.

ATTENTION: Mr. J. R. French, Jr.

Denver Division P. O. Box 2100

Denver, CO 80201

CERTIFIED MAIL P-521-852-712 LETTER DATED JANUARY 12, 1996

RECEIVED: 1/22/96

Exhibit Prepared by:

EXHIBIT "B" Page 2 of 2

River Gas Corporation
Proposed Well D-3
NW/SW, Section 18, T15S, R10E, SLM
Carbon County, Utah
Notification to Parties Within 1/2 Mile Radius
Page 2 of 2

United States of America U. S. Department of the Interior Bureau of Land Management Moab District Office P. O. Box 970 Moab, UT 84532

CERTIFIED MAIL P-521-852-713 LETTER DATED JANUARY 12, 1996 RECEIVED: 1/24/96

United States of America
U. S. Department of the Interior
Bureau of Land Management
Price Resource Area
900 North 700 East
Price, UT 84501

CERTIFIED MAIL P-521-852-714 LETTER DATED JANUARY 12, 1996 RECEIVED: 1/24/96

United States of America U. S. Department of the Interior Bureau of Land Management 324 South State, Suite 301 Salt Lake City, UT 84111-2303 CERTIFIED MAIL P-521-852-715 LETTER DATED JANUARY 12, 1996 RECEIVED: 1/25/96

Utah School and Institutional Trust Lands Administration ATTENTION: Mr. Edward W. Bonner Mineral Resources Specialist 3 Triad Center, Suite 400 355 West North Temple Salt Lake City, UT 84180-1204 CERTIFIED MAIL P-521-852-716 LETTER DATED JANUARY 12, 1996 RECEIVED: 1/24/96

BEFORE THE DIVISION OF OIL, GAS AND MINING DEPARTMENT OF NATURAL RESOURCES STATE OF UTAH

---00000---

IN THE MATTER OF THE
APPLICATION OF RIVER GAS
CORPORATION FOR
ADMINISTRATIVE APPROVAL OF
THE D-3 WELL LOCATED IN

.

ACTION

ADMINISTRATIVE APPROVAL OF THE D-3 WELL LOCATED IN SECTION 18, TOWNSHIP 15 SOUTH, RANGE 10 EAST, S.L.M., CARBON COUNTY, UTAH, AS A CLASS II INJECTION WELL CAUSE NO. UIC-166

NOTICE OF AGENCY

---ooOoo---

THE STATE OF UTAH TO ALL PERSONS INTERESTED IN THE ABOVE ENTITLED MATTER.

Notice is hereby given that the Division of Oil, Gas and Mining (the "Division") is commencing an informal adjudicative proceeding to consider the application of River Gas Corporation for administrative approval of the D-3 well, to be drilled in Section 18, Township 15 South, Range 10 East, Carbon County, Utah, for conversion to a Class II injection well. The proceeding will be conducted in accordance with Utah Admin. R.649-10, Administrative Procedures.

The estimated injection intervals from 4300 feet to 5000 feet (Entrada Formation) and from 5600 feet to 6100 feet (Navajo Formation) will be selectively perforated and tested prior to water injection. The maximum injection pressure and rate will be determined by step rate testing after completion of the well.

Any person desiring to object to the application or otherwise intervene in the proceeding, must file a written protest or notice of intervention with the Division within fifteen days following publication of this notice. If such a protest or notice of intervention is received, a hearing will be scheduled before the Board of Oil, Gas and Mining. Protestants and/or intervenors should be prepared to demonstrate at the hearing how this matter affects their interests.

Dated this 21st day of February 1996.

STATE OF UTAH

DIVISION OF OIL, GAS & MINING

Associate Director, Oil & Gas



DIVISION OF OIL, GAS AND MINING

Ted Stewart **Executive Director** James W. Carter Division Director 801-538-5319 (TDD)

355 West North Temple 3 Triad Center, Suite 350 Salt Lake City, Utah 84180-1203 801-538-5340 801-359-3940 (Fax)

February 21, 1996

Newspaper Agency Corporation Legal Advertising Tribune Building, Front Counter 143 South Main Salt Lake City, Utah 84111

Notice of Agency Action - Cause No. UIC-166 Re:

Gentlemen:

Enclosed is a copy of the referenced Notice of Agency Action. Please publish the Notice, once only, as soon as possible. Please send proof of publication and billing to the Division of Oil, Gas and Mining, 355 West North Temple, 3 Triad Center, Suite 350, Salt Lake City, Utah 84180-1203.

Sincerely,

Lisha Cordova

Administrative Analyst

Enclosure





State of Utah DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt Governor Ted Stewart Executive Director James W. Carter Division Director 355 West North Temple 3 Triad Center, Suite 350 Salt Lake City, Utah 84180-1203 801-538-5340 801-359-3940 (Fax) 801-538-5319 (TDD)

February 21, 1996

Sun Advocate P. O. Box 870 76 West Main Price, Utah 84501

Re:

Notice of Agency Action - Cause No. UIC-166

Gentlemen:

Enclosed is a copy of the referenced Notice of Agency Action. Please publish the Notice, once only, as soon as possible. Please send proof of publication and billing to the Division of Oil, Gas and Mining, 355 West North Temple, 3 Triad Center, Suite 350, Salt Lake City, Utah 84180-1203.

Sincerely,

Lisha Cordova

Administrative Analyst

Lisha Cordova

Enclosure



River Gas Corporation D-3 Well Cause No. UIC-166

Publication Notices were sent to the following:

Newspaper Agency Corporation Legal Advertising Tribune Building, Front Counter 143 South Main Salt Lake City, Utah 84111

Sun Advocate
P. O. Box 870
76 West Main
Price, Utah 84501

Bureau of Land Management P. O. Box 7004 125 South 600 West Price, Utah 84501

River Gas Corporation 511 Energy Center Boulevard Northport, Alabama 35476


U.S. Environmental Protection Agency Region VIII Attn. Dan Jackson 999 18th Street Denver, Colorado 80202-2466

Ed Bonner School & Institutional Trust Lands Administration 3 Triad Center, Suite 400 Salt Lake City, Utah 84180-1203

Lisha Cordova

Administrative Analyst

February 21, 1996



143 SOUTH MAIN ST. P.O. BOX 45838 SALT LAKE CITY, UTAH 84145 FED. TAX I.D. # 87-0217663

CUSTOMER'S COPY

PROOF OF PUBLICATION

ACCOUNT NAME

CUSTOMER NAME AND ADDRESS	ACCOUNT NUMBER	
DIV OF OIL, GAS & MINING	D5385340L-07	02/27/96
355 WEST NORTH TEMPLE 3 TRIAD CENTER #350 SLC. UT 84180		
510,		

	DIV OF OIL, GAS & MINING					
	TELEPHONE	INVOICE NUMBER				
	801-538-5340 TL2N8200861					
	SCI	HEDULE				
	START 02/27/96	END 02/27/96				
NOTICE OF AGENCY ACTION CAUSE NO. UIC-166 BEFORE THE DIVISION OF OIL,		REF. NO.				
CAUSE NO. UIC-166 BEFORE THE DIVISION OF OIL, GAS AND MINING DEPARTMENT OF NATURAL RESOURCES, STATE OF UTAH	U.	rc-166				
IN THE MATTER OF THE APPLICA- TION OF RIVER GAS CORPORA- TION FOR ADMINISTRATIVE AP- PROVAL OF THE D-3 WELL LOCATED IN SECTION 18, TOWN- SHIP 15 SOUTH, RANGE 40 EAST, S.L.M., CARBON COUNTY, UTAH, AS A CLASS II INJECTION WELL	CA	PTION				
PROVAL OF THE D-3 WELL LOCATED IN SECTION 18, TOWN- SHIP 15 SOUTH, RANGE 10 EAST,	NOTICE OF AGENCY ACTIONCAUSE N					
AS A CLASS II INJECTION WELL		SIZE				
THE STATE OF UTAH TO ALL PER- SONS INTERESTED IN THE ABOVE ENTITLED MATTER.	74 LINES	1.00 COLUMN				
Notice is hereby given that the Division of Oil, Gas and Min-ing (the "Division") is commencing an informal adjudicative proceeding to consider the application of River Gas Corporation for administrative approval	TIMES	RATE				
ing an informal adjudicative proceeding to consider the ap- plication of River Gas Corpora-	1	1.64				
tion for administrative approval- of the D-3 well, to be drilled in Section 18, Township 15 South, Range 10 East, Carbon County, Utah, for conversion to a Class II injection well. The proceeding will be conducted in accor- dance with Utah Admin. R.649-	MISC. CHARGES	AD CHARGES				
Utah, for conversion to a Class II injection well. The proceeding will be conducted in accor-	.00	121.36				
10, Administrativo i rocciacios.		TOTAL COST				
The estimated injection intervals from 4300 feet to 5000 feet (Entrada Formation) and from 5500 feet to 6400 feet (Navalo		121.36				
vals from 4300 feet to 5000 feet (Entrada Formation) and from 5600 feet to 6100 feet (Navalo Formation) will be selectively perforated and tested prior to water injection. The maximum injection pressure and rate will be determined by step rate testing after completion of the well.	AFFIDAV	/IT OF PUBLICATION				
well.	TOTAL BOUNDARY CONTONION	TECAT POORVERDED T CERTIFY THA				

AFFIDAVIT OF PUBLICATION

well. WSPAPER AGENCY	CORPORATION LEGAL BOOKKEEPE	R, I CERTIFY THAT THE ATTACHED
Any persons desiring to ob-	OTICE OF AGENCY ACTIONCAUSE N	FOR
wise intervene in the proceed. ITS EMENT OF ing, must file a written protest or notice of intervention with the	GAS & MINING WAS PUB	LISHED BY THE NEWSPAPER AGENCY
Division within fifteen days fol- lowing publication of this no-RATION, AGENT	FOR THE SALT LAKE TRIBUNE AN	LISHED BY THE NEWSPAPER AGENCY D DESERET NEWS, DAILY NEWSPAPERS RCULATION IN UTAH. AND PUBLISHED
	LISH LANGUAGE WITH GENERAL CI	RCULATION IN UTAH, AND PUBLISHED
Mining Protestants and/or in-	SALT LAKE COUNTY IN THE STAT	E OF UTAH.
terests.	START 02/27/96 END 02/27/	96
DATED this 21st day of February, 1996.	Dine Roner	
STATE OF UTAH DIVISION OF OIL, GAS AND MINING R. J. First Absolute Director Oil and Gas		En landario Esta de Santo de la companya del companya del companya de la companya

หาง. กเก Associate Director, Oil and Gas 2N820080

Constant looked besidest, 1996 State of Utah THIS IS NOT A STATEMENT BUT A "PROOF OF PUBLICATION" PLEASE PAY FROM BILLING STATEMENT.

STATE OF UTAH)

SS.

County of Carbon,)

I, Kevin Ashby, on oath, say that I am the Publisher of the Sun Advocate, a twice-weekly newspaper of general circulation, published at Price, State and County aforesaid, and that a certain notice, a true copy of which is hereto attached, was published in the full issue of such newspaper for 1 (One) consecutive issues, and that the first publication was on the 27th day of February, 1996 and that the last publication of such notice was in the issue of such newspaper dated the 27th day of February, 1996.

win Hor Kevin Ashby - Publisher

Subscribed and sworn to before me this 27th day of February, 1996.

Notary Public My commission expries January 10, 1999 Residing at Price, Utah

Zinda Theyn

Publication fee, \$57.10



NOTICE OF AGENCY ACTION CAUSE NO. UIC-166

BEFORE THE DIVISION OF OIL, GAS AND MINING DEPARTMENT OF NATURAL RESOURCES STATE OF UTAH

IN THE MATTER OF THE APPLICATION OF RIVER GAS CORPORA-TION FOR ADMINISTRATIVE APPROVAL OF THE D.3 WELL LOCATED IN SECTION 18, TOWNSHIP 15 SOUTH, RANGE 10 EAST, S.L.M., CARBON COUNTY, UTAH, AS A CLASS II INJECTION WELL THE STATE OF UTAH TO ALL PERSONS INTERESTED IN THE ABOVE ENTITLED MATTER.

Notice is hereby given that the Division of Oil, Gas and Mining (the "Division") is commencing an informal adjudicative proceeding to consider the application of River Gas Corporation for administrative approval of the D-3 well, to be drilled in Section 18, Township 15 South, Range 10 East, Carbon County, Utah, for conversion to a Class II injection well. The proceeding will be conducted in accordance with Utah Admin. R.649-10, Administrative Procedures.

The estimated injection intervals from 4300 feet to 5000 feet (Entrada Formation) and from 5,600 feet to 6,100 feet (Navajo Formation) will be selectively perforated and tested prior to water injection. The maximum injection pressure and rate will be determined by step rate testing after completion of the well.

Any person desiring to object to the application or otherwise intervene in the proceeding, must file a written protest or notice of intervention with the Division within fifteen days following publication of this notice. If such a protest or notice of intervention is received, a hearing will be scheduled before the Board of Oil, Gas and Mining. Protestants and/or intervenors should be prepared to demonstrate at the hearing how this matter affects their interests.

Dated this 21st day of February 1996.

STATE OF UTAH DIVISION OF OIL, GAS & MINING -s-R. J. Firth

Associate Director, Oil & Gas

Published in the Sun Advocate February 27, 1996.

2871 pec Ged 6 pluad bonts

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

Name of Company: RIVER GAS CORP
Well Name: <u>UTAH D-3</u>
Api No. 43-007-30290
Section 18 Township 15S Range 10E County CARBON
Drilling Contractor <u>CAZA</u>
Rig #
SPUDDED:Date 2/27/96
Time
How_ROTARY
Drilling will commence
Reported by GREG MUELLER
Telephone # 1-801-637-8876
Date: <u>2/28/96</u> Signed: <u>MKH</u>

F UTAH DIVISION OF OIL, GAS AND MINING Learn Designation and Secial Number: ML - 38666 & Windian Allabor of Tribe Name: SUNDRY NOTICES AND REPORTS ON WELLS 7. Unit Agreement Name: Do not use this form for proposals to drill turn wells, deopen existing wells, or to reenter proposals and abandoned wells Use APPLICATION FOR PERMIT TO DRILL, OR DEEPEN form for such proposals. UFU67921X a. Was Name and Number. 1. Type of Well: OIL GAS OTHER: Disposal Well UTAH e. API Well Number: 2. Name of Coemics: 43-007-30290 River Gas Corporation 10. Field and Pool, or Wildcatt 3. Address and Taleshone Number: DRUNKARDS WASH 511 Energy Center Boulevard a. Location of Well COUNTY: CARBON 1600' FSL, 1126' FWL Fixtures: ос, в_{уг.}т.,в.м.: Sec., 18, Т15S, R10E UTAH CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA 11 SUBSEQUENT REPORT NOTICE OF INTENT (Submit Original Form Only) (Submit in Dunileute) . | New Construction. ☐ Abandonment ☐ Abandonment Mew Construction ☐ Casing Repair Pull or Alter Casing Casing Repair Pull or Alter Casing Shoot or Acidize Change of Plans Change of Plans ☐ Recompletion Conversion to injection ☐ Shoot or Acidize Conversion to injection ∨ Vent or Flare Fracture Treat ☑ Vent or Flare Fracture Treat ☐ Water Shut-Off Multiple Completion ☐ Water Shut-Off Other Change in RAP (see Below Other Date of work completion ___ Current Approximate date work will start COMPLETION OR RECOMPLETION AND LOG form Must be accompanied by a cement verification report. 12. DESCRIBE PROPOSED OF COMPLETED OPERATIONS (Clearly state all pertinent datase, and give pertinent datase, if well in directionally dillied, give substatuse locations and measured and true riscal depths for all markers and zones pelitinent to this work.) After surface casing is set, (500') we propose to nipple-up a Class 2 AG type BOP with a spacer spool. This BOP will consist of a 13-5/8" - 2000# annular and 13-5/8" - 2000# rotating head. From past records, we have not experienced excessive pressure to the depths this BOP system will be used in. After intermediate casing is set, (3500') a Class 3 RRAG type BOP will be installed. This BOP will consist of 11" blind rams, 11" pipe rams, 11" - 300 psi annular and an 11" - 3000 psi rotating head. 13. Regulatory/Engl. Mgr. 3/1/96 NATURE SAVER™ FAX MEMO 01616 im THOMPSU Co./Dept. (1193)

After surface casing is set, we propose to nipple-up a

Class 2 AG type BOP with a spacer spool. This BOP will

consist of a 135/8" - 2000 annular and 135/8" - 2000

Potating head. From part records, we had not experienced

excessive pressure to the depths this BOP system will be used


After intermediate casing is set (3500'), a Class 3

RRAG type BOP will. This BOP will consist of 11" blind rams,

11" pipe rams, 11" 3000 pii annular and a 11" 3000 pii rotating head.

STATE OF WALL DIVISION OF UIL, GAS AND HINING ENTITY ACTION FORM - FORM 6

OPERATOR _	River Gas Corporation				
ADDRESS	511 Energy Center Blvd.	-			
	Northport, AL 35476	_			



OF OIL, GAS & MINIS

ACTTON 3000	CURRENT ENTITY NO.	NEW ENTITY NO.	AP (HUNDER	WELL NAME	QQ	SC	HELL	OCATION	COUNTY	SPUD DATE	EFFECTIVE
В	11256	>	43-007-30290	Utah D-3		1.8	15S	10E	Carbon	02/27/96	5712
WELL 1 CO	ज्ञानस्य IS ;	Entity	added 3-5-9	16 (Drunkards Wash Unit).	Lee	10	135	101	Carbon	102/27/30	I
MELL 2 CI	DEPLETE S:				.1			<u> </u>			I
WELL 3 CO	DEMENTS;	1									I
NELL 4 CI	UNNENTS:	Y		·				-			,
MELL 5 CO	DI)ES (See 1	nstructions	on back of form)						0,	01	1

B - Add new well to existing entity (group or unit well).
C - Re-assign well from one existing entity to another existing entity.
D - Ke-assign well from one existing entity to a new entity.
E - Other (explain in comments section)

HOTE: Use COMMENT section to explain why each Action Code was selected.

(3/89)

Signature Dennis Plowman

Reservoir Technician

Title

Date

Phone No. (205, 759-3282)

DIVISION OF OIL, GAS AND MINING E G E I V

	5.	Lease	Designation	ണർ	Serial	Number
--	----	-------	-------------	----	--------	--------

	,	1011 van 7 1006 111	MI - 38666		
SUNDRY	NOTICES AND REPORTS	ON WELLS	6. If Indian, Allottee or Tribe Name:		
	osals to drill new wells, deepen existing wells, or to re-	oter office and sharefored works. IVIIVI	7. Unit Agreement Name:		
Do not use this form for prop Use APPI	CATION FOR PERMIT TO DRILL OR DEEPEN form for	such proposition	<u>UŦU67921X</u>		
			6, Well Name and Number:		
1. Type of Well: OIL GAS	Type of Well: OIL GAS OTHER: Disposal Well				
2. Name of Operator:	-		9. API Well Number:		
Rive	r Gas Corporation		43-007-30290		
3. Address and Telephone Number:			10. Field and Pool, or Wildcat:		
511	<u>Energy Center Bouleva</u>	rd	DRUNKARDS WASH		
4. Location of Well Footages: 1600 FS	L, 1126' FWL	40% ingriss attanta (%) i	county: CARBON		
co, sec. 18	. T15S. R10E		State: UTAH		
	OPRIATE BOXES TO INDICATE	NATURE OF NOTICE, REPO			
NOTIC	CE OF INTENT	SUBSE	QUENT REPORT		
(Sub	omit in Duplicate)	(Submit	Original Form Only)		
Abandonment	☐ New Construction	Abandonment	. ☐ New Construction		
Casing Repair	☐ Pull or Alter Casing	Casing Repair	Pull or Alter Casing		
Change of Plans	☐ Recompletion	☐ Change of Plans	Shoot or Acidize		
☐ Conversion to Injection	☐ Shoot or Acidize	☐ Conversion to Injection	─ Vent or Flare		
☐ Fracture Treat	☐ Vent or Flare	☐ Fracture Treat	☐ Water Shut-Off		
☐ Multiple Completion	☐ Water Shut-Off	Other Change in	BOP (see below)		
Other		_	·		
		Date of work completionC	urrent		
Approximate date work will start		Peport results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION AND LOG form.			
		* Must be accompanied by a cement verific	cation report.		
DESCRIBE PROPOSED OR COMPLETED vertical depths for all markers and zones	OPERATIONS (Clearly state all pertinent details, and personent to this work.)	give pertinent dates. If well is directionally drille-	d, give subsurface locations and measured and true		
Class 2 Additional Class 2 Addit	r surface casing is s G type BOP with a spa 2000# annular and 13 we have not experienc system will be used i	cer spool. This BO -5/3" - 2000# rota ed excessive press n.	P will consist of a ting head. From past ure to the depths		
Afte BOD will	r intermediate casing he installed. This BO	is set, (3500') a P will consist of	Class 3 RRAG type		

pipe rams, 11" - 300 psi annular and an 11" - 3000 psi rotating head.

Regulatory/Eng. Mgr Date: 3/1/96

STATE OF UTAH DEPARTMENT OF I RAL RESOURCES

_		
6. Le	ase	Designation and Serial Number
ML	- ·	38666
7. Inc	iiar	Allottee or Tribe Name

DIVISION OF OIL, GAS AND MININ	ML - 38666	
		7. Indian Allottee or Tribe Name
SUNDRY NOTICES AND REPORTS C	IN WELLS	
On not use this form for proposals to drill new wells, deepen existing wells, or to rec Use APPLICATION FOR PERMIT— for such propo		8. Unit or Communitization Agreement
		UTU67921X
1. Type of Well Cit., XX Gas Other (specify)		9. Well Name and Number
Well Coald	ed Methane	Utah D-3
2. Name of Operator		10. APi 'Yell Number
River Gas Corporation		43-007-30290
3. Address of Operator	4. Telephone Number	11. Field and Pool, or Wildcat
511 Energy Center Blvd. Northport, AL 35476	(205) 759–3282	Drunkards Wash
5. Location of Well Footage: 1600' FSL & 1126' FWL QQ. Sec. T., R., M.: NW/SW Sec. 18, T15S, R10E	State	: Carbon : UTAH
12. CHECK APPROPRIATE BOXES TO INDICATE NA	ATURE OF NOTICE, REPO	RT, OR OTHER DATA
NOTICE OF INTENT (Submit in Duplicate)	SUBSE((Submit 0	QUENT REPORT Original Form Only)
Abandonment New Construction Casing Repair Pull or Alter Casing Change of Plans Recompletion Shoot or Acidize Fracture Treat Vent or Flare Multiple Completion Water Shut-Off Other	Abandonment • Casing Repair Change of Plans Conversion to Injection Fracture Treat Other Weekly Prog	New Construction Pull or Alter Casing Shoot or Acidize Vent or Flare Water Shut-Off
Approximate Date Work Will Start	Date of Work Completion	
	Report results of Multiple Completion WELL COMPLETION OR RECCompanied by a teme	
13. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertin locations and measured and true vertical depths for all markers and zones pertin	ent details, and give pertinent dates. ent to this work.)	If well is directionally drilled, give subsurface
See Attached		

14. I hereby certify that the foregoing is true and correct Dennis Plowman Name & Signature

TitleReservoir Technician Oate

State Use Only)

DAILY REPORT

RIVER GAS CORPORATION
D-3 (DISPOSAL WELL)
1600' FSL & 1126' FWL
NW/4 of SW/4 Sec. 18, T15S, R10E
Carbon County, Utah

Elevation: 6300' API: 43-007-30290

Drilling Contractor: Bill Jr. Rathole Drilling

Page 1

02/28/96

Day 1. Present Operations: Prepare to start drilling. Current Depth: 80'. Depth drilled in 24 hrs: 80'. Drilling fluid: Air. Drilled 20' w/#1 26" Augor bit in ½ hour. Drilled 20' to 80' w/#2 17-1/2" Mission bit in 2 hours. Total rotating hrs: 2-1/2. Spud Well 9:48am, 2/27/96. Set 1 jnt 20" structural conductor csg @ 20' in a 26" conductor borehole. Daily Costs: \$4150.00. Cumulative Costs: \$4150.00.

02/29/96

Day 2. Present Operation: Drilling.Current Depth: 225'. Depth drilled in 24 hrs: 145'. Drilling fluid: Air, 210PSI, & 1200-1400 cfm. Drilled 20' 225' W/#2 17-1/2" mission hammer bit in 13-1/2 hrs. Total rotating hrs: 16. Daily Costs: \$24921.21. Cumulative Costs: \$29071.21.

03/01/96

Day 3. Present Operation: Drilling. Current Depth: 355'. Depth drilled in 24 hrs: 130'. Drilling fluid: Air, 200-225PSI, & 1200-1400 cfm. Drilled w/#2 17-1/2" mission hammer bit for 13-1/2 hours. Total rotating hrs: 29-1/2. Daily Costs: \$8737.24. Cumulative Costs: \$37808.45.

03/04/96

Day 4. Present Operation: Drilling. Current Depth: 510'. Depth drilled in 24 hrs: 155'. Drilling fluid: Air, 200-225PSI, & 1200-1450 cfm. Drilled 20' w/#2 17-1/2" mission hammer bit in 21 hrs. Total rotating hrs: 50.5. Daily Costs: \$7431.00. Cumulative Costs: \$45239.45.

RIVER GAS CORPORATION
D-3 (DISPOSAL WELL)
1600' FSL & 1126' FWL
NW/4 of SW/4 Sec. 18, T15S, R10E
Carbon County, Utah
Elevation: 6300'

API: 43-007-30290

Drilling Contractor: Bill Jr. Rathole Drilling

Page 2

03/04/96

Day 5. Present Operation: Digging cellar-install wellhead. Current Depth: 526'. Depth drilled in 24 hrs: 20'. Drilled 20' to 530' w/#2 17-1/2" Mission hammer bit in 4-1/2 hours. Total rotating hrs: 55. Set 12 jnts 13-3/8" H-40 surface csg @ 526' using 600 sks \$\mathrm{G}\mathrm{G}\mathrm{F}\math

03/04/96

Day 6. Present Operation: prepare to rig up #16. Current Depth: 527'. Repaired leak in casing, tested - good @ 700PSI. Daily Costs: \$4758.43. Cumulative Costs: \$71547.67.

STATE OF UTAH DIVISION OF OIL, GAS AND MINING CEMENTING OPERATIONS

WELL NAME: Wat D-3 API NO: 43-007-30290
QTR/QTR: NWSW SECTION: / TOWNSHIP: NS RANGE: 10E
COMPANY NAME: RIVER GAS COMPANY MAN GERG MUEller
INSPECTOR: J. R. MATTHEWS DATE: 3/18/94
CASING INFORMATION: SURFACE CASING: 13 3
SIZE: 9 GRADE: K-55 HOLE SIZE: 12 14 DEPTH: 37 20
PIPE CENTRALIZED:
CEMENTING COMPANY: Dowell Schlumberger
CEMENTING STAGES:
SLURRY INFORMATION: 1. CLASS: G ADDITIVES: 5/50 Por w/8/3/10% Salt BWOW) + 2 % Calle
1.CLASS: ADDITIVES: SON OF SON
Salr Brow 1+2/6 Call
LEAD: 1250 SK TAIL: 1200 Shr ClG +4
2.SLURRY WEIGHT LBS. PER GALLON:
LEAD: 12.5 TAIL: 15.8
3.WATER (GAL/SX)
LEAD: 10.8 TAIL: 5.0 4. Yield 1.92 cuft/sx 1.15 cuft/sk
4. Yield 1. 92 Cuff/SX LOST RETURNS:
1 INCH INFORMATION: WEIGHT: CEMENT TO SURFACE:
FEET: SX: CLASS: CACL%: RETURNS:
ADDITIONAL COMMENTS:
1250 5k led = 3400 cuft coment
2005k tul = 230 aff cenal
Ron 89gt 40# KSSLTEC + SJE 36#KSS Calyer on density shows wrished out section 23 00 to 3100'
Califer on density shours wished out Reclied
2300 to 3100'

STATE OF UTAH DIVISION OF OIL, GAS AND MINING CEMENTING OPERATIONS

WELL NAME: <u>UTAH D-3</u> API NO: <u>43-007-30290</u>	_
QTR/QTR: NW/SW SECTION: 18 TOWNSHIP: 15S RANGE: 10E	
COMPANY NAME: RIVER GAS COMPANY MAN GREG MUELLER	
INSPECTOR: F. R. MATTHEWS DATE: 3/18/96	_
CASING INFORMATION: SURFACE CASING: 13 3/8"	
SIZE: 9 5/8" GRADE: K-55 HOLE SIZE: 12 1/4" DEPTH: 3720'	
PIPE CENTRALIZED: YES	
CEMENTING COMPANY: DOWELL	
CEMENTING STAGES: 1	
SLURRY INFORMATION: 1.CLASS: "G" ADDITIVES: 50/50 POZ W/8% GEL 10% SALT	-
(BWOW) + 2% CACL	_
LEAD : 1250 SX TAIL: 200 SX CLASS "G"	
2.SLURRY WEIGHT LBS. PER GALLON:	•
LEAD 12.5 #'S TAIL: 15.8 #'S	•
3.WATER (GAL/SX)	
LEAD: 10.8 # 'S TAIL: 5.0 #'S	
4. YIELD: 1.92 CU/FT SX 1/15 CU/FT SX	
CEMENT TO SURFACE: LOST RETURNS:	
1 INCH INFORMATION: WEIGHT: CEMENT TO SURFACE:	
FEET: SX: CLASS: CACL%: RETURNS:	
ADDITIONAL COMMENTS: 1250 SX LEAD= 2400 CUFT CEMENT-200SX TAIL	
230 CU/FT CEMENT. RAN 89 JTS K-55 40# LT & C-5 JTS K-55 36 #.	
CALIPER ON DENSITY SHOWS WASHED OUT SECTION-2300' TO 3100'	

Form 9 STATE OF UTAH	
DEPARTMENT OF NO PAL RESO	
DIVISION OF OIL, AS AND M	INING 38666
3.3.3.9.3.6.1.0.1.1.0.1.0.1.0.1.0.1.0.1.0.1.0.1.0	MAR 2.5 1996 Tipbian Allottee or Tribe Name
CUNDENC NOTICES AND DEPORT	
SUNDRY NOTICES AND REPORT	S ON WELLS
and the desputies form for proposals to drift new wells, deepen existing wells, dr.	to reenter plugged and abandoned wells: 8. Unit or Communitization Agreement
Use APPLICATION FOR PERMIT— for such t	The state of the s
1. Type of Weil	UTU67921X
Cil VV Gae Charlesoità	albed Methane
2. Name of Operator	ocar b-3
River Gas Corporation	10. APi 'Yell Number
3. Address of Operator	43-007-30290
511 Energy Center Blvd. Northport, AL 3547	(005) 750 0000
5. Location of Well	6 (205) 759-3282 Drunkards Wash
Footage : 1600' FSL & 1126' FWL	a . Carbon
QQ. Sec. T., R., M. : NW/SW Sec 18, T155, R10E	County: Carbon
	State : UTAH
NOTICE OF INTENT	NATURE OF NOTICE REPORT, OR OTHER DATA
(Submit in Duplicate)	SUBSEQUENT REPORT (Submit Original Form Only)
Abandonment	Abandonment • New Construction
Casing Repair Pull or Alter Casing	Casing Repair Pull or Alter Casing
Change of Plans Recompletion	Change of Plans Shoot or Acidize
☐ Conversion to Injection ☐ Shoot or Acidize	Conversion to Injection Vent or Flare
Fracture Treat Vent or Flare	Fracture Treat Water Shut-Off
Multiple Completion Water Shut-Off	Cther Weekly Progress Report
Other	
•	Date of Work Completion
Approximate Date Work Will Start	
	Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION AND LOG form.
	Must be accompanied by a tement verification report.
3. DESCRIBE PROPOSED OR COMPLETED ORERATIONS (Closely grate all	
locations and measured and true vertical depths for all markers and zones p	pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface pertinent to this work.)
The proof of the second of the	
See Attached	
See Attached	
apple for the state of the stat	Marine in the second of the se
•	
I hereby certify that the foregoing is true and correct	, ,
me & Signature Dennis Plowman	uman Title Reservoir Technician Dai D3/18/96
aie Uce Coiv)	www.

RIVER GAS CORPORATION
D-3 (DISPOSAL WELL)
1600' FSL & 1126' FWL
NW/4 of SW/4 Sec. 18, T15S, R10E
Carbon County, Utah
Elevation: 6300'
API: 43-007-30290
Drilling Contractor: Caza Drilling

Page 5

03/18/96

Day 19. Present Operation: Drilling. Current Depth: 3658'. Depth drilled in 24 hrs: 48'. Drilling fluid: Mud. Drilled 3422' to 3630' w/#7 12-1/4" Sec 86F bit in 13-1/2 hrs. Drilled 3630' w/#8 12-1/4" smith bit in 9-1/2 hrs. Total rotating hrs: 235. Daily Costs: \$7914.00. Cumulative Costs: \$219214.03.

03/18/96

Day 20. Present Operation: GIH - drilling 10'. Currrent Depth: 3710'. Depth drilled in 24 hrs: 52'. Drilling fluid: Mud. Drilled 3630' to 3710' w/#8 12-1/4" smith bit in 16 hrs. Drilled 3710' w/#9 12-1/4" smith bit in 2-1/2 hrs. Total rotating hrs: 244. Daily Costs: \$16646.00. Cumulative Costs: \$235860.03.

RIVER GAS CORPORATION
D-3 (DISPOSAL WELL)
1600' FSL & 1126' FWL
NW/4 of SW/4 Sec. 18, T15S, R10E
Carbon County, Utah
Elevation: 6300'
API: 43-007-30290

Drilling Contractor: Caza Drilling

Page 4

Day 14. Present Operation: Repair U-joint on rig. Current Depth: 3077'. Depth drilled in 24 hrs: 112'. Drilling fluid: Mud. Drilled 2891' w/#6 12-1/4" Sec s84F bit in 22-1/2 hrs. Total rotating hrs: 144. Daily Costs: \$9981.71. Cumulative Costs: \$174682.84.

Day 15. Present Operation: Drilling. Current Depth: 3222'. Depth drilled in 24 hrs: 145'. Drilling fluid: Mud, 500-600psi. Drilled 2891' w/#6 12-1/4" Sec S84F bit in 23-1/2 hrs. Total rotating hrs: 161. Daily Costs: \$8762.00. Cumulative Costs: 183444.84.

Day 16. Present Operation: Drilling. Current Depth: 3365'. Depth drilled in 24 hrs: 143'. Drilling fluid: Mud. Drilled 2891' w/#6 12-1/4" Sec S84F bit in 24 hrs. Total rotating hrs: 182. Daily Costs: \$9087.47. Cumulative Costs: \$192532.31.

Day 17. Present Operation: Drilling. Current Depth: 3464'. Depth drilled in 24 hrs: 99'. Drilling fluid: Mud. Drilled 2891' to 3422' w/#6 12-1/4" Sec S84F bit in 13.5 hrs. Drilled 3422' w/#7 12-1/4" Sec 86F bit in 10 hrs. Total rotating hrs: 197-1/2. Daily Costs: \$10689.72. Cumulative Costs: \$203222.03.

Day 18. Present Operation: Repair #2
Pump/Drilling. Current Depth: 3610'. Depth drilled
in 24 hrs: 146'. Drilling fluid: Mud. Drilled
3422' w/#7 12-1/4" Sec 86F bit in 24 hrs. Total
rotating hrs: 221-1/2. Daily Costs: \$8078.00.
Cumulative Costs: \$211300.03.

RIVER GAS CORPORATION
D-3 (DISPOSAL WELL)
1600' FSL & 1126' FWL
NW/4 of SW/4 Sec. 18, T15S, R10E
Carbon County, Utah
Elevation: 6300'

API: 43-007-30290

Drilling Contractor: Caza Drilling

Page 3

03/07/96

Day 9. Present Operation: Prepare to Drill.

Current Depth: 1910'. Depth drilled in 24 hrs:
29'. Drilling fluid: Air, 300-350PSI, & 1600-2400
cfm. Drilled 526' to 1900' w/#3 12-1/4" hammer bit
in 5 hrs. Drilled 1900' to 1910' w/#4 12-1/4"
hammer bit in 10 hrs. Drilled 1910' w/#5 12-1/4"
smith bit in 2 hrs. Total rotating hrs: 81-1/2".

Daily Costs: \$10645.80. Cumulative Costs:
\$120360.77.

03/08/96

Day 10. Present Operation: Drilling. Current Depth: 2685'. Depth drilled in 24 hrs: 775'. Drilling fluid: Air, 280-350PSI, & 2000-2800 cfm. Drilled 1910 w/#5 12-1/4" smith bit in 24 hrs. Total rotating hrs: 105-1/2. Daily Costs: \$8810.80. Cumulative Costs: \$129171.57.

03/11/96

Day 11. Present Operation: Working Stuck Pipe. Current Depth: 2891'. Depth drilled in 24 hrs: 206'. Drilling fluid: Air/Mist, 350-15000, & 2800 cfm. Drilled 1910' to 2891' w/#5 12-1/4" Smith F-2 bit in 24 hrs. Total rotating hrs: 117.5. Daily Costs: \$8000.56. Cumulative Costs: \$137172.13.

03/11/96

Day 12. Present Operation: Ream & Condition Hole. Current Depth: 2981'. Depth drilled in 24 hrs: 248'. Drilling fluid: Air/Mud, 8.6#/gal, & 300-400 cfm. Drilled 1910' to 2891' w/#5 12-1/4" Smith F-2 bit in 5-1/2 hrs. Drilled 2391' w/#6 12-1/4" Sec S84F bit in 14 hrs. Total rotating hrs: 117.5, w/8 hrs. Reaming. Daily Costs: \$15876.00. Cumulative Costs: \$153048.13.

03/11/96

Day 13. Present Operation: Drilling. Current Depth: 2965'. Depth drilled in 24 hrs: 74'. Drilling fluid: Mud, 8.5# 2000 vis 85. Drilled 2891' w/#6 12-1/4" Sec S84F bit in 24 hrs. Totalt rotating hrs: 127. Daily Costs: \$11653.00. Cumulative Costs: \$164701.13.

· D	STATE OF UTAH IVISION OF OIL, GAS AND	MINING NEGET	
		MAR 2 6 1996	5. Lease Designation and Serial Number: ML - 38666
SUNDRY N	NOTICES AND REPOR	to the second se	6. If Indian, Allottee or Tribe Name;
Do not use this form for proposel Use APPLICA	is to drill new wells, deepen existing wells, or ITION FOR PERMIT TO DRILL OR DEEPEN fo	to reenter plugged and ebendoned wette.	UTU67921X
1. Type of Welt: OfL GAS	OTHER: Disposal W	ell(Waste Water)	6. Well Name and Number:
2.Name of Operator: River Gas Corpo			9. API Well Number: 43 = 007 = 30290
a. Address and Telephone Number: 511 Energy Cent		thport. Alabama 35476	10. Field and Pool, or Wildcet:
4. Location of Well Footages: 1600' FSL & 1 GO, Sec.,T.,R.M.: Sec. 18. T	126' FWL (NW/4		County: Carbon State: Utah
		TE NATURE OF NOTICE, REPO	ORT, OR OTHER DATA
	OF INTENT in Duplicate)	2	QUENT REPORT t Original Form Only)
Abandonment Casing Repair Change of Plans Conversion to Injection Fracture Treat Multiple Completion	 New Construction Pull or Alter Casing Recompletion Shoot or Addize Vent or Flare Water Shut-Off 	☐ Abandonment * ☐ Casing Repair ☐ Change of Plans ☐ Conversion to Injection ☐ Fracture Treat XX Other _Weekly Prog	☐ New Construction ☐ Pull or After Casing ☐ Shoot or Acidize ☐ Vent or Flare ☐ Water Shut-Off
pproximate date work will start		Date of work completion Report results of Multiple Completions of COMPLETION OR RECOMPLETION AND Must be accompanied by a comput verific	

SEE ATTACHED

13. Trie: Reg / Engineering Mg Page: 3-22-96

(This space for State use only)

File Rurelo AS Wah D-3 P.M. Z A.M. -0009 000Z

MAR 2 2 1996 DIV OF OIL, GAS & MINING

DEPARTMENT OF NATURAL RESOURCE	CES 6. Lease Designation and Serial Number
DIVISION OF 🕋 GAS AND MÍNI	
	7. Indian Allottee or Tribe Name
SUNDRY NOTICES AND REPORTS O	DN WELLS
Og not use this form for proposals to drill new wells, deepen existing wells, or to re Use APPLICATION FOR PERMIT—for such propo	enter plugged and abandoned wells: 8. Unit or Communitization Agreement usals
	UTU 67921X
	Disposal Well Sa Mall 9. Well Name and Number D-3
2. Name of Cperator	10. API Well Number
River Gas Corporation 3. Address of Operator	4. Telephone Number 11. Field and Pool, or Wildcat
511 Energy Center Blvd. Northport, AL 354	776 (205) 759-3282 Drunkards Wash
Footage 1600: FSL & 1126' FWL CC. Sec. T. R. M.: NW/SW, Sec 18, T15S, R10E	County: Carbon State: UTAH
12. CHECK APPROPRIATE BOXES TO INDICATE N.	ATURE OF NOTICE: REPORT: OR OTHER DATA
NOTICE OF INTENT (Submit in Duplicate)	SUBSEQUENT REPORT (Submit Original Form Only)
Abandonment New Construction Casing Repair Pull or Alter Casing Change of Plans Recompletion Conversion to Injection Shoot or Acidize Fracture Treat Vent or Flare Multiple Completion Water Shut-Off Other	Abandonment * New Construction Casing Repair Pull or Alter Casing Change of Plans Shoot or Acidize Conversion to Injection Vent or Flare Fracture Treat Water Shut-Off Other Extending Depth
	Date of Work Completion 3/27/96
Approximate Date Work Will Start	Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION AND LOG form. * Must be accompanied by a rement verification report.
13. DESCRISE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertin locations and measured and true vertical depths for all markers and zones pertin	sect details, and give geginent dates. If well is directionally drilled, give subsurface
Proposed total depth was extended to 6500'. C	Original total depth was 6300'.
14 I hereby certify that the foregoing is true and correct Mame & Signature Callen Hurth Cullen Hurth	
(State Use City)	Title Tech. Assistant Care 3/27/96

**	<i>p</i> 4	DIV	ISION OF	OIL, GAS AND	MINIM	G APR 4	. 1998
			سلانسا و ا	NA NA NA NA	NR 		5. Lease Designation and Serial Number:
	2					a la	ML - 38666
	SUNI	DRY N	OTICES	AND REPO	RTS C	N WELLS	6. If Indian, Allottee or Tribe Name:
Do	not use this form	for proposals	to drill new wells,	deepen existing wells, of TO DRILL OR DEEPEN	or to reenter form for suc	plugged and abandoned wells. h proposals.	7. Unit Agreement Name:
1. Type of Well:		GAS 🗍	OTHER:				8. Well Name and Number:
			<u> </u>	DISPOSAT	кетт	(Waste Water)	9. API Well Number:
2. Name of Oper		_			(205)	759-3282	43-007-30290
			orpora	tion	(200)		10. Field and Pool, or Wildcat:
3. Address and 1	Telephone Number 511 Fn		Cantar	Boulevaro	d No	rthport, Al. 35476	Drunkards Wash
4. Location of W		cidy	Center	Dourevari	<u>u </u>		
Footages:		FSL 8	1126'	FWL			county: Carbon
QQ, Sec.,T.,R.	. м.: Sec	18, 7	15S, R	10E (NW/	4 of	SW/4)	State: Utah
11.						TURE OF NOTICE, REPOR	RT, OR OTHER DATA
		NOTICE	OF INTENT	-		SUBSEQ	UENT REPORT riginal Form Only)
☐ Abandonr	ment		☐ New Co	nstruction		Abandonment *	☐ New Construction
☐ Casing Re			☐ Pull or A	Alter Casing		Casing Repair	☐ Pull or Alter Casing
☐ Change o	•		☐ Recomp	oletion		Change of Plans	Shoot or Acidize
	on to Injection		☐ Shoot o	r Acidize		☐ Conversion to Injection	☐ Vent or Flare
☐ Fracture 7			☐ Vent or	Flare		☐ Fracture Treat	☐ Water Shut-Off
☐ Multiple C			☐ Water S		1	XCX Other Weekly Progr	ress Report
							•
				_	}	Date of work completion	
Approximate	date work wil	l start				Report results of Multiple Completions and COMPLETION OR RECOMPLETION AND L	d Recompletions to different reservoirs on WELL. OG form.
					Į.	a tall the comment undiffer	tion remot

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

SEE ATTACHED

13. <u>Steven L.</u>

Title: Req./Engineering Mg Pate: 3-29-96

(This space for State use only)

RIVER GAS CORPORATION

D-3 (DISPOSAL WELL)

1600' FSL & 1126' FWL

NW/4 of SW/4 Sec. 18, T15S, R10E

Carbon County, Utah Elevation: 6300' API: 43-007-30290

Drilling Contractor: Caza Drilling

Page 6

03/21/96 Day 23. Present Operation: Drying out

Hole/Drilling. Current Depth: 4567'. Depth drilled in 24 hrs: 762'. Drilling fluid: Air & 2000 scf. Drilled 3718' w/#10 8-3/4" smith bit in 24 hrs. Total rotating hrs: 274-1/2. Daily Costs:

Total rotating hrs: 2/4-1/2. Daily Costs: \$10210.00. Cumulative Costs: \$346006.08.

03/25/96

Day 24. Present Operation: Drilling. Current Depth: 5102'. Depth drilled in 24 hrs: 535'. Drilling fluid: Air, 30/35000#/60-70 RPM - 200psi, & 2000'-2200' cfm. Drilled 3718' to 4828' w/#10 8-3/4" halco hammer bit in 11 hrs. Drilled 4826' w/#11 8-3/4" reed bit in 10 hrs. Total rotating hrs: 281-1/2. Daily Costs: \$7942.80. Cumulative Costs: \$353948.88.

03/25/96

Day 25. Present Operation: Drilling. Current Depth: 5398'. Depth drilled in 24 hrs: 296'. Drilling fluid: Air/Mud. Drilled 4826' w/#11 8-3/4" reed bit in 24 hrs. Total rotating hrs: 300-1/2. Daily Costs: \$16480.00. Cumulative Costs: \$370428.88.

03/25/96

Day 26. Present Operation: Drilling. Current Depth: 5628'. Depth drilled in 24 hrs: 230'. Drilling fluid: Mud. Drilled 4826' w/#11 8-3/4" reed bit in 24 hrs. Total rotating hrs: 324-1/2. Daily Costs: \$9438.00. Cumulative Costs: \$379866.88.

03/25/96

Day 27. Present Operation: TOH. Current Depth: 5981'. Depth drilled in 24 hrs: 353'. Drilling fluid: Mud. Drilled 4826' to 5981' w/#11 8-3/4" reed bit in 24 hrs. Total rotating hrs: 347-1/2. Daily Costs: \$9091.00. Cumulative Costs: \$388957.88.

RIVER GAS CORPORATION

D-3 (DISPOSAL WELL)

1600' FSL & 1126' FWL

NW/4 of SW/4 Sec. 18, T15S, R10E

Carbon County, Utah

Elevation: 6300' API: 43-007-30290

Drilling Contractor: Caza Drilling

Page 7

03/26/96

Day 28. Present Operation: Drilling. Current Depth: 6185'. Depth drilled in 24 hrs: 204'. Drilling fluid: Mud. Drilled 4826' to 5981' w/#118-3/4" reed bit in 6 hrs. Drilled 5981' w/#128-3/4" reed bit in 17 hrs. Total rotating hrs: 360-1/2. Daily Costs: \$15202.66. Cumulative Costs: \$404160.54.

03/28/96

Day 29. Present Operation: Drilling. Current Depth: 6448'. Depth drilled in 24 hrs: 263'. Drilling fluid: Mud. Drilled 4826 w/#11 8-3/4" reed bit in 24 hrs. Total rotating hrs: 383-1/2. Daily Costs: \$7989.74. Cumulative Costs: \$412150.28.

03/29/96

Day 30. Present Operation: Logging. Current Depth: 6510'. Depth drilled in 24 hrs: 62'. Drilling fluid: Mud. Drilled 5981' to 6510' w/#11 8-3/4" reed bit in 18 hrs. Total rotating hrs: 393-1/2. Drilled 6448' to 6510', condition hole to log, Survey 1-1/2 @ 6510', circulate and pull out of hole. RU Schlumberger @ 12:40 am 3/28/96 to log AIT/Dipole Sonic. NOTE: Schlumberger having trouble w/communication system. Daily Costs: \$7733.00. Cumulative Costs: \$419883.28.

03/29/96

Day 31. Logging. At 2:30am 3/29/96 core tool stuck. Arm would not retract. Attmepts to pull arm off tool failed. Calculations show possible cable stuck @ or near casing seat +/- 4000'. Discussed procedure w/schlumberger and called Graco Fishing Tool for equipment. Discussed options w/Mr. Willis @ 3:10am. Daily Costs: \$6909.00. Cumulative Costs: \$426792.28.

SUNDRY NOTICES	AND REPORTS (APR 1 1 1995 ON WELLS A OF OIL, GAS & MINING	5. Lease Designation and Serial Number: ML - 38666 6. If Indian, Allottee or Tribe Name: 7. Unit Agreement Name:						
Do not use this form for proposals to drill new wells Use APPLICATION FOR PERMI	to DRILL OR DEEPEN form for su		UTU-67921X						
1. Type of Well: OIL GAS OTHER:	Disposal Well	(Waste Water)	8. Well Name and Number:						
2. Name of Operator: River Gas Corpora	tion (205) 759-3282	9. API Well Number: 43-007-30290 10. Field and Pool, or Wildcat:						
3. Address and Telephone Number: 511 Energy Center	Drunkards Wash								
4. Location of Well Footages: 1600' FSL & 1126' QQ, Sec.,T.,R.,M.: Sec 18, T155, R			county: Carbon State: Utah						
11. CHECK APPROPRIATE BO	XES TO INDICATE N	ATURE OF NOTICE, REPOR	T, OR OTHER DATA						
NOTICE OF INTENT (Submit in Duplicate)		SUBSEQU	ENT REPORT ginel Form Only)						
☐ Abandonment ☐ New Co	onstruction	☐ Abandonment *	☐ New Construction						
Casing Repair Pull or	Alter Casing	Casing Repair	☐ Pull or Alter Casing						
Change of Plans Recom	pletion	☐ Change of Plans	☐ Shoot or Acidize						
☐ Conversion to Injection ☐ Shoot of	r Acidize	Conversion to Injection	☐ Vent or Flare						
☐ Fracture Treat ☐ Vent or	i	Fracture Treat	☐ Water Shut-Off						
Multiple Completion Water S	ihut-Off	Other Wkly Progres	5 Kpc						
OtherApproximate date work will start		Date of work completion Report results of Multiple Completions and COMPLETION OR RECOMPLETION AND LO * Must be accompanied by a cement verification							
 DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clear vertical depths for all markers and zones pertinent to this work. 		re pertinent dates. If well is directionally drilled, g	ive subsurface locations and measured and true						
Moved Ross Well S	ervice Workove	· · · · · · · · · · · · · · · · · · ·	ion on April 1, 1996						
Rigged up and drilled									
2-7/8" Tubing out of t	he hole and ra	an a Bond Log (Schl	umberger) on April						
3, 1996. Swabbed the h	ole to reduce	the Hydrostatic Pr	essure before Per-						
forating the well with	Halliburton N	Wireline Service. P	erforated @ 6030'-						
6040' 6 spf. on April	4, 1996. Rigge	ed up and swabbed t	he well to retrieve						
water samples for the	State. Rigged	up Halliburton Ene	rgy Service and						
Acidize the well with	1000 gals of 2	28% HCL Acid. Rate	25 BPM.						

Name & Signature:

ISIP-950psi, 5min-750psi, 10min-600psi, & 15min-510psi.

True: V.P. Utah Operations Date: 4-8-96
V.P. Utah Operations

(This space for State use only)

RIVER GAS CORPORATION
D-3 (DISPOSAL WELL)
1600' FSL & 1126' FWL
NW/4 of SW/4 Sec. 18, T15S, R10E

Carbon County, Utah Elevation: 6300'

API: 43-007-30290

Drilling Contractor: Caza Drilling

Page 8

04/01/96

Day 32. Present Operation: Logging. Current Depth: 6510'. Waiting on Fishing Tools. Attempt to pull tool free w/rig. Pulled out of rope socket. GIH w/fish tool, tagged fish @ 5829'. Pumped on string-fish not latched. GIH-push fish. Latched fish, chain out of hole. LD fish, recovered 4 cores. Break down fishing tools & load out. Attempt to core - Tool would not operate downhole. Tested before going in hole. POOH and begin repairs, GIH w/bond log tool. Logging w/bond log. Daily Costs: \$9639.00. Cumulative Costs: \$436431.28.

04/01/96

Day 33. Present Operation: Circulate/Prepare to cement. TD 3/27/96 @ 5:00pm, 6510'. Running bond log, attempt to locate sidewall core gun. RD Schlumberger, TIH, circulate & condition. POOH & LD drill string. RU csg crew, Set 101 jnts Production Csg @ 6507.58' in 8-3/4" production borehole using 49 sks 50/50 POZ + 8% D-20 + 10% D-44 + D-35 + 2% S-1 and 323 sks 10-1 RFC. Daily Costs: \$126946.35. Cumulative Costs: \$563377.63.

04/01/96

Day 34. Present Operation: Done-Rig Released. Plug Down 3/31/96 12:45pm. Daily Costs: \$51556.97. Cumulative Costs: \$614934.60.

04/08/96

4/1/96-RU Ross's. 4/2/96-RU to drill out D.V. Tool (4095'). 4/3/96-pulled Tubing out of hole and ran Bond Log. 4/4/96-Swabbed the hole to reduce Hydrostatic Pressure before perforating. Perforated well @ 6030'-6040' 6 spf. Also, RU & swabbed well to retrieve wtr samples for the State. RU Halliburton and acidized well w/1000gals of 28% HCL. Rate 2-.5BPM. ISIP-950psi, 5 min-750psi, 10 min-600psi, & 15 min-510psi.

CLIENT STATE OF WAY.	On Ga	25+1	Mini	NC					A		RICA							C	H	AI]	N ()F	CU	ST	ODY	[
ADDRESS STRIAD CENT	ER Śu	ITE 3	50	1	1					ALY'	WE!	I L													,	5 4 1
SALT LAKE CIT	4 UT	84180					. 4				ORII Sou														¥	à
PHONE/FAX 359-3940								Salt	Lake	Cit	y, Ut 841			(801) (801)				L	AE	3 #		2:	554	'گ		_
CONTACT RRAD HIL							7	7	77	7	7	7/	7	7	7	7	7	7	7	7	7	7	7			
						/	//	//	//	//	//		//	//	/		/,	//	//	//	A POOR I					
SITE RIVER GAS						//	/ /	/ !?/c		//	//		//	//	//	//		/	//	//			TIDAL 4	, DOID		ca
				Š		/s			(y (3)		//	//	\mathbb{Z}	//	//		/	/	/	//	/Q/ \$7/	/ 1	I = P	riority		:5
SAMPLER'S SIGNATURE			, a	8			3/3				//	//	//		//	//	//	//					$\Pi = P$ $\Pi = 5$		tush	
SAMPLE ID	SAMPLE DATE/TIME	MATRIX	0 */			\$\\\ \$\\\			//	//		//	//		//	//	//	//	//		/	CO	s = s MM (tandard ENT		
SWAB #1				Í													\perp				SE	5	ATT	Kit		
SWAB #2		ļ						_	_				1.				\perp						···			,
				\perp				_ _	\downarrow				_	\sqcup	_	-	_	_	_	\downarrow						
		ļ.		_	Ш				_	_			-		_		\bot	_	_	+						
				_	\sqcup	_		-	+	-			+	\vdash	+	-	+	+	-	+-						
			\vdash		\dashv			+	+	+	-		+-	\vdash	\dashv	+	+	+	-	+			· · · · · ·		·	
				+	╁		\vdash	\dashv	+		+	+	+	\vdash	\dashv		+	+	\vdash	-						
		<u> </u>		+					+		\dashv	+	\dagger		+	+	+	\dagger	 	+						
				\dagger				1	+			\top	\dagger	H	1	\top	\dagger	\dagger	\dagger	+						_
				\top					1							\top		T		1		***				
								$\int \int $																		
0.05 (Relin	quish	ed B		traspot o	Ш						Time /6./		lecei [,]	ved I	3y: Si	gnatu	re				I	Date/Tim	e
Quote # /P.O. # 2 00 43 4			PRIN	TENA	ME	7	20	ZAX		4		47		151		PRIN	TN	AME								
Special Instructions:			Relin			: Sig			,	-)	<u></u>		Date/	Time					gnatu	re				I	Date/Tim	ē
															\dashv						. ~ 					
			PRIN			Sign	alure					[Date/	Time				AME or L		tory,	By:			<u> </u>	Date/Tim	
																177	•	h.		Ha	1		<u> </u>	4/8	196	
		····	PRIN	T NA	ME									· · · · · · · · · · · · · · · · · · ·	P	RIN	T NA	ME	<u> 5</u> 1	an	1 a +	las	war	-/	161	0
																						/				



WEST ANALYTICAL LABORATORIES

INORGANIC ANALYSIS REPORT

Client: State of Utah-Oil, Gas, and Mining

Date Sampled: February 15, 1996

Lab Sample ID.: 25073-02

Field Sample ID.: Texaco SWD 1 Sample #2

Contact: Dan Jarvis

Date Received: February 16, 1996

Received By: Sherlyn Lewis

Set Description: Two Waste Samples

Analytical Results


NAVAJO 55 Formation

463 West 3600 South Salt Lake City; Utah	TOTAL METALS	Method <u>Used:</u>	Detection <u>Limit</u> : mg/Kg	Amount <u>Detected:</u> mg/Kg
***************************************	Calcium	6010	5.0	2,700.
	Magnesium	6010	5.0	700.
(801) 263-8686 Fax (801) 263-8687	Potassium	6010	5.0	280.
	Sodium	6010	5.0	4,600.
	OTHER CHEMISTRIES			
	Bicarbonate (as CaCO ₃)	310.1	10.	460.
	Bromide	320.1/405.0	0.05/0.1	1.8
	Carbonate (as CaCO ₃)	310.1	10.	<10.
	Chloride	4500 CLB	0.5	11,000.
	†Conductivity	120.1	10.	24,000.
	Nitrate (as N)	353.2	0.01	<0.01
	pH	150.1	0.1	6.6
	Sulfate	375.4	5.0	3,600.
	TDS	160.1	1.0	23,000.

Conductivity reported in µmhos/cm @ 25 C.

Released by:

Laboratory Supervisor



CHAIN OF CUSTODY REPORT (ln01) Apr 08 1996, 04:42 pm

gin Number: L25542

Account: OGM100 State of Utah - Oil, Gas, and Mining

Site : RIVER GAS

(or UTA110)

Contact: Brad Hill

Laboratory
Sample Number

DIV. OF-OIL, GAS & MINING
Sample Number

Date
Date
Date
Date

		SWAB #1		05-APR-96 08-AP	R-96 17 <i>-1</i>	
nly one	sampl	e container per s	sample, water chem & metals, SHARE. PO	200434	0	1 Contain
Nater	P	BI/CARB	Bicarbonate & carbonate		apr 8	1 Concarn
Vater	C	BICARB	Bicarbonate (as CaCO3)	Expires:19-APR-96		
later	C ·	CARB	Carbonate (as CaCO3)	Expires:19-APR-96		
Vater	S	BR	Bromide	Expires:03-MAY-96		
Vater	S.	CA	Calcium	Expires:02-OCT-96		
Vater	s.	.CL	Chloride	Expires:03-MAY-96		
Vater	s .	COND	Conductivity (Specific)	Expires:03-MAY-96		
later	s·	DIG-MET	Total Metal Digestion	Expires:02-OCT-96		
Vater	s.	K	Potassium	Expires:02-OCT-96		
Vater	s ·	MG	Magnesium	Expires:02-OCT-96		
later	S -	NA /	Sodium	Expires:02-OCT-96		
later	s.	NO3	Nitrate (as N)	Expires:03-MAY-96	. •	
Vater	S	PH	рH	Expires:06-APR-96		
Water	S	S04	Sulfate	Expires:03-MAY-96		
later	S	TDS	Total dissolved solids	Expires:12-APR-96		
	1	SWAB #2		05-APR+96 08-AP	R-96 17- <i>1</i>	APR-96
525542-2 Only one	e sampl	le container per	sample, water chem & metals, SHARE			
.25542-2 Only one Vater	sampl P	le container per s BI/CARB	Bicarbonate & carbonate		R-96 17- <i>1</i> apr 8	
.25542-2 Only one Vater	e sampl	le container per s BI/CARB BICARB	Bicarbonate & carbonate Bicarbonate (as CaCO3)	Expires:19-APR-96		
.25542-2 Only one Water Water	e sampl P C C	e container per s BI/CARB BICARB CARB	Bicarbonate & carbonate Bicarbonate (as CaCO3) · Carbonate (as CaCO3)	Expires:19-APR-96 Expires:19-APR-96		
.25542-2 Only one Water Water Water Water	e sampl P C C S	ie container per s BI/CARB BICARB CARB BR	Bicarbonate & carbonate Bicarbonate (as CaCO3) Carbonate (as CaCO3) Bromide	Expires:19-APR-96 Expires:19-APR-96 Expires:03-MAY-96		
325542-2 Only one Water Water Water Water Water	sampl P C C S S	Le container per s BI/CARB BICARB CARB BR CA	Bicarbonate & carbonate Bicarbonate (as CaCO3) Carbonate (as CaCO3) Bromide Calcium	Expires:19-APR-96 Expires:19-APR-96 Expires:03-MAY-96 Expires:02-OCT-96		
325542-2 Only one Nater Nater Nater Nater Nater	sampl P C C S S	Le container per s BI/CARB BICARB CARB BR CA CL	Bicarbonate & carbonate Bicarbonate (as CaCO3) Carbonate (as CaCO3) Bromide Calcium Chloride	Expires:19-APR-96 Expires:19-APR-96 Expires:03-MAY-96 Expires:02-OCT-96 Expires:03-MAY-96		
125542-2 Only one Water Water Water Water Water Water	e sampl P C C S S S	Le container per s BI/CARB BICARB CARB BR CA CL COND	Bicarbonate & carbonate Bicarbonate (as CaCO3) Carbonate (as CaCO3) Bromide Calcium Chloride Conductivity (Specific)	Expires:19-APR-96 Expires:19-APR-96 Expires:03-MAY-96 Expires:02-OCT-96 Expires:03-MAY-96 Expires:03-MAY-96		
325542-2 Only one Nater Nater Nater Nater Nater	sampl P C S S S S	Le container per s BI/CARB BICARB CARB BR CA CL COND DIG-MET	Bicarbonate & carbonate Bicarbonate (as CaCO3) Carbonate (as CaCO3) Bromide Calcium Chloride Conductivity (Specific) Total Metal Digestion	Expires:19-APR-96 Expires:19-APR-96 Expires:03-MAY-96 Expires:02-OCT-96 Expires:03-MAY-96 Expires:03-MAY-96 Expires:02-OCT-96		
a25542-2 Inly one Mater Mater Mater Mater Mater Mater Mater	e sampl P C S S S S S	Le container per s BI/CARB BICARB CARB BR CA CL COND DIG-MET K	Bicarbonate & carbonate Bicarbonate (as CaCO3) Carbonate (as CaCO3) Bromide Calcium Chloride Conductivity (Specific) Total Metal Digestion Potassium	Expires:19-APR-96 Expires:19-APR-96 Expires:03-MAY-96 Expires:03-MAY-96 Expires:03-MAY-96 Expires:03-MAY-96 Expires:02-OCT-96 Expires:02-OCT-96		
25542-2 mly one later later later later later later later later later	e sampl P C S S S S S S	Le container per s BI/CARB BICARB CARB BR CA CL COND DIG-MET K MG	Bicarbonate & carbonate Bicarbonate (as CaCO3) Carbonate (as CaCO3) Bromide Calcium Chloride Conductivity (Specific) Total Metal Digestion Potassium Magnesium	Expires:19-APR-96 Expires:19-APR-96 Expires:03-MAY-96 Expires:03-MAY-96 Expires:03-MAY-96 Expires:03-MAY-96 Expires:02-OCT-96 Expires:02-OCT-96 Expires:02-OCT-96		
25542-2 only one later later later later later later later later	sampl P C S S S S S S	Le container per s BI/CARB BICARB CARB BR CA CL COND DIG-MET K MG NA	Bicarbonate & carbonate Bicarbonate (as CaCO3) Carbonate (as CaCO3) Bromide Calcium Chloride Conductivity (Specific) Total Metal Digestion Potassium Magnesium Sodium	Expires:19-APR-96 Expires:19-APR-96 Expires:03-MAY-96 Expires:03-MAY-96 Expires:03-MAY-96 Expires:03-MAY-96 Expires:02-OCT-96 Expires:02-OCT-96 Expires:02-OCT-96 Expires:02-OCT-96 Expires:02-OCT-96		
25542-2 mly one later later later later later later later later later later later	sampl P C S S S S S S	Le container per s BI/CARB BICARB CARB BR CA CL COND DIG-MET K MG	Bicarbonate & carbonate Bicarbonate (as CaCO3) Carbonate (as CaCO3) Bromide Calcium Chloride Conductivity (Specific) Total Metal Digestion Potassium Magnesium Sodium Nitrate (as N)	Expires:19-APR-96 Expires:19-APR-96 Expires:03-MAY-96 Expires:03-MAY-96 Expires:03-MAY-96 Expires:03-MAY-96 Expires:02-OCT-96 Expires:02-OCT-96 Expires:02-OCT-96 Expires:02-OCT-96 Expires:02-OCT-96 Expires:02-OCT-96		
25542-2 mly one later	e sampl P C S S S S S S S S S S S S S S S S S S	Le container per s BI/CARB BICARB CARB BR CCA CL COND DIG-MET K MG NA NO3 PH	Bicarbonate & carbonate Bicarbonate (as CaCO3) Carbonate (as CaCO3) Bromide Calcium Chloride Conductivity (Specific) Total Metal Digestion Potassium Magnesium Sodium Nitrate (as N)	Expires:19-APR-96 Expires:19-APR-96 Expires:03-MAY-96 Expires:03-MAY-96 Expires:03-MAY-96 Expires:02-OCT-96 Expires:02-OCT-96 Expires:02-OCT-96 Expires:02-OCT-96 Expires:02-OCT-96 Expires:02-OCT-96 Expires:03-MAY-96 Expires:03-MAY-96 Expires:06-APR-96		
325542-2 Only one Nater Nater Nater Nater Nater	e sampl P C S S S S S S S S S S S S S S S S S S	Le container per s BI/CARB BICARB CARB BR CA CL COND DIG-MET K MG NA NO3	Bicarbonate & carbonate Bicarbonate (as CaCO3) Carbonate (as CaCO3) Bromide Calcium Chloride Conductivity (Specific) Total Metal Digestion Potassium Magnesium Sodium Nitrate (as N)	Expires:19-APR-96 Expires:19-APR-96 Expires:03-MAY-96 Expires:03-MAY-96 Expires:03-MAY-96 Expires:03-MAY-96 Expires:02-OCT-96 Expires:02-OCT-96 Expires:02-OCT-96 Expires:02-OCT-96 Expires:02-OCT-96 Expires:02-OCT-96		APR-96 1 Contain

Page 1	
Signature:	
Date	

CLIENT SATE OF WAY	On GA	+5+1	Minir	مالا				ΑN	MERIC. WE					C	HA	AIN O	F CI	U STODY
ADDRESS 3 TRIAD CENT	ER Su	ITE 3	50	Π					LYTIC LATORI	AL							`	
SALT LAKE CIT	4,47	84180					63 W	est 3	600 So	uth	(004)	262.6						
PHONE/FAX 359-3940) <u> </u>	4					Sait 1	Lake	City, U 841	tan l 15	(801) (Fax (801) (L	AB	#	255	42
CONTACT BRAD HIL						//	//		//,	//	////	//		//	//,		/&/	
STE RIVER GAS				Æ	\$ /		//			//		//	//	//	//,			
					//5			// !//		//	////			//		TOWN THE OWN THE PROPERTY OF T	TURN I =	AROUND TIMES Priority I
SAMPLER'S SIGNATURE			ړ	5/E/						//	////	//		//	//,		II =	Priority II 5 Day Rush
SAMPLE ID	SAMPLE DATE/TIME	MATRIX	0				7 /	//			////	//	//	//	//		S =	Standard MENTS
SWAB #1	4/5/96 447	welv														SEE	AT	TAUTED
SWAB #2	4/5/96 5:07									_	1.	1				u		и
				$\perp \perp$	_	\sqcup	_	-		_		igspace		_	-			
77					-	\vdash	+-			_		+	\vdash	-	+			
					-							+	\vdash	-	+			
					1													
				$\bot \bot$				-		_								
				-	_	\vdash	-	-		-		-		_	-		· · · · · · · · · · · · · · · · · · ·	
					-		7 1			_		+		_	-			
			Relinq	uished l	BAY Si	eleaspere	\mathcal{W}		L		Date/Time	Re	ceived	By: S	ignatur	<u> </u> 		Date/Time
Quote # /P.O. # 2 00 434			#)	>	<u> </u>		<u>4</u>		1	4/8	8/16 16:10				····			
Special Instructions:				r NAMi uished i		<u>DR</u> gnature	(A)	ŀ	410	$\overline{\top}$	Date/Time		INT !		E Signatur	re		Date/Time
			DDIN	Γ ΝΑΜ								DD	INT I	JA 7/11				
				ched By		ature					Date/Time	Re	ceived	for L		tory By:		Date/Time
			PRIN	T NAM	E							PR	INT	NAME	£10	na H	aywa	rd 1610



AMERICAN WEST ANALYTICAL LABORATORIES

INORGANIC ANALYSIS REPORT

Client: State of Utah-Oil, Gas, and Mining

Date Sampled: February 15, 1996

Lab Sample ID.: 25073-02

Field Sample ID.: Texaco SWD 1 Sample #2

Contact: Dan Jarvis

Date Received: February 16, 1996

Received By: Sherlyn Lewis

Set Description: Two Waste Samples

Analytical Results

NAMOSS Formation

463 West 3600 South Salt Lake City, Utah	TOTAL METALS	Method <u>Used:</u>	Detection Limit: mg/Kg	Amount <u>Detected:</u> mg/Kg
84115	Calcium	6010	5.0	2,700.
	Magnesium	6010	5.0	700.
(801) 263-8686 Fax (801) 263-8687	Potassium	6010	5.0	280.
1 4 (001) 2 7 10 10 10 10 10 10 10 10 10 10 10 10 10	Sodium	6010	5.0	4,600.
	OTHER CHEMISTRIES Bicarbonate (as CaCO ₃)	310.1	10.	460.
	Bromide	320.1/405.0	0.05/0.1	1.8
	Carbonate (as CaCO ₃)	310.1	10.	<10.
	Chloride	4500 CLB	0.5	11,000.
	†Conductivity	120.1	10.	24,000.
	Nitrate (as N)	353.2	0.01	<0.01
. *	pH	150.1	0.1	6.6
	Sulfate	375.4	5.0	3,600.
	TDS	160.1	1.0	23,000.

Conductivity reported in µmhos/cm @ 25 C.

Released by:

Report Date 2/27/96

1 of 1
This report is provided for the exclusive use of the addressee. Privileges of subsequent use of the name of this company or any member of its staff, or reproduction of this report in connection with the advertisement, promotion or sale of any product or process or in connection with the re-publication of this report for any purpose than for the addressee will be granted only on contract, this company accepts no responsibility except for the difference of the process of the difference of the process. CONTRACT. THIS COMPANY ACCEPTS NO RESPONSIBILITY EXCEPT FOR THE DUE PERFORMANCE OF INSPECTION AND/OR ANALYSIS IN GOOD FAITH AND

STATE OF UTAH Division of Oil, Gas and Mining 355 West North Temple 3 Triad Center, Suite 350 Salt Lake City, Utah 84180-1203


INJECTION WELL - PRESSURE TEST

Test Date: 4 19 96 W	Well Owner/Operator: Rive	er Gas
Disposal Well:	Enhanced Recovery Well:	Other:
API No.: 43- <u>007 -30290</u> W	Vell Name/Number: \\\	h D-3
Section: \\\ \begin{array}{c c} \T	'ownship: \\ \(\) \(\) \(\)	Range: E
Initial Conditions:		
	Pressure:	psi
Casing/Tubing Annulus - 1	Pressure:	psi
Conditions During Test:		
Time (Minutes) 0 /2:/0 / // . 5 10 15 /2:25 / // . 20 25 30 Results: Pass/Fail Conditions After Test:	Annulus Pressure 2050 2050 2050 2050	Tubing Pressure
Tubing Pressure:	psi	
Casing/Pubing Annulus Pr	ressure: <u>2050</u> p	osi
REMARKS: 15 Min (a)	Zano Took	11 66/p.
7" esq. 26"7 Dwellon breating, C	ft, K-55 Signating test	250 than t premuse
Terry Diets Operator Representative		hes Kierst M Witness
Pormor representative	230	



RIVER GAS CORPORATION

511 Energy Center Blvd.
Northport, Alabama 35476
Phone (205) 759-3282
Fax (205) 759-3188 (Accounting)
Fax (205) 758-5309 (Corporate)



May 6, 1996

Mr. Gil Hunt State of Utah Department of Natural Resources Division of Oil, Gas, and Mining 3 Triad Center, Suite 350 Salt Lake City, UT 84180-1203

Re: Utah D-3 Injection Application

NW / SW of Sec. 18, T 15 S, R 10 E S.L.B. & M., Carbon County, Utah

Dear Mr. Hunt:

Enclosed is an original and one copy of the remaining information to be submitted for the Utah D-3 injection well. Attached to the updated UIC form 1 is the following information.

Attachment #1 - Updated description of the casing, and casing test

Attachment #2 - Estimated amounts of fluid to be injected daily

Attachment #3 - Water analyses: formation fluid and compatibility anlysis

Attachment #4 - Proposed average and maximum injection pressures

Attachment #5 - Information on swabbing run per conversation with John

Hollingshead of 4/23/94

Attachment #6 - Evidence to support a finding that the proposed injection well will

not initiate fractures through the overlying strata that could enable

the injected fluid to enter the fresh water strata.

Copies of electrical, radioactive and cement bond logs

If any aspect of this application remains incomplete or if I may be of assistance in any way please contact me at your convenience.

Sincerely,


Callen Hurtt

Technical Assistant

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

APPLICATION FOR INJECTION WELL - UIC FORM 1

OPERATOR _	River Gas Corporation
ADDRESS _	511 Energy Center Blvd.
	Northport, AL 35476



Well name and number:Utah D-3									
Field or Unit name: Drunkards Wash Lease no. ML-38666									
Well location: QQ $_{ m NW/SW}$ section $_{ m 18}$ township $_{ m 15S}$ range $_{ m 10E}$ county $_{ m Carbon}$									
Is this application for expansion of an existing project? Yes 🛣 No []									
Will the proposed well be used for: Enhanced Recovery? Yes [] No [] Disposal? Yes [] No [] Storage? Yes [] No []									
Is this application for a new well to be drilled? Yes 🛛 No []									
If this application is for an existing well, has a casing test been performed on the well? Yes $\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \$									
Proposed injection interval: from $5,600'$ to $6,100'$									
Proposed maximum injection: rate 28,800 BWPD pressure 1820 psig									
Proposed injection zone contains [] oil, [] gas, and/or [] fresh water within $\%$ mile of the well.									
IMPORTANT: Additional information as required by R615-5-2 should accompany this form.									
List of Attachments: <u>casing description</u> , casing test, water analyses, swabbing informantion, evidence and data, copies of logs									
I certify that this report is true and complete to the best of my knowledge.									
Name Callen Hurtt Signature Cullus Hurth Title Technical Assistant Date 5/6/96 Phone No. (205) 759-3282									
(State use only) Application approved by Title Approval Date									

Comments:

PROPOSED DISPOSAL WELL D-3

SEC. 18, T 15 S, R 10 E (1600' FSL, 1126 FWL) CARBON COUNTY, UTAH

20" CONDUCTOR 20"

13-3/8" H-40 48#/FT. CASING 526 G.L.

9-5/8' K-55 36#/FT. CASING 3718' G.L.

7" J-55 26#/FT. CASING 6491 G.L.

River Gas Corp. →→→ MikeChambers

Curve 3 : Disabled

Curve 2 : Unit 1 Pump 1 Flow rate

PRESSURE TEST CASING FOR

Volume is computed from : Unit 1 Pump 1 Flow rate Scan Period (Sec) : 4 Playback : Recording Rate was 4 seconds 0 0 09: 47 PAUSE 米米米 11:54 9.1 BBL 2: 00 END JOB 11.0 12:24 *** END OF REPLAY

NATURE SAVERT FAX MEMO 01616 Date Phone #

BASIC ACQUISITION MODE

CEMENT JOB

REAL-TIME MODE - OIL UNITS

DATE: 19/04/96

A. Type: Produced Water

B. Source: Ferron Coal Group

C. Volume: 28,800 BWPD

A. Fluid Injected:

A sample of produced water was analyzed by Stim-Lab Inc. and the results are shown under the "Injection" column of the attached report.

B. D-3 Formation Fluid:

Two laboratories, Stim-Lab Inc. & Chemtech-Ford, analyzed the formation water from D-3. Their findings are shown on the attached reports.

C. Compatability Produced & Formation Waters: Stim-Lab Inc. conducted this test and the results are shown at the bottom of their report.



7406 N. 81 HIGHWAY • P. O. BOX1644 • DUNCAN, OKLAHOMA 73534 TELEPHONE 405/252-4309 • FAX NUMBER 405/252-6979

GLENN PENNY.
President

May 6, 1996

John Hollingshead River Gas Corp. 3600 Watermelon Rd.. Suite 205 Northport, AL 35476

RE: Analysis of Injection Water Compatibility with Navajo Connate Water, Project SL 4377

Dear Mr. Hollingshead,

STIM-LAB Inc. has completed both water analysis and simple compatibility study for mixing the proposed injection water at Drunkards Wash Field with a connate water sample from the proposed injection zone of the D-3 disposal well. Table 1 gives the analysis of both waters as received. Since neither were maintained in a pressurized state, the pH and carbonate values are most probably higher than would be the case in their natural state due to CO₂ release. Also, a considerable amount of precipitation of iron carbonate hydrate was present in the bottom of the connate water sample. Therefore, the dissolved iron value for this sample is most probably low. This may be the case also for the injection water as it was obtained from the holding pond where some settling of any precipitant may have also occurred. Previous experience with this injection water has shown that it has in the past precipitated iron carbonate hydrate requiring filtration before injection.

The compatibility study looked at mixing the two waters at three volume ratios as shown in Table 1. These were compared with a control mixed with deionized water. These show that some amount of carbonate formation occurred at all ratios with the injection water. A slight amount also occurred with the deionized water at the higher connate water ratio. The precipitant was mostly orange in color and readily soluble in 5% HCl with effervescence which would suggest at lease a portion of it was iron carbonate hydrate. I would expect that with fresh samples maintained under pressure that the precipitation would be less or possibly not occur at all as CO₂ retained in solution would maintain a lower pH with mixing and limit precipitant formation.

Mr. John Hollingshead May 6, 1996 Page 2

I understand an injection test was previously performed on the well with 6000 barrels of tap water. If the well was not flowed back and no formation crossflow is present, this should provide a suitable barrier to prevent any near-wellbore contact of fluids and limit the potential for scaling near the wellbore. If the well has been flowed since that time, I would recommend a preflush of tap water be injected ahead of the flood water. We can discuss the volumes further if needed. Keeping the injection water under pressure from the point of production to re-injection would also limit the amount of CO₂ evolution and reduce the possibility of carbonate formation. It should be pointed out that acid jobs performed on the D-1 well had minimal effect on injection pressure. This would indicate that carbonate precipitation near the wellbore was not a problem with the current injection system.

STIM-LAB Inc. appreciates the opportunity work with you on this project. If you have any questions regarding this testing, please feel free to give Mike Conway or myself a call.

Sincerely

Ron Himes, Group Leader Core Testing Group

RH

STIME LAB

Table 1

SL 4377

River Gas Corporation D-3 Connate and Injection Water Analysis Analyzed 5/1-5/2/96

	Injection	Connate
pН	8.71	6.14
Carbonate	420 mg/L	0 mg/L
Bicarbonate	3890 mg/L	705 mg/L
Chlorides	2518 mg/L	116163 mg/
TDS	8402 mg/L	217264 mg/
Sulfate	<1.6 mg/L	3390 mg/L
Calcium	17,5 mg/L	1390 mg/L
Magnesium	15.8 mg/L	465 mg/L
Iron	<2.5 mg/L	10.9 mg/L
Aluminum	<5.0 mg/L	<5.0 mg/L
Sodium	2600 mg/L	78500 mg/L
•	63 mg/L	1500 mg/L
Potassium	109 mg/L	5386 mg/L
Hardness	100 11191-	

Examination of Injection and Connate Water Compatibility

Mixing Ratio	FeCO3/CaCO3	Final		
Connate/Injection	(mg/L)	pH		
75/25	95	6.88		
50/50	127	7		
25/75	85	7.38		
Mixing Ratio				
Connate& DI				
75/25	24	6.68		
50/50	1	6.78		
25/75	0	6.97		

CHEMTECH-FORD

Date: 4/25/96

To: River Gas of Utah 290 South Highway 55 Price, UT 84501

Group #: 7633 Lab #: 96-U004171

Project: DRUNKARDS WASH Sample Desc: Well D-3 Disposal Well

Date Sampled: 4/80/865 Date Submitted: 4/8/96 Time Sampled: 16:47 Time Received: 13:10

CERTIFICATE OF ANALYSIS

			DATE			
PARAMETER	RESULT	MDL	ANALYZED		METHOD	analyst
INORGANIC PARAMETERS						
Bicarbonate as HCO3, mg/L	952	. 1	4/ 9/96	9:00	SM 2320B	TM
Carbonate as CO3, mg/L	< 1	1	4/ 9/96	9:00	SM 2320B	TM
Alkalinity, Solids, mg/L	469	1	4/ 9/96	9:00	SM 2320B	TM
Hydroxide as OH, mg/L	< 1	3.	4/ 9/96		SM 2320B	\mathbf{TM}
Alkalinity, Total, mg/L	781	. 1	4/ 9/96	9:00	SM 2320B	TM
Carbon Dioxide, mg/L	1,450	1	4/ 9/96	9:00	SM 4500 D	TM
Chloride, mg/L	129,000	500	4/10/96		EPA 325.3	TM
Conductance, Specific, umhos/cm	372,000	0.1	4/11/96	11:15	EPA 120.1	DI
Cyanide (T), mg/L	< 0.002	0.002	4/13/96		ASTM D203	5 DI
Fluoride, mg/L	< 0.5	0.5	4/12/96	11:45	EPA 340.2	DI
Hardness, EDTA Titration, mg/L	5,250	50	4/13/96		EPA 130.2	TM
Mercury (T), as Hg, mg/L	0.0004	0.0003	4/10/96		EPA 245.1	KA
Nitrite, Nitrogen, mg/L	0.010	0.005	4/ 8/96		EPA 354.1	KA
Nitrate/Nitrite-Nitrogen, mg/L	1.1	0.4	4/10/96		EPA 353.1	TH
pH, Units	5.70	0.05	4/ 8/96		EPA 150.1	LS
Phosphorus, Ortho, mg/L	< 0.01	0.01	4/ 9/96		SM 4500	KA 🗸
Sulfate, mg/L	3,760	1000	4/11/96	14:30	EPA 375.4	u.
Total Dissolved Solids, mg/L	215,000	250	4/15/96		EPA 160.1	MO
Total Suspended Solids, mg/L	528	2.5	4/ 8/96	15:30	EPA 160.2	LS Je
Turbidity, NTU	402	0.05	4/8/96	15:00	EPA 180.1	LS C
Antimony (T), as Sb, mg/L	< 0.4	0.4	4/17/96	13:09	EPA 200.7	LH (

Approved By:

{generic.rpt}

801 262 7299 PHONE 801 262 7378 FAX



Date: 4/25/96

To: River Gas of Utah 290 South Highway 55 Price, UT 84501

Group #: 7633 Lab #: 96-U004171 Project: DRUNKARDS WASH Sample Desc: Well D-3

Disposal Well

Date Sampled: 4/5/96 Date Submitted: 4/8/96

Time Sampled: 16:47 Time Received: 13:10

CERTIFICATE OF ANALYSIS

PARAMETER	RESULT	MDL	DATE ANALYZED	METHOD	analyst
INORGANIC PARAMETERS					
Arsenic (T), as As, mg/L	< 0.3	0.3	4/17/96 13:0	9 EPA 200.7	LH
Barium (T), as Ba, mg/L	0.23	0.05	4/17/96 13:0	9 EPA 200.7	LH
Beryllium (T), as Be, mg/L	< 0.005	0.005			LH
Cadmium (T), as Cd, mg/L	< 0.025	0.025			LH
Calcium (T), as Ca, mg/L	1,150	0.5			LH
Chromium(T), as Cr, mg/L	0.06	0.025	·		LH
Copper (T), as Cu, mg/L	0.19	0.05	4/17/96 13:0		
Iron (T), as Fe, mg/L	62.6	0.05	4/17/96 13:0		ĽH
Lead (T), as Pb, mg/L	< 0.2	0.2	4/17/96 13:0		
Magnesium (T), as Mg, mg/L	315	0.5	4/17/96 13:0		
Manganese (T), as Mn, mg/L	0.90	0.05	4/17/96 13:0		LH
Nickel (T), as Ni, mg/L	< 0.05	0.05	4/17/96 13:0		
Potassium (T), as K, mg/L	840	0.5	4/17/96 13:0	9 EPA 200.7	LH
Selenium (T), as Se, mg/L	< 0.4	0.4	4/17/96 13:0		
Silver (T), as Ag, mg/L	< 0.025	0.025	4/17/96 13:0		
Sodium (T) by difference, mg/L	83,300	5	4/24/96	CAL	LH
Thallium (T), as Tl, mg/L	< 0.75	0.75	4/17/96 13:0	9 EPA 200.7	LH
Zinc (T), as Zn, mg/L	0.27	0.05	4/17/96 13:0	9 EPA 200.7	LH
Cation, meq/L	3,730		4/24/96		RR
Anion, meq/L	3,730		4/24/96		ŔŔ
% Difference,	0.02		4/24/96		RR

Approved By:

{generic.rpt}

801 262 7299 PHONE 801 262 7378 FAX





Date: 4/25/96

To: River Gas of Utah 290 South Highway 55 Price, UT 84501

Group #: 7633 Lab #: 96-U004171

Project: DRUNKARDS WASH Sample Desc: Well D-3 Disposal Well

Date Sampled: 4/5/96 Date Submitted: 4/8/96

Time Sampled: 16:47 Time Received: 13:10

CERTIFICATE OF ANALYSIS

DATE PARAMETER RESULT ANALYZED MDL METHOD ANALYST INORGANIC PARAMETERS Receiving Temperature, C -2 4/ 8/96 13:10 RCG

NOTE: Sample submitted on ice. Sample submitted past holding time for Cr(Hex), NO2, Ortho-P, & Turbidity. Sample destroyed a \$100 tube on graphite furnace. Electrical conductivity caused us to run all metal by ICP.

Approved By:

{generic,rpt}

001 262 7298 PHONE 801 262 7378 FAX

A. Proposed Average Injection Pressure:

Proposed average = 1820 psi

B. Maximum Injection Pressure:

$$(.735^{psi}/_{ft} - .433^{psi}/_{ft})$$
 (6035 ft) = 1822 psi

Summary of events leading up to swabbing for formation water

The cementing of the 7" production casing was completed at 12:45 P.M. on 3/31/96. The drilling rig was rigged down and off location late P.M. of 4/1/96. The following morning, 4/2/96, the completion rig was spotted, rigged up, and BOP's nippled up. Milling operations on the D.V. tool (4095'G.L.) commenced at 2:00 P.M. of the same day. By mid P.M. 4/2/96, the mill was lowered to 6442', and the hole was circulated for four hours. Fluid circulation continued for an additional two hours in the A.M. of 4/3/96. At noon of the same day, wireline was rigged up and run in the hole to bond log the production string. The late P.M. was spent running in the hole with a 7" RTTS packer and a 2 7/8" tubing string. On A.M. 4/4/96, fluid level was swabbed down to 5000'. The tubing and packer was tripped out of the hole by 2:00 P.M.. Perforators were rigged up and run in the hole to shoot the casing from 6030'-6040' 6 spf. By late P.M., perforaters were out of the hole. The packer and tubing was started in the hole. The packer was set at 6015' by early A.M. on 4/5/96. The hole was swabbed from 8:00 P.M. to 5:00 P.M. of the same day. The swab runs were as follows:

RUN	# TIME	FLUID HIT(FT.)	PULL FROM(FT.)	FLUID RECOVERED (FT.)	
1.	8:00 A.M.	2100	3800	1600	
2.	8:20 A.M.	3700	5100	1500	
3.	8:40 A.M.	4900	6000	1200	
4.	9:00 A.M.	5600	6000	400	
5.	9:20 A.M.	5600	6000	400	
6.	9:40 A.M.	5600	6000	400	
7.	10:00 A.M.	5700	6000	300	
8.	10:40 A.M.	5700	6000	300	
9.	10:52 A.M.	5700	6000	300	
10.	11:12 A.M.	5500	6000	500	
11.	11:30 A.M.	5700	6000	300 17)	
12.	11:50 A.M.	5700	6000	300	$\overline{}$
13.	12:10 A.M.	5700	6000	$\chi_{1,1,2}$	١,
14.	12:30 P.M.	5700	6000	300	$o_{\mathcal{D}_{\lambda}}$
15.	12:50 P.M.	5700	6000	300 / ") -
16.	1:10 P.M.	5700	6000	300	
17.	1:30 P.M.	5700	6000	300)
18.	1:50 P.M.	5700	6000	300 \\ \/ \/	7
19.	2:10 P.M.	5700	6000	300 LON X	
20.	2:30 P.M.	5700	6000	300 / \	
21.	2:50 P.M.	5700	6000	300 / XV	
22.	3:20 P.M.	5700	6000	300	
23.	3:40 P.M.	5750	6000	250	
24.	4:00 P.M.	5700	6000	300 0 10/11/	
25.	4:20 P.M.		6000	250	
26.	4:40 P.M.	5750	6000	250<1st run	
27.	5:00 P.M.	5700	6000	<u>300</u> <2nd run	
				11,850	

<-- denotes runs that State samples were caught from.

11,850 ft. fluid recovered (68.6 bbls.)

Evidence and Data:

A step rate test was conducted to determine the fracture extension pressure. The pressure realized was 4438 psi at a midpoint perforation of 6035 ft. This pressure translates into a frac gradient of .735 $^{\rm psi}/_{\rm ft}$ which was used in attachment #4 to determine a maximum injection pressure at the surface. A detailed report has been attached for review.

ANALYSIS of INJECTION TESTS PERFORMED on WELL D-3 in DRUNKARDS WASH CARBON COUNTY, UTAH


On April 9, 1996, two step rate tests and 1 long term injection test at constant rate were conducted to determine the fracture parting pressure (fracture extension pressure) on the Wingate interval perforated from 6030 - 40 ft. The surface readout gauge used during the injection stages was placed at ± 6060 ft. and the retrievable gauge used to monitor pressure during the extended shut-in was hung in the collar at 6058 ft. All reported pressures were adjusted to 6035 ft which represents the mid point of the perforations.

EXECUTIVE SUMMARY

The initial bottom hole pressure was 2351 psi. During the first step rate injection test, the reservoir flow capacity was increasing as the rate increased at the low flow rates. Therefore, the rate was increased in steps up to 25 BPM to create a hydraulic fracture and ensure that all the Wingate formation was taking fluid. The pressure was allowed to decline below 3000 psi and a second step rate was conducted. The analysis of the data (figure 1) shows that the fracture extension pressure was 4438 psi which represents a fracture gradient of 0.735 psi/ft. After the pressure had declined to 3159 psi, a 12 hr injection at 2 BPM was conducted. The data was successfully modeled with a short, finite conductivity fracture and an injection permeability of 5.5 md (figure 2). This analysis confirmed that the previously created fracture did not extend during the constant rate injection even at the ending injection pressure of 4431 psi. The pressure decline was then monitored for 133 hours to determine reservoir permeability The principal findings were:

1. The Wingate permeability in the vicinity of the wellbore is approximately 3 md (figure 3). The reduced permeability compared to the measured core permeability's of 10-50 md is due to the crossbedding.

2. The pressure behavior is best modeled by a well setting near one end of a bounded rectangle with the following dimensions.



3. The same crossbedding previously mentioned is most likely the cause of the boundaries observed. Experiences with well D-1 would suggest that the boundaries are not completely sealing boundaries, but "leak" pressure and fluid at a much reduced permeability.

3/0

Figure 1: Analysis of Step Rate Test to Determine Fracture Extension Pressure




Figure 2





Figure 3



River Gas Corp. $\rightarrow \rightarrow \rightarrow$ MikeChambers


2003

WELL	TREA	TME	NT RE	POR	T			Schlumbe Dowel					DATE		
DS-494-C PR	INTED IN U.	S.A.						CHLUMBERG			TED			1-96	
WELL NAME	AND NUMB	EĦ			LOC	CATION (LEGAL)			LOCATION	ut		TREATMENT N		
POOL/FIELD	-3				FOR	MATION	<u> </u>		<u> </u>	OTTOM HOLE		OF WELL		PE OF WELL	ĮNJ.
DUNK	ards	U	ash]_			·							<u>X</u>
COUNTY/PA	HISH				STA	7	<u></u>				BLE PRESS	SUHE	TOP	TO BOTTOM	T NO OF
TYPE OF SE	TVICE				PRI	MARY TI	REATING FL	UID	CA	SING SIZE	wt	DEPTH	 	то	1000
MATE	RACTURING	ENT	SAND CO	NTAOL IER		461	- 1~	later		7"		930		70	<u> </u>
OPERATOR NAME	Riv		Gas						10	BING SIZE	WT	DEPTH		то 7 6	
NAME							خبر _ ال			ACKER TYPE	E PACI	CER DEPTH		то	
SERVICE IN	STRUCTIONS	* hu	<u>255W</u>	٧	tes	1 /	16	Lasing	\ !		45 4514	ULAR VOL		то	
Wit	K K		Wat	es					'	BING VOLUM	AININ	OLAH VOL	PERF. DIA	TO METER-	IN.
										OPEN HOLE	CA	SING VOL.		ATED INTE	
										ISPLACEMEN	_	27_	JOB DONE DO	OWN	FT.
FOR CONV						00 GAL	LONS	:00	"	ISPEMOENTEN	C. TI	. 1	ING CASING	ANNULUS	вотн
ARRIVED (ON LOCAT	ION: 7	29:00			N REC		.00		PRES	SURE		NOTAT	IONS	
TIME (000) to 2400)	TYPE OF	FLUID	RATE BPM	CO2 - N RATE	√2 INC VO	REMENT L. BBLS.	CUM. VOL. BBLS.	PROP TYPE	PROP	CSG.	TBG				
09:00												Pre-Job	Safety Meeti		
11:45												Pressur	e Test To	3,000	psi
11:50	K()		7		, 1	11	Ð			Ð		Star	+ pump	ing Ka	1 was
12:07	1661					Θ	11		_	7,000		Shut	down	Wate	h
<u> </u>	1200						- * *			7		Piess	iuc 15	MIN	
	<u> </u>				_				1		TSTP.	7/10	<i>/</i>)		
<u>.</u>			_		+						T .	200	0		_
	 			 	-			<u> </u>	+-		1/)-	700			
				<u> </u>					+	<u> </u>	10	7 10	<u> </u>		-
	 								+-	ŧ –		7	<i>O</i>	Tabel	
					\dashv			<u> </u>			 	Job	COMP	<u>e 1621.</u>	
	ļ			<u> </u>	_		<u> </u>		-	 		 			
				<u> </u>			ļ			 	 	 			
									<u> </u>		<u> </u>	ļ			·
											<u> </u>				· · ·
														<u> </u>	
						_					,		٠		
	†								1	<u> </u>	,		Ť		
	 	-		-	\dashv				_		1	1		·	
	 		}	 	+		 -		_			1			
	<u></u>		BPM AVER	RAGE IN	JECTION	RATES	<u></u>		+	1.7		OLUME FLU	JID INJECTED		
FLUID		NITROGE	N	I CARBO	ON DIOX	IDE	I TOTAL W	//PROP	WATE	R/ACID BBLS		BBLS		CCF CARBON	TONS
MAXIMUM	, FI	NAL ·	TREATING	PRESS	URE SU	IMMARY IMME	D. S.D.P.	15 MIN S.I.P.	TOTAL	INJECTED	QU		TOTAL ORDER	D/DESIGNED	
7.00	ON PRIOR TO	7_00/ o this to		1UU	U	<u></u>			+-			LBS		<u></u>	Les
								☐ Test☐ Stabilized		OLUME				_ GALS % P	AD
CUSTOMER	REPRÉSEN	TATIVE			DS SER	VICE SU	PERVISOR	1,000.	FRACT	TURE GRADIE	ENT	-			
	•				ے ر	1777	٧١ ،	olmper				-	PAGE	OF	PAGES

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

APPLICATION FOR INJECTION WELL - UIC FORM 1

OPERATOR .	River Gas Corporation	
ADDRESS	511 Energy Center Blvd.	
	Northport, AL 35476	



Well name and number:Utah_D-3								
Field or Unit name: _Drunkards Wash Lease no. ML-38666								
Well location: QQ NW/SW section <u>18</u> township <u>15S</u> range <u>10E</u> county <u>Carbon</u>								
Is this application for expansion of an existing project? Yes XX No []								
Will the proposed well be used for: Enhanced Recovery? Yes [] No [] Disposal? Yes [] No [] Storage? Yes [] No []								
Is this application for a new well to be drilled? Yes 🛛 No []								
If this application is for an existing well, has a casing test been performed on the well? Yes [X] No [] Date of test: 4/19/96 API number: 4300730290								
Proposed injection interval: from <u>5,600'</u> to <u>6,100'</u>								
Proposed maximum injection: rate <u>28,800 BWPD</u> pressure <u>1820</u> psig								
Proposed injection zone contains [] oil, [] gas, and/or [] fresh water within % mile of the well.								
IMPORTANT: Additional information as required by R615-5-2 should accompany this form.								
List of Attachments: <u>casing description; casing test, water analyses, swabbing</u> informantion, evidence and data, copies of logs								
I certify that this report is true and complete to the best of my knowledge.								
Name Callen Hurtt Signature Cullus Hurth Title Technical Assistant Date 1/205) 759-3282 Phone No. (205) 759-3282								
(State use only) Application approved by Title Approval Date								

Comments:

PROPOSED DISPOSAL WELL D-3

SEC. 18, T 15 S, R 10 E (1600' FSL, 1126 FWL) CARBON COUNTY, UTAH

20" CONDUCTOR 20' 13-3/8" H-40 48#/FT. CASING 526 G.L. 9-5/8' K-55 36#/FT. CASING 3718' G.L. 7° J-55 26#/FT. CASING 6491 G.L.

Curve 2 : Unit 1 Pump 1 Flow rate Curve 3 : Disabled

PRESSURE TEST CASING FOR

D-3!

NATURE SAVER™ FAX MEMO 01615 Date ZZ 70 rages 7

Te OHN HOLLINGS HEAD

CA Dept 1 BiG TONN Co.

Phone #

Fax * 768-5209 Fax * (037-8924) Fee

Unit 1 Pump 1 Flow rate Scan Period (Sec) : 4 Playback : Recording Rate was 4 seconds PSI BPM 6 PAUSE 11:54 END JOB 11.0 12:24 END OF REPLAY

BASIC ACQUISITION MODE

CEMENT JOB

REAL-TIME MODE - OIL UNITS

DATE: 19/04/96 TIME: 12: 30

WELL	TREAT	MENT R	EPORT			Schlum					DATE .		
DS-494-C PF	RINTED IN U.S	i A .		DC	WELL S	CHLUMBER		CORPOR	ATED		4-10	1-96	
WELL NAME	AND NUMBE	Я		LOCATION	(LEGAL)		Ō:	LOCATION	1		TREATMENT N		
_0-	-3						\	lernal	J. U.		067		
POOLIFIELD	٠. ا	1	-	FORMATIO	N		. [BOTTOM HOL TEMPERATUR	TE NÊW	F OF WELL REWORK	OIL GAS	PE OF WELL WATER	X inn
COUNTYIPA	ACAS AISH	<u> Uash</u>		STATE				ALLOW	ABLE PRES			TED INTE	
Carl	~ 1			luta	.h		Т.	3G:	- csa.		TOP	TO BOTTO	NO. OF HOLDS
TYPE OF SE		NT SAND	CONTROL	PRIMARY 1	TREATING FL	UID	-	ASING SIZE	WI	DEPTH		то	
	FRACTURING	NT SANDO	THER	LKC	L 1~	ater		UBING SIZE	76 S	0EPTH		TO	
OPERATOR	Rive	r Gas										70	+
		-			عبر د الآو			PACKER TYP	PE PAC	KER DEPTH		το	
SERVICE IN	STRUCTIONS	Pressu	12 +	دخل	7.76	Lasin						το	
- Lit	九人	'L Wa	ter				Ţ	UBING VOLU	ME ANN	VULAR VOL		то	<u> </u>
+								OPEN HOLE	CA	SING VOL.	PERF. DIAM		IN.
									. 7	77	TOTAL-		FT.
FOR CON	VERSION PL	JRPOSES 24 BB	LS EQUAL	S 1000 GAL	LONS			DISPLACEME	NT C. T	BG. I TUE	JOB DONE DO	WN I ANNULUS I	вотн
ARRIVED (ON LOCATIO	ON: 09100) LE	FT LOCATI	ION: 13	: <i>0</i> 0] X		
TIME				TION REC		,	1 9505		SURE		NOTAT	IONS	• .
10001 to 24001	TYPE OF F	LUID PATE BPN	RATE	INCREMENT VOL. BBLS.	VOL. BBLS.	PROP TYPE	PAGE 1	CSG.	TBG		0 1 1 24 11		
<u>09:00 </u>										Pre-Job	Safety Meetin		
11:45										Pressur	re Test To3	, 000_	psi
11:50	K()	7		11/	Ð			0		Star	+ Dums	ina K	e) wat
17:07	1///			4	11			•		<1 +	Jan	1.	
12:07	1700	-	 	1	1-1-1		- 	7,000	 	SVAI	down	ware.	<u> </u>
			 	 	ļ	<u> </u>		ļ	_	Piess	MC 15	MIN	
	· .			1				<u> </u>	ISIL	+700	0		
		1							5 ~	100	0		
-									1/)-	7000	<u> </u>		
			-	 	 		 		10				
	 			 	ļ			 	15	1200	0	- 1	
		<u> </u>								del	COMP	etech.	٠
					<u></u>								
	 		1				- 	-		1.			
	 		 	 			_	 	 	 			
			<u> </u>	ļ				<u> </u>		ļ			
										1			
			-	 		 		-	 	-	· · ·	··	· · · · · · · · · · · · · · · · · · ·
			1	 	ļ			<u> </u>	1	1.			· · ·
			<u> </u>	<u> </u>							<u> </u>	······	
				ļ		-		1.73	1	:			
FLUID	NI	TROGEN	CARBON		TOTAL W	PROP	WATE	R/ACID . BBLS	OIL	OLUME FLU BBLS	NITROGEN	CF	I DIOXIDE
MAXIMUM 7 />D	b 151N/	TREATIN	G PRESSURI VERAGE	SUMMARY IMMER	D. S.D.P. DÜÜ	15 MIN S.I.P.	TOTAL	LINJECTED			PRANT PLACED TOTAL ORDEREC		Les
PAODUCTIO	N PRIOR TO	THIS TREATMENT				☐ Test							
CHETOLES	DEPDECENT	TIVE	1 64	denvior ex	nenviene.	Stabilized		OLUME				GALS % P	AD
CUSTOMER	REPRESENTA	*114VE	08	SERVICE SU	, A	Imper	FRAC	TURE GRADIE	-N1				
				CIVY	(د ۱۷	INVIDE					PAGE	OF	PAGES

A. Type: Produced Water

B. Source: Ferron Coal Group

C. Volume: 28,800 BWPD

- A. Fluid Injected:
 - A sample of produced water was analyzed by Stim-Lab Inc. and the results are shown under the "Injection" column of the attached report.
- B. D-3 Formation Fluid:

Two laboratories, Stim-Lab Inc. & Chemtech-Ford, analyzed the formation water from D-3. Their findings are shown on the attached reports.

C. Compatability Produced & Formation Waters: Stim-Lab Inc. conducted this test and the results are shown at the bottom of their report.



7406 N. 81 HIGHWAY • P. O. BOX1644 • DUNCAN, OKLAHOMA 73534 TELEPHONE 405/252-4309 • FAX NUMBER 405/252-6979

GLENN PENNY. President

May 6, 1996

John Hollingshead River Gas Corp. 3600 Watermelon Rd.. Suite 205 Northport, AL 35476

RE: Analysis of Injection Water Compatibility with Navajo Connate Water, Project SL 4377

Dear Mr. Hollingshead,

STIM-LAB Inc. has completed both water analysis and simple compatibility study for mixing the proposed injection water at Drunkards Wash Field with a connate water sample from the proposed injection zone of the D-3 disposal well. Table 1 gives the analysis of both waters as received. Since neither were maintained in a pressurized state, the pH and carbonate values are most probably higher than would be the case in their natural state due to CO₂ release. Also, a considerable amount of precipitation of iron carbonate hydrate was present in the bottom of the connate water sample. Therefore, the dissolved iron value for this sample is most probably low. This may be the case also for the injection water as it was obtained from the holding pond where some settling of any precipitant may have also occurred. Previous experience with this injection water has shown that it has in the past precipitated iron carbonate hydrate requiring filtration before injection.

The compatibility study looked at mixing the two waters at three volume ratios as shown in Table 1. These were compared with a control mixed with deionized water. These show that some amount of carbonate formation occurred at all ratios with the injection water. A slight amount also occurred with the deionized water at the higher connate water ratio. The precipitant was mostly orange in color and readily soluble in 5% HCl with effervescence which would suggest at lease a portion of it was iron carbonate hydrate. I would expect that with fresh samples maintained under pressure that the precipitation would be less or possibly not occur at all as CO₂ retained in solution would maintain a lower pH with mixing and limit precipitant formation.

Mr. John Hollingshead May 6, 1996 Page 2

I understand an injection test was previously performed on the well with 6000 barrels of tap water. If the well was not flowed back and no formation crossflow is present, this should provide a suitable barrier to prevent any near-wellbore contact of fluids and limit the potential for scaling near the wellbore. If the well has been flowed since that time, I would recommend a preflush of tap water be injected ahead of the flood water. We can discuss the volumes further if needed. Keeping the injection water under pressure from the point of production to re-injection would also limit the amount of CO_2 evolution and reduce the possibility of carbonate formation. It should be pointed out that acid jobs performed on the D-1 well had minimal effect on injection pressure. This would indicate that carbonate precipitation near the wellbore was not a problem with the current injection system.

STIM-LAB Inc. appreciates the opportunity work with you on this project. If you have any questions regarding this testing, please feel free to give Mike Conway or myself a call.

Sincerely

Ron Himes, Group Leader Core Testing Group

RH

STIM LAB

Table 1

SL 4377

River Gas Corporation D-3 Connate and Injection Water Analysis Analyzed 5/1-5/2/96

	Injection	Connate
рH	8.71	6.14
Carbonate	420 mg/L	0 mg/L
Bicarbonate	3890 mg/L	705 mg/L
Chlorides	2518 mg/L	116163 mg/
TDS	8402 mg/L	217264 mg/
Sulfate	<1.6 mg/L	3390 mg/L
Calcium	17.5 mg/L	1390 mg/L
Magnesium	15.8 mg/L	465 mg/L
Iron	<2.5 mg/L	10.9 mg/L
Aluminum	<5.0 mg/L	<5.0 mg/L
Sodium	2600 mg/L	78500 mg/L
Potassium	63 mg/L	1500 mg/L
Hardness	109 mg/L	5386 mg/L

Examination of Injection and Connate Water Compatibility

Mixing Ratio	FeCO3/CaCO3	Final pH		
Connate/Injection	(mg/L)			
75/25	95	6.88		
50/50	127	7		
25/75	85	7.38		
Mixing Ratio				
Connate& D1				
75/25	24	6.68		
50/50	1	6.78		
25/75	0	6.97		

NALYTICAL LABORATORIES



Date: 4/25/96

To: River Gas of Utah 290 South Highway 55 Price, UT 84501

Group #: 7633 Lab #: 96-U004171

Project: DRUNKARDS WASH Sample Desc: Well D-3

Disposal Well

Date Sampled: 4/5/96 Date Submitted: 4/8/96

Time Sampled: 16:47 Time Received: 13:10

CERTIFICATE OF ANALYSIS

·			DATE			
PARAMETER	RESULT	MDL	ANALYZED		METHOD	analyst
INORGANIC PARAMETERS						
Bicarbonate as HCO3, mg/L	952	1	4/ 9/96	9:00	SM 2320B	TM
Carbonate as CO3, mg/L	< 1	1	4/ 9/96	9:00	SM 2320B	TM
Alkalinity, Solids, mg/L	469	1	4/ 9/96	9:00	SM 2320B	TM
Hydroxide as OH, mg/L	< 1	1	4/ 9/96	9:00	SM 2320B	TM
Alkalinity, Total, mg/L	781	. 1	4/ 9/96	9:00	SM 2320B	TM
Carbon Dioxide, mg/L	1,450	1	4/ 9/96	9:00	SM 4500 D	TM
Chloride, mg/L	129,000	500	4/10/96	11:00	EPA 325.3	TM
Conductance, Specific, umhos/cm	372,000	0.1	4/11/96	11:15	EPA 120.1	DI
Cyanide (T), mg/L	< 0.002	0.002	4/13/96	4:20	ASTM D203	5 DI
Fluoride, mg/L	< 0.5	0.5	4/12/96	11:45	EPA 340.2	DI
Hardness, EDTA Titration, mg/L	5,250	50	4/13/96	11:00	EPA 130,2	TM
Mercury (T), as Hg, mg/L	0.0004	0.0003	4/10/96	15:08	EPA 245.1	KA
Nitrite, Nitrogen, mg/L	0.010	0.005	4/ 8/96	17:00	EPA 354.1	KA
Nitrate/Nitrite-Nitrogen, mg/L	1.1	0.4	4/10/96	10:05	EPA 353.1	TH
pH, Units	5.70	0.05	4/ 8/96	15:00	EPA 150.1	LS
Phosphorus, Ortho, mg/L	< 0.01	0.01	4/ 9/96	17:15	SM 4500	KA
Sulfate, mg/L	3,760	1000	4/11/96	14:30	EPA 375.4	TM
Total Dissolved Solids, mg/L	215,000	250	4/15/96	2:05	EPA 160.1	MO
Total Suspended Solids, mg/L	528	2.5	4/ 8/96	15:30	EPA 160.2	LS
Turbidity, NTU	402	0.05	4/ 8/96	15:00	EPA 180.1	LS
Antimony (T), as Sb, mg/L	< 0.4	0.4	4/17/96	13:09	EPA 200.7	LH

Approved By:

{generic.rpt}

801 262 7298 PHONE 801 262 7378 FAX

ANALYTICAL LABORATORIES



Date: 4/25/96

To: River Gas of Utah 290 South Highway 55 Price, UT 84501

Group #: 7633 Lab #: 96-U004171

Project: DRUNKARDS WASH

Sample Desc: Well D-3 Disposal Well

Date Sampled: 4/5/96 Date Submitted: 4/8/96

Time Sampled: 16:47 Time Received: 13:10

CERTIFICATE OF ANALYSIS


PARAMETER	RESULT	MDL	DATE ANALYZED	METHOD	ANALYST
INORGANIC PARAMETERS					
Arsenic (T), as As, mg/L	< 0.3	0.3	4/17/96 13:09	EPA 200.7	LH
Barium (T), as Ba, mg/L	0.23	0.05	4/17/96 13:09		LH
Beryllium (T), as Be, mg/L	< 0.005	0.005	4/17/96 13:09		LH
Cadmium (T) , as Cd, mg/L	< 0.025	0.025	4/17/96 13:09		
Calcium (T), as Ca, mg/L	1,150	0.5	4/17/96 13:09	EPA 200,7	LH
Chromium(T), as Cr, mg/L	0.06	0.025	4/17/96 13:09	EPA 200.7	LH
Copper (T), as Cu, mg/L	0.19	0.05	4/17/96 13:09	EPA 200.7	LH
Iron (T), as Fe, mg/L	62.6	0.05	4/17/96 13:09		LH
Lead (T), as Pb, mg/L	< 0.2	0.2	4/17/96 13:09		LH
Magnesium (T), as Mg, mg/L	315	0.5	4/17/96 13:09		LH
Manganese (T), as Mn, mg/L	0.90	0.05	4/17/96 13:09		LH
Nickel (T), as Ni, mg/L	< 0.05	0.05	4/17/96 13:09		LH
Potassium (T), as K, mg/L	840	0.5	4/17/96 13:09		LH
Selenium (T), as Se, mg/L	< 0.4	0.4	4/17/96 13:09		LH
Silver (T), as Ag, mg/L	< 0.025	0.025	4/17/96 13:09	EPA 200.7	LH
Sodium (T) by difference, mg/L	83,300	5	4/24/96	CAL	LH
Thallium (T), as Tl, mg/L	< 0.75	0.75	4/17/96 13:09	EPA 200.7	LH
Zinc (T), as Zn, mg/L	0.27	0.05	4/17/96 13:09	EPA 200.7	LH
Cation, meq/L	3,730		4/24/96		RR
Anion, meg/L	3,730		4/24/96		RR
% Difference,	0.02		4/24/96		RR

Approved By:

{generic.rpt}

801 262 7299 PHONE 801 262 7378 FAX

CHEMTECH-FORD



Date: 4/25/96

To: River Gas of Utah 290 South Highway 55 Price, UT 84501

Group #: 7633 Lab #: 96-U004171

Project: DRUNKARDS WASH

Sample Desc: Well D-3 Disposal Well

Date Sampled: 4/5/96 Date Submitted: 4/8/96

Time Sampled: 16:47 Time Received: 13:10

CERTIFICATE OF ANALYSIS

DATE PARAMETER RESULT ANALYZED MDL METHOD ANALYST INORGANIC PARAMETERS Receiving Temperature, C 4/ 8/96 13:10 RCG

NOTE: Sample submitted on ice. Sample submitted past holding time for Cr(Hex), NO2, Ortho-P, & Turbidity. Sample destroyed a \$100 tube on graphite furnace. Electrical conductivity caused us to run all metal by ICP.

Approved By:

{generic,rpt}

301 262 7299 PHONE 801 262 7378 FAX

A. Proposed Average Injection Pressure:

Proposed average = 1820 psi

B. Maximum Injection Pressure:

$$(.735^{psi}/_{ft} - .433^{psi}/_{ft})$$
 (6035 ft) = 1822 psi

Summary of events leading up to swabbing for formation water

The cementing of the 7" production casing was completed at 12:45 P.M. on 3/31/96. The drilling rig was rigged down and off location late P.M. of 4/1/96. The following morning, 4/2/96, the completion rig was spotted, rigged up, and BOP's nippled up. Milling operations on the D.V. tool (4095'G.L.) commenced at 2:00 P.M. of the same day. By mid P.M. 4/2/96, the mill was lowered to 6442', and the hole was circulated for four hours. Fluid circulation continued for an additional two hours in the A.M. of 4/3/96. At noon of the same day, wireline was rigged up and run in the hole to bond log the production string. The late P.M. was spent running in the hole with a 7" RTTS packer and a 2 7/8" tubing string. On A.M. 4/4/96, fluid level was swabbed down to 5000'. The tubing and packer was tripped out of the hole by 2:00 Perforators were rigged up and run in the hole to shoot the casing from 6030'-6040' 6 spf. By late P.M., perforaters were out of the hole. The packer and tubing was started in the hole. The packer was set at 6015' by early A.M. on 4/5/96. The hole was swabbed from 8:00 P.M. to 5:00 P.M. of the same day. The swab runs were as follows:

RUN	# TIME	<u>. </u>	FLUID HIT(FT.)	PULL FROM(FT.)	FLUID RECOVERED (FT.)
1.	8:00	A.M.		3800	1600
2.	8:20	A.M.	3700	5100	1500
3.	8:40	A.M.	4900	6000	1200
4.	9:00	A.M.	5600	6000	400
5.	9:20	A.M.	5600	6000	400
6.	9:40	A.M.	5600	6000	400
7.	10:00	A.M.	5700	6000	300
8.	10:40	A.M.	5700	6000	300
9.	10:52	A.M.	5700	6000	300
10.	11:12	A.M.	5500	6000	500
11.	11:30	A.M.	5700	6000	300
12.	11:50	A.M.	5700	6000	300
13.	12:10	A.M.	5700	6000	300
14.	12:30	P.M.	5700	6000	300
15.	12:50	P.M.	5700	6000	300
16.	1:10	P.M.	5700	6000	300
17.	1:30	P.M.	5700	6000	300
18.	1:50	P.M.	5700	6000	300
19.	2:10	P.M.	5700	6000	300
20.	2:30	P.M.	5700	6000	300
21.	2:50	P.M.	5700	6000	300
22.	3:20	P.M.	5700	6000	300
23.	3:40	P.M.	5750	6000	250
24.	4:00	P.M.	5700	6000	300
25.	4:20	P.M.	5750	6000	250
26.	4:40	P.M.	5750	6000	250<1st run
27.	5:00	P.M.	5700	6000	<u>300</u> <2nd run
					11.850

<-- denotes runs that State samples were caught from.

^{11,850} ft. fluid recovered (68.6 bbls.)

Evidence and Data:

A step rate test was conducted to determine the fracture extension pressure. The pressure realized was 4438 psi at a midpoint perforation of 6035 ft. This pressure translates into a frac gradient of .735 $^{\rm psi}/_{\rm ft}$ which was used in attachment #4 to determine a maximum injection pressure at the surface. A detailed report has been attached for review.


ANALYSIS of INJECTION TESTS PERFORMED on WELL D-3 in DRUNKARDS WASH CARBON COUNTY, UTAH

On April 9, 1996, two step rate tests and 1 long term injection test at constant rate were conducted to determine the fracture parting pressure (fracture extension pressure) on the Wingate interval perforated from 6030 - 40 ft. The surface readout gauge used during the injection stages was placed at ± 6060 ft. and the retrievable gauge used to monitor pressure during the extended shut-in was hung in the collar at 6058 ft. All reported pressures were adjusted to 6035 ft which represents the mid point of the perforations.

EXECUTIVE SUMMARY

The initial bottom hole pressure was 2351 psi. During the first step rate injection test, the reservoir flow capacity was increasing as the rate increased at the low flow rates. Therefore, the rate was increased in steps up to 25 BPM to create a hydraulic fracture and ensure that all the Wingate formation was taking fluid. The pressure was allowed to decline below 3000 psi and a second step rate was conducted. The analysis of the data (figure 1) shows that the fracture extension pressure was 4438 psi which represents a fracture gradient of 0.735 psi/ft. After the pressure had declined to 3159 psi, a 12 hr injection at 2 BPM was conducted. The data was successfully modeled with a short, finite conductivity fracture and an injection permeability of 5.5 md (figure 2). This analysis confirmed that the previously created fracture did not extend during the constant rate injection even at the ending injection pressure of 4431 psi. The pressure decline was then monitored for 133 hours to determine reservoir permeability The principal findings were:

- 1. The Wingate permeability in the vicinity of the wellbore is approximately 3 md (figure 3). The reduced permeability compared to the measured core permeability's of 10-50 md is due to the crossbedding.
- 2. The pressure behavior is best modeled by a well setting near one end of a bounded rectangle with the following dimensions.



3. The same crossbedding previously mentioned is most likely the cause of the boundaries observed. Experiences with well D-1 would suggest that the boundaries are not completely sealing boundaries, but "leak" pressure and fluid at a much reduced permeability.

Figure 1: Analysis of Step Rate Test to Determine Fracture Extension Pressure




Figure 2






Figure 3







INORGANIC ANALYSIS REPORT

Client: State of Utah - Oil, Gas, and Mining

Date Sampled: April 5, 1996 Lab Sample ID.: 25542-02

Field Sample ID.: River Gas/Swab #2

Contact: Brad Hill

Date Received: April 8, 1996 Received By: Elona Hayward

Set Description: Two Water Samples

	Analytical Results			
463 West 3600 South	TOTAL METALS	Method <u>Used:</u>	Detection <u>Limit</u> : mg/L	Amount <u>Detected:</u> mg/L
Salt Lake City, Utah 84115	Calcium	6010	0.05	1,400.
	Magnesium	6010	0.05	380.
	Potassium	6010	0.1	1,300.
(801) 263-8686 Fax (801) 263-8687	Sodium	6010	0.1	98,000.
	OTHER CHEMISTRIES			
	Bicarbonate (as CaCO ₃)	310.1	10.	810.
	Bromide	320.1	0.05	9.4
	Carbonate (as CaCO ₃)	310.1	10.	<10.
	Chloride	4500 CLB	0.5	130,000.
	†Conductivity	120.1	10.	150,000.
	*Nitrate (as N)	353.2	0.1	<0.1
	pH	150.1	0.1	6.5
	Sulfate	375.4	5.0	4,800.
	TDS	160.1	1.0	230,000.

Conductivity reported in µmhos/cm @ 25 C.

Released by:

Laboratory Supervisor

The detection limits were raised due to sample matrix interference.



WEST **ANALYTICAL LABORATORIES** **INORGANIC ANALYSIS REPORT**

Client: State of Utah - Oil, Gas, and Mining

Date Sampled: May 22, 1996 Lab Sample ID.: 25984-01

Field Sample ID.: River Gas D-3

Contact: Dan Jarvis

Date Received: May 22, 1996 Received By: Laurie Hastings Set Description: One Water Sample

	Analytical Results					
463 West 3600 South	TOTAL METALS	Method <u>Used:</u>	Reporting Limit: mg/L	Amount <u>Detected:</u> mg/L		
Salt Lake City, Utah 84115	Calcium	6010	0.05	1,700.		
Salt Lake City, Utah 84115 Magnesi Potassiu (801) 263-8686 Fax (801) 263-8687 OTHER CH	Magnesium	6010	0.05	350.		
	Potassium	6010	0.1	2,200.		
	Sodium	6010	0.1	57,000.		
	OTHER CHEMISTRIES					
	Bicarbonate (as CaCO ₃)	310.1	10.	830.		
	Chloride	4500 CLB	0.5	70,000.		
	† Conductivity	120.1	10.	89,000.		
	pН	150.1	0.1	6.0		
	Sulfate	375.4	5.0	3,500.		
	TDS	160.1	1.0	130,000.		

Released by:

Laboratory Supervisor

THIS REPORT IS PROVIDED FOR THE EXCLUSIVE USE OF THE ADDRESSEE. PRIVILEGES OF RESPONSED THE SCAPE OF THIS COMPANY DEOLN'S MEMBER OF ITS STAFF, OR REPRODUCTION OF THIS REPORT IN CONNECTION WITH THE ADVERTISEMENT, PROMOTION OR SALE OF ANY PRODUCT OR PROCESS OR IN CONNECTION WITH THE RE-PUBLICATION OF THIS REPORT FOR ANY PURPOSE THAN FOR THE ADDRESSEE WILL BE GRANTED ONLY ON CONTRACT. THIS COMPANY ACCEPTS NO RESPONSIBILITY EXCEPT FOR THE DUE PERFORMANCE OF INSPECTION AND/OR ANALYSIS IN GOOD FAITH AND ACCORDING TO THE RULES OF THE TRADE AND OF SCIENCE.

Conductivity reported in µmhos/cm @ 25 C.





Wingaka.
Wingaka

Client: State of Utah - Oil, Gas, and Mining

Date Sampled: April 5, 1996 Lab Sample ID.: 25542-01

Field Sample ID.: River Gas/Swab #1

Contact: Brad Hill

Date Received: April 8, 1996 Received By: Elona Hayward

Set Description: Two Water Samples

Analytical Results

	Analytical Results						
163 West 3600 South	TOTAL METALS	Method <u>Used:</u>	Detection <u>Limit</u> : mg/L	Amount <u>Detected:</u> mg/L			
Salt Lake City, Utah 84115	Calcium	6010	0.05	1,300.			
	Magnesium	6010	0.05	400.			
	Potassium	6010	0.1	1,000.			
(801) 263-8686 Fax (801) 263-8687	Sodium	6010	0.1	95,000.			
	OTHER CHEMISTRIES						
	Bicarbonate (as CaCO ₃)	310.1	10.	810.			
	Bromide	320.1	0.05	8.8			
	Carbonate (as CaCO3)	310.1	10.	<10.			
	Chloride	4500 CLB	0.5	130,000.			
	†Conductivity	120.1	10.	150,000.			
	*Nitrate (as N)	353.2	0.1	<0.1			
	pН	150.1	0.1	6.5			
	Sulfate	375.4	5.0	5,000.			
	TDS	160.1	1.0	230,000.			

[†] Conductivity reported in µmhos/cm @ 25 C.

Released by:

Laboratory Supervisor

^{*} The detection limits were raised due to sample matrix interference.



RIVER GAS CORPORATION

511 Energy Center Blvd.
Northport, Alabama 35476
Phone (205) 759-3282
Fax (205) 759-3188 (Accounting)
Fax (205) 758-5309 (Corporate)

May 10, 1996

Mr. Gil Hunt State of Utah Department of Natural Resources Division of Oil, Gas, & Mining 3 Triad Center Ste. 350 Salt Lake Ciy, Ut 84180-1203

Dear Mr. Gil Hunt,

Please find enclosed a report containing the injection test analysis for the D-3 disposal well in the Drunkards Wash Unit. The report also includes a stimulation procedure and treatment design for the potential injection intervals (Wingate Sand, Navajo Sand). The 3-D simulator, GOPHER, was utilized to arrive at the proposed design. If you have any questions about the contents of the report, please call me at 205-759-3282. If you prefer, I would be happy to come to Salt Lake City to discuss the report in person.

Present plans are to stimulate this well the week of May 20 to May 24, 1996, if our proposal is approved. This aggressive time frame will help us better coordinate our available man-power and allow us to start construction on the surface facilities.

Your assistance with this matter is appreciated, and I will be touch with you soon.

Most cordially,

got Holligher

John Hollingshead Reservoir Engineer

ANALYSIS OF INJECTION TESTS PERFORMED ON WELL D-3 IN DRUNKARDS WASH CARBON COUNTY, UTAH

PREPARED FOR:

RIVER GAS CORPORATION 3600 WATERMELON ROAD NORTHPORT, ALABAMA 35476

PREPARED BY:

STIM-LAB, INC. 7406 NORTH HWY 81 DUNCAN, OKLAHOMA 73534

P.O. NUMBER: VERBAL/JOHN HOLLINGSHEAD FILE NUMBER: SL 4377



ANALYSIS of INJECTION TESTS PERFORMED on WELL D-3 in DRUNKARDS WASH CARBON COUNTY, UTAH

On April 9, 1996, two step rate tests and 1 long term injection test at constant rate were conducted to determine the fracture parting pressure (fracture extension pressure) on the Wingate interval perforated from 6030 - 40 ft. The surface readout gauge used during the injection stages was placed at ± 6050 ft. and the retrievable gauge used to monitor pressure during the extended shut-in was hung in the collar at 6058 ft. All reported pressures were adjusted to 6035 ft which represents the mid point of the perforations. The injection pressures were used to calibrate the stress model obtained from Dipole Sonic Log run in late March. Finally stimulation designs were prepared to maximize injectivity into the well.

EXECUTIVE SUMMARY

I. Fracture Extension Pressure and Permeability

The initial bottom hole pressure was 2351 psi. During the first step rate injection test, the reservoir flow capacity was increasing as the rate increased at the low flow rates. Therefore, the rate was increased in steps up to 25 BPM to create a hydraulic fracture and ensure that all the Wingate formation was taking fluid. The pressure was allowed to decline below 3000 psi and a second step rate was conducted. The analysis of the data (figure 1) shows that the fracture extension pressure was 4438 psi which represents a fracture gradient of 0.735 psi/ft. After the pressure had declined to 3159 psi, a 12 hr injection at 2 BPM was conducted. The data was successfully modeled with a short, finite conductivity fracture and an injection permeability of 5.5 md (figure 2). This analysis confirmed that the previously created fracture did not extend during the constant rate injection even at the ending injection pressure of 4431 psi. The pressure decline was then monitored for 133 hours to determine reservoir permeability The principal findings were:

- 1. The Wingate permeability in the vicinity of the wellbore is approximately 3 md (figure 3). The reduced permeability compared to the measured core permeability's of 10-50 md is due to the crossbedding.
- 2. The pressure behavior is best modeled by a well setting near one end of a bounded rectangle with the following dimensions.




Figure 1: Analysis of Step Rate Test to Determine Fracture Extension Pressure




Figure 2





Figure 3



3. The same crossbedding previously mentioned is most likely the cause of the boundaries observed. Experiences with well D-1 would suggest that the boundaries are not completely sealing boundaries, but "leak" pressure and fluid at a much reduced permeability.

II. Stress Profile

The interpretation of the Dipole Sonic Log provides Young's Modulus and Poissons Ratio which are used to compute mechanical strength. Tectonic stresses must also be computed to determine the total stress. Injection data from the step rate test as modeled with the 3-D fracture design program, GOHFER (Grid Oriented Hydraulic Fracture Extension Replicator) was used to estimate the tectonic stress component.

- 1. The simulation match is shown in figure 4. The details of the simulation are given in Appendix A. The low rate data where the pressure is dominated by matrix leakoff cannot be modelled and is shown by a dashed line. The fracture dimensions at the end of pumping 44690 gal of water is given in figure 5: height = 240 ft, $x_f = 360 \text{ ft}$.
- 2. The calibrated stress profile developed from the injection data and Dipole Sonic Log is shown in figures 6. The principal feature is the very high stress, multiple barriers that cap the Navajo sandstone.

III. Stimulation Design

Based on the limited injectivity observed in the Wingate injection test, a Hydraulic Fracturing strategy was developed to optimize the water disposal capacity of D-3. The areas of permeability that were targeted for stimulation are shown in figure 7.

1. Wingate: 5995-6055 ft: The created fracture during the water injection test was contained by the moderately higher stresses seen from 5950-5980 ft. This is basically the only barrier separating the Navajo from the Wingate. Therefore the design treatment size, pump rate and viscosity were selected which would not penetrate the barrier. The design is summarized in Table 1 and described in detail in Appendix B. The proppant concentration (lb/ft²) is given in figure 8.

Table 1
Fluid: 9950 gal of 40 lb/1000 gal Guar Proppant: 42,140 lb 20/40 sand Treatment: Pump down tubing at 10 BPM.

Stage	Volume	Sand Concentration
	gallons	lb/gallon
1	2000	0
2	500	1
3	500	2
4	500	3
5.	1000	4
6	6000	6

Figure 4: Comparison of Predicted versus Actual Bottom Hole Pressure




Figure 5

End of Pumping Fracture Width (inches)






Figure 6: Computed Stress from Mechanical Properties Log




Figure 7 Input Properties Permeability (md)






Figure 8

End of Simulation Proppant Concentration (pounds per square foot)





Approach to the Navajo: 5540-5910 ft: Various perforated intervals, fluid viscosities, and pump rates were examined to attempt to place deep penetrating fractures. No stress barriers were identified short of the cap at the top. Therefore the approach was to place the best possible stimulation treatment through a set of perforations from 5550-5600 ft. Small treatments are being considered for the other intervals to ensure communication of the perforations with the primary fracture placed through the uppermost perforations.

2. Navajo A: 5500-5600 ft: The principal factor limiting deep penetration into the permeable zones is leak-off. Large pads do not provide significantly improved penetration. The major factor seems to be placing large volumes at low sand concentrations to maximize penetration into the permeable zone. Therefore one may be advised to consider using 3% diesel in the first 50% of the treatment to improve the penetration depth. Further simulations will be conducted to refine the recommendation. The current design recommended is summarized in Table 2. The detailed design is given in Appendix C. The proppant placement in pounds/gallon which emphasizes the influence of leakoff on the sand concentration in shown at approximately 30 minutes after shut-in in figure 9. Figure 10 gives the proppant concentration (lb/ft²) at the end of the simulation.


Table 2
Fluid: 53000 gal of 35 lb/1000 gal Borate Gel
Proppant: 185,000 lb 20/40 sand

Treatment: Pump down Casing at 60 BPM.

Stage	Volume	Sand Concentration
	gallons	lb/gallon
1	8000	0
2	5000	1
3	6000	2
4	8000	3
5	10000	4
6	4000	6

Figure 9

End of Simulation Proppant Volume Fraction for Proppant #1 (pounds per gallon)







Figure 10

Individual Time Step Report Proppant Concentration (pounds per square foot)



3. Navajo E: 5790-5870 ft: The simulation shows that this zone will not be adequately stimulated from the treatment through the Navajo A perforations.

Table 3

Fluid: 21,000 gal of 35 lb/1000 gal Borate Gel -Low Fluid Loss

Proppant: 58,000 lb 20/40 sand

Treatment: Pump down Tubing at 10 BPM.

Stage	Volume gallons	Sand Concentration lb/gallon
1	4000	0
2	3000	1
3	3000	2
4	3000	3
5	6000	4
6	2000	6

The primary factor significantly limiting extension in the primary zone is fluid loss. Therefore 3% hydrocarbon should be evaluated for additional fluid loss control. The proppant distribution at the end of the simulation is given in figure 11. The complete simulation is given in Appendix D.


4. Navajo B-D: 5650-5770 ft: If the fracturing pressure during the Navajo E treatment decreases dramatically as predicted in figure 12, then these zones will be stimulated by both stimulation treatments (Navajo A and Navajo E) and will only need to be broken down after perforating. A careful analysis of the pressures will be required in the event that the treatment in Navajo E screens out due to excessive leak-off which is highly possible. That is why the treatments are recommended down open ended tubing so that pressure can be carefully monitored on the annulus. If the pressure in the Navajo treatment does not decline significantly, then some of the non-permeable stringers are behaving as barriers to fracture height growth and the B, C and D zones will need to be stimulated separately as a group, probably perforated in the Navajo C with a similiar treatment as used in the Navajo E.


Stimulation Procedure:

- 1. Perforate and fracture stimulate the Wingate down open ended tubing.
- 2. Plug back with sand in the casing and fracture stimulate the Navajo E down open ended tubing.
- 3. Evaluate treatment pressure and either perforate and break-down Navajo D, C and B or fracture stimulate through perforations in the Navajo C.
- 4. Plub back with sand in the casing and fracture stimulate the Navajo A down casing.

Figure 11

End of Simulation Proppant Concentration (pounds per square foot)





Well: D-3

Set: RGU3


Run: 01

Page: 4

Figure 12

Net Pressure (BHP - Closure) Pressure (PSI) vs Time (Minutes)

4017 PSI Closure Pressure



GOHFER



GRID ORIENTED HYDRAULIC FRACTURE EXTENSION REPLICATOR

LICENSED TO: STIM-LAB, Incorporated

A FRACTURING TREATMENT DESIGN PREPARED FOR: APPENDIX A: WINGATE STEPRATE TEST

Company:

River Gas Corporation

Well:

D-3

Field:

Drunkards Wash

Formation:

Navajo

Section:

18

Township:

15 s

Range:

10 e

County:

Carbon

State:

Utah

File References:

Set: RGU1

Run: 13

This information is presented in good faith, but no warranty is given by the licensee, and the licensee assumes no liability for advice or recommendations made concerning results to be obtained from the use of any product or services. The results given are estimates based on calculations produced by a computer model including various assumptions on the well, reservoir and treatment. The results depend on the input data provided by the Operator. Estimates as to unknown data can be no more accurate than the model, the assumptions, and such input data. The information presented is the licensee's best estimate of the actual result that may be achieved and should be used for comparison purposes rather than absolute values. The quality of input data, and hence results, may be improved through the use of certain tests and procedures which the licensee can assist in selecting. The Operator has superior knowledge of the well, the reservoir, the field and the conditions affecting them. If the Operator is aware of any conditions whereby a neighboring well or wells might be affected by the treatment proposed herein, it is the Operator's responsibility to notify the owner or owners of the well accordingly.

Prices quoted are estimates only and are good for 30 days from the date of issue. Actual charges may vary depending upon time, equipment, and material ultimately required to perform these services.

Freedom from infringement of patents of the licensee or others is not to be inferred.





5695 Ft

Input Array of Formation Properties

Layer	Poisson's Ratio	Young's Modulus (psi)	Net Closure Stress (psi)	Tensile Strength (psi)	Permeability (md)	Porosity (Fraction)	Reservoir Pore Pressure (psi)	Cw Sqrt(min)
1	0.26	4.70E+06	1588.85	400.00	5.000	0.15	2226.90	0.0080
2	0.26	4.90E+06	1619.13	400.00	0.000	0.00	2234.70	0.0000
3	0.25	5.00E+06	1610.96	400.00	5.000	0.15	2242.50	0.0080
4	0.25	5.40E+06	1617.00	400.00	0.000	0.00	2250.30	0.0000
5	0.23	6.20E+06	1651.89	400.00	5.000	0.15	2258,10	0.0080
6	0.28	4.20E+06	1624.80	400.00	5.000	0.15	2265.90	0.0080
7	0.27	4.00E+06	1576.44	400.00	5.000	0.15	2273.70	0.0080
8	0.28	4.40E+06	1715.39	400.00	5.000	0.15	2281.50	0.0080
9	0.28	4.00E+06	1640.27	600.00	0.000	0.00	2289.30	0.0000
10	0.24	5.70E+06	1654.55	400.00	5.000	0.15	2297.10	0.0080
11	0.27	5.00E+06	1697,42	400.00	0.000	0.00	2304.90	0.0000
12	0.24	6.90E+06	1793.16	400.00	0.000	0.00	2312.70	0.0000
13	0.22	7.30E+06	1775.27	400.00	0.000	0.00	2320.50	0.0000
14	0.23	8.20E+06	1920.04	650.00	0.000	0.00	2328.30	0.0000
15	0.22	7.90E+06	1860.15	400.00	0.000	0.00	2336.10	0.0000
16	0.25	5.80E+06	1769.24	400.00	5,000	0.15	2343.90	0.0080
17	0,29	4.00E+06	1736.49	400.00	5.000	0.15	2351.70	0.0080
18	0.28	4.00E+06	1654.33	400.00	5.000	0.15	2359.50	0.0080
19	0.24	5.70E+06	1689.22	400.00	0.000	0.00	2367.30	0.0000
20	0.22	7.60E+06	1838.36	400.00	0.000	0.00	2375.10	0.0000
21	0.23	6.80E+06	1788.20	400.00	0.000	0.00	2382.90	0.0000
22	0.23	7.20E+06	1818.38	400.00	0.000	0.00	2390.70	0.0000
23	0.23	7.20E+06	1821.92	400.00	0.000	0.00	2398.50	0.0000
_24	0.22	7.10E+06	1762.10	400.00	0.000	0.00	2406.30	0.0000
25	0.22	7.80E+06	1881.56	400.00	0.000	0.00	2414.10	0.0000
26	0.21	7.80E+06	1834.89	400.00	0.000	0.00	2421.90	0.0000
27	0.22	7.30E+06	1798.13	400.00	0.000	0.00	2429.70	0.0000
28	0.22	7.30E+06	1826.88	400.00	0.000	0.00	2437.50	0.0000
29	0.22	6.80E+06	1765.33	400.00	0.000	0.00	2445.30	0.0000
30	0.22	7.40E+06	1846.77	400.00	0.000	0.00	2453.10	0.0000

Node Size (ft): 20

Treatment Design

STAGE NUMBER	SUBSTEP	PROPPANT NAME	PROPPANT CONC (lb/gal)	FLUID VOLUME (gallons)	FLUID NAME	SLURRY RATE
1	25	20/40 Ottawa	0	4120	Water 120 000 none 00.00	(BPM) 3
2	10	20/40 Ottawa	0	1680	Water 120 000 none 00.00	4
3	10	20/40 Ottawa	00	2100	Water 120 000 none 00.00	5
4	5	20/40 Ottawa	00	2520	Water 120 000 none 00.00	6
5	5	20/40 Ottawa	0	3440	Water 120 000 none 00.00	8.2
6	5	20/40 Ottawa	0	5145	Water 120 000 none 00.00	12.3
7	10	20/40 Ottawa	00	6879	Water 120 000 none 00.00	16.4
8	10	20/40 Ottawa	00	8543	Water 120 000 none 00.00	20.3
9	15	20/40 Ottawa	00	10435	Water 120 000 none 00.00	24.2
10	100	20/40 Ottawa	0	60	Water 120 000 none 00.00	1

Fluid Properties

Fluid Name	Zero Shear Viscosity (cp)	n'	Onset of Low Shear Plateau (1/sec)	Onset of High Shear Plateau (1/sec)
Water 120 000 none 00.00	.8	1	10	100000000

Viscosity at Reservoir Temperature = 60 °F


				
Shear Rate (1/sec)	0.01	40	170	511
				
Apparent Viscosity (cp)	1	1	1	1

Proppant Properties


Proppant Name	Density (g/cc)	Size (in)
20/40 Ottawa	2.65	.03

Net Pressure (BHP - Closure) Pressure (PSI) vs Time (Minutes)


9 PSI Closure Pressure



Fracture Growth Fracture Size vs Time (Minutes)



End of Pumping Fracture Width (inches)





GOHFER



GRID ORIENTED HYDRAULIC FRACTURE EXTENSION REPLICATOR LICENSED TO: STIM-LAB, Incorporated

A FRACTURING TREATMENT DESIGN PREPARED FOR: APPENDIX B: WINGATE STIMULATION RECOMMENDATION

Company:

River Gas Corporation

Well:

D-3

Field:

Drunkards Wash

Formation:

Navajo

Section:

18

Township:

15 S

Range:

10 E

County:

Carbon

State:

Utah

File References:

Set: RGU2

Run: 05

This information is presented in good faith, but no warranty is given by the licensee, and the licensee assumes no liability for advice or recommendations made concerning results to be obtained from the use of any product or services. The results given are estimates based on calculations produced by a computer model including various assumptions on the well, reservoir and treatment. The results depend on the input data provided by the Operator. Estimates as to unknown data can be no more accurate than the model, the assumptions, and such input data. The information presented is the licensee's best estimate of the actual result that may be achieved and should be used for comparison purposes rather than absolute values. The quality of input data, and hence results, may be improved through the use of certain tests and procedures which the licensee can assist in selecting. The Operator has superior knowledge of the well, the reservoir, the field and the conditions affecting them. If the Operator is aware of any conditions whereby a neighboring well or wells might be affected by the treatment proposed herein, it is the Operator's responsibility to notify the owner or owners of the well accordingly.

Prices quoted are estimates only and are good for 30 days from the date of issue. Actual charges may vary depending upon time, equipment, and material ultimately required to perform these services.

Freedom from infringement of patents of the licensee or others is not to be inferred.





Page: 2

Input Array of Formation Properties

Layer	Poisson's Ratio	Young's Modulus (psi)	Net Closure Stress (psi)	Tensile Strength (psi)	Permeability (md)	Porosity (Fraction)	Reservoir Pore Pressure (psi)	Cw Sqrt(min)
1	0.26	4.70E+06	1588.85	350.00	5.000	0.15	2226.90	0.0031
2	0.26	4.90E+06	1619.13	350.00	0.000	0.00	2234.70	0.0000
3	0.25	5.00E+06	1610.96	350.00	5.000	0.15	2242.50	0.0031
4	0.25	5.40E+06	1617.00	350.00	0.000	0.00	2250.30	0.0000
5	0.23	6.20E+06	1651.89	350.00	5.000	0.15	2258.10	0.0031
_6	0.28	4.20E+06	1624.80	350.00	5.000	0.15	2265.90	0.0031
7	0.27	4.00E+06	1576.44	350.00	5.000	0.15	2273.70	0.0031
8	0.28	4.40E+06	1715.39	350.00	5.000	0.15	2281.50	0.0031
9	0.28	4.00E+06	1640.27	450.00	0.000	0.00	2289.30	0.0000
10	0.24	5.70E+06	1654.55	350.00	5.000	0.15	2297.10	0.0031
	0.27	5.00E+06	1697.42	350.00	0.000	0.00	2304.90	0.0000
12	0.24	6.90E+06	1793.16	350.00	0.000	0.00	2312.70	0.0000
13	0.22	7.30E+06	1775.27	350.00	0.000	0.00	2320.50	0.0000
14	0.23	8.20E+06	1920.04	550.00	0.000	0.00	2328.30	0.0000
15	0.22	7.90E+06	1860.15	350.00	0.000	0.00	2336.10	0.0000
16	0.25	5.80E+06	1769.24	350.00	5.000	0.15	2343.90	0.0031
17	0.29	4.00E+06	1736.49	350.00	5.000	0.15	2351.70	0.0031
18	0.28	4.00E+06	1654.33	350,00	5.000	0.15	2359.50	0.0031
19	0.24	5.70E+06	1689.22	350.00	0.000	0.00	2367.30	0.0000
20	0.22	7.60E+06	1838.36	350.00	0.000	0.00	2375.10	0.0000
21	0.23	6.80E+06	1788.20	350.00	0.000	0.00	2382.90	0.0000
22	0.23	7.20E+06	1818.38	350.00	0.000	0.00	2390.70	0.0000
23	0.23	7.20E+06	1821.92	350.00	0.000	0.00	2398.50	0.0000
24	0.22	7.10E+06	1762.10	350.00	0.000	0.00	2406.30	0.0000
25	0.22	7.80E+06	1881.56	350.00	0.000	0.00	2414.10	0.0000
26	0.21	7.80E+06	1834.89	350.00	0.000	0.00	2421.90	0.0000
27	0.22	7.30E+06	1798.13	350.00	0.000	0.00	2429.70	0.0000
28	0,22	7.30E+06	1826.88	350.00	0.000	0.00	2437.50	0.0000
29	0.22	6.80E+06	1765.33	350.00	0.000	0.00	2445.30	0.0000
30	0.22	7.40E+06	1846.77	350.00	0.000	0.00	2453.10	0.0000

Node Size (ft): 20

Treatment Design

STAGE NUMBER	SUBSTEP	PROPPANT NAME	PROPPANT CONC (lb/gal)	FLUID VOLUME (gallons)	FLUID NAME	SLURRY RATE (BPM)
11	10	20/40 Ottawa	0	2000	40# Guar 000 000 none 00.00	10
2	10	20/40 Ottawa	2	500	40# Guar 000 000 none 00.00	10
33	10	20/40 Ottawa	3	500	40# Guar 000 000 none 00.00	10
4	10	20/40 Ottawa	4	1000	40# Guar 000 000 none 00.00	10
5	10	20/40 Ottawa	6	6000	40# Guar 000 000 none 00.00	10
6	100	20/40 Ottawa	0	60	40# Guar 000 000 none 00.00	0

Fluid Properties

Fluid Name	Zero Shear Viscosity (cp)	n'	Onset of Low Shear Plateau (1/sec)	Onset of High Shear Plateau (1/sec)
40# Guar 000 000 none 00.00	220	.58	20	1000000

Viscosity at Reservoir Temperature = 60 °F

Shear Rate (1/sec)	_0.01	40	170	511
Apparent Viscosity (cp)	214	91	55	36

Proppant Properties

Proppant Name	Density (g/cc)	Size (in)
20/40 Ottawa	2.65	.03

Treatment Design

STAGE NUMBER	SUBSTEP	PROPPANT NAME	PROPPANT CONC (lb/gal)	FLUID VOLUME (gallons)	FLUID NAME	SLURRY RATE (BPM)
11	10	20/40 Ottawa	0	2000	40# Guar 000 000 none 00.00	10
2	10	20/40 Ottawa	2	500	40# Guar 000 000 none 00.00	10
3	10	20/40 Ottawa	3	500	40# Guar 000 000 none 00.00	10
4	10	20/40 Ottawa	4	1000	40# Guar 000 000 none 00.00	10
5	10	20/40 Ottawa	6	6000	40# Guar 000 000 none 00.00	10
6	100	20/40 Ottawa	0	60	40# Guar 000 000 none 00.00	0

Fluid Properties

Fluid Name	Zero Shear Viscosity (cp)	n'	Onset of Low Shear Plateau (1/sec)	Onset of High Shear Plateau (1/sec)
40# Guar 000 000 none 00.00	220	.58	20	1000000

Viscosity at Reservoir Temperature = 60 °F


Shear Rate (1/sec)	0.01	40	170	511
Apparent Viscosity (cp)	214	91	55	36

Proppant Properties

Proppant Name	Density (g/cc)	Size (in)
20/40 Ottawa	2.65	.03

Net Pressure (BHP - Closure) Pressure (PSI) vs Time (Minutes)


12 PSI Closure Pressure




Set: RGU2


Run: 05


Page: 5







End of Pumping Fracture Width (inches)







End of Pumping Proppant Volume Fraction for Proppant #1 (pounds per gallon)







End of Simulation Fracture Width (inches)







End of Simulation Proppant Volume Fraction for Proppant #1 (pounds per gallon)





End of Simulation Proppant Concentration (pounds per square foot)





GOHFER



GRID ORIENTED HYDRAULIC FRACTURE EXTENSION REPLICATOR

LICENSED TO: STIM-LAB, Incorporated

A FRACTURING TREATMENT DESIGN PREPARED FOR: APPENDIX C: NAVAJO A STIMULATION RECOMMENDATION

Company:

River Gas Corporation

Well:

D-3

Field:

Drunkards Wash

Formation:

Navajo

Section:

18

Township:

15 s

Range:

10 e

County:

Carbon

State:

Utah

File References:

Set: RGU4

Run: 05

This information is presented in good faith, but no warranty is given by the licensee, and the licensee assumes no liability for advice or recommendations made concerning results to be obtained from the use of any product or services. The results given are estimates based on calculations produced by a computer model including various assumptions on the well, reservoir and treatment. The results depend on the input data provided by the Operator. Estimates as to unknown data can be no more accurate than the model, the assumptions, and such input data. The information presented is the licensee's best estimate of the actual result that may be achieved and should be used for comparison purposes rather than absolute values. The quality of input data, and hence results, may be improved through the use of certain tests and procedures which the licensee can assist in selecting. The Operator has superior knowledge of the well, the reservoir, the field and the conditions affecting them. If the Operator is aware of any conditions whereby a neighboring well or wells might be affected by the treatment proposed herein, it is the Operator's responsibility to notify the owner or owners of the well accordingly.

Prices quoted are estimates only and are good for 30 days from the date of issue. Actual charges may vary depending upon time, equipment, and material ultimately required to perform these services.

Freedom from infringement of patents of the licensee or others is not to be inferred.






Input Array of Formation Properties

5245 Ft	Layer	Poisson's Ratio	Young's Modulus (psi)	Net Closure Stress (psi)	Tensile Strength (psi)	Permeability (md)	Porosity (Fraction)	Reservoir Pore Pressure	Cw Sqrt(min)
	1	0.29	5.62E+06	1978.27	436.20	0.000	0.00	(psi)	
	2	0.30	5.62E+06	2044.99	436,20	0.000	0.00	1953.90	0.0000
	3	0.32	1.10E+07	2879.65	436.20	0.000	0.00	1961.70	0.0000
	4	0.29	7.77E+06	2273.22	436.20	0.000	0.00	1969.50	0.0000
	5	0.27	7.77E+06	2158.39	436.20	0.000	0.00	1977.30	0.0000
	6	0.29	9.38E+06	2493.18	436.20	0.000	0.00	1985.10	0.0000
	7	0.30	9.38E+06	2561.13	436.20	0.000	0.00	1992.90	0.0000
	8	0.30	9.38E+06	2566.36	436.20	0.000	0.00	2000.70	0.0000
	9	0.31	9.92E+06	2706.88	436.20	0.000	0.00	2008.50	0.0000
	10	0.28	8.85E+06	2381.18	436.20	0.000	0.00	2016.30	0.0000
	11	0.26	7.23E+06	2056.63	436.20	0.000	0.00	2024.10	0.0000
	12	0.21	6.95E+06	1751.55	436.20	0.000	0.00	2031.90	0.0000
	13	0.27	8.10E+06	2267.74	436.20	0.000	0.00	2039.70	0.0000
	14	0.30	9.40E+06	2599.73	436.20	0.000	0.00	2047.50	0.0000
	15	0.24	1.02E+07	2345.02		0.000	0.00	2055.30	0.0000
	16	0.20	8.40E+06	1927.24	436.20 436.20	0.000	0.00	2063.10	0.0000
	17	0.21	6.20E+06	1670.27		5.000	0,15	2070.90	0.0019
	18	0.22	5.80E+06	1674.47	436.20	37.500	0.15	2078.70	0.0019
	19	0.19	7.70E+06	1794.49	436.20 436.20	15.000	0.15	2086.50	0.0019
	20	0.19	7.30E+06	1745.45		0.000	0.00	2094.30	0.0000
	21	0.21	8.30E+06	1956.24	436.20	0.000	0.00	2102.10	0.0000
	22	0.22	6.00E+06	1714.24	436.20	5.000	0.15	2109.90	0.0019
	23	0.25	4.30E+06	1696.92	436.20	0.000	0.00	2117.70	0.0000
	24	0.26	4.80E+06	1796.35	436.20 436.20	50.000	0.15	2125.50	0.0019
	25	0.25	5.60E+06	1814.73	436.20	20.000	0.15	2133.30	0.0019
	26	0.27	4.00E+06	1763.15		0.000	0.00	2141.10	0.0000
	27	0.22	7.50E+06	1926.44	436.20	10.000	0.15	2148.90	0.0019
	28	0.25	4.40E+06	1730.80	436.20 436.20	0.000	0.00	2156.70	0.0000
	29	0.28	4.00E+06	1808.78		5,000	0.15	2164.50	0.0019
	30	0.28	4.30E+06	1852.41	436.20 436.20	10.000	0.15	2172.30	0.0019
	31	0.28	4.10E+06	1897.05	436.20	5.000	0.15	2180.10	0.0019
	32	0.25	5.70E+06	1916.50		20.000	0.15	2187.90	0.0019
	33	0.26	4.00E+06	1762.62	436.20	10.000	0.15	2195.70	0.0019
	34	0.24	6.50E+06	1937.22	436.20	0.000	0.00	2203.50	0.0000
	35	0.23	7.30E+06	1985.76	436.20	0.000	0.00	2211.30	0.0000
	36	0.22	7.60E+06	1970.41	436.20	0.000	0.00	2219.10	0.0000
	37	0.24	7.80E+06	2087.72	436.20	0.000	0.00	2226.90	0.0000
	38	0.22	7.70E+06	1961.65	650.00	0.000	0.00	2234.70	0.0000
	39	0.28	4.20E+06	1948.96	436,20	0.000	0.00	2242.50	0.0000
	40	0.28	4.00E+06	1946.96	436.20	0.000	0.00	2250.30	0.0000
5 Ft				1921.02	436.20	0.000	0.00	2258.10	0.0000

Node Size (ft): 20

Input Properties Permeability (md)



Treatment Design

STAGE NUMBER	SUBSTEP	PROPPANT NAME	PROPPANT CONC (lb/gal)	FLUID VOLUME (gallons)	FLUID NAME	SLURRY RATE (BPM)
11	5	20/40 Ottawa	0	8000	PCPPH3895 160 015 sp 01.00	
2	5	20/40 Ottawa	1	5000	PCPPH3895 160 015 sp 01.00	60
3	5	20/40 Ottawa	2	6000	PCPPH3895 160 015 sp 01.00	60
4	5	20/40 Ottawa	3	8000	PCPPH3895 160 015 sp 01.00	60
5	5	20/40 Ottawa	4	10000	PCPPH3895 160 015 sp 01.00	60
6	5	20/40 Ottawa	6	12000	PCPPH3895 160 015 sp 01.00	60
7	5	20/40 Ottawa	8	4000		60
8	100	20/40 Ottawa	0	20	PCPPH3895 160 015 sp 01.00	60
9	30	20/40 Ottawa	0	300	PCPPH3895 160 015 sp 01.00 PCPPH3895 160 015 sp 01.00	1

Fluid Properties

Fluid Name	Zero Shear Viscosity (cp)	n'	Onset of Low Shear Plateau (1/sec)	Onset of High Shear Plateau
PCPPH3895 160 015 sp 01.00	1000	.41	20	(1/sec) 1000000

Viscosity at Reservoir Temperature = 60 °F


Shear Rate (1/sec)	0.01	40	170	511
Apparent Viscosity (cp)	993	374	176	94

Proppant Properties


Proppant Name	Density (g/cc)	Size (in)
20/40 Ottawa	2.65	
		03

Net Pressure (BHP - Closure) Pressure (PSI) vs Time (Minutes)


3998 PSI Closure Pressure




End of Pumping Fracture Width (inches)




End of Pumping Proppant Volume Fraction for Proppant #1 (pounds per gallon)




End of Simulation Fracture Width (inches)






End of Simulation Proppant Volume Fraction for Proppant #1 (pounds per gallon)



Individual Time Step Report Proppant Concentration (pounds per square foot)



GOHFER



GRID ORIENTED HYDRAULIC FRACTURE EXTENSION REPLICATOR

LICENSED TO: STIM-LAB, Incorporated

A FRACTURING TREATMENT DESIGN PREPARED FOR: APPENDIX D: NAVAJO E STIMULATION RECOMMENDATION

Company:

River Gas Corporation

Well:

D-3

Field:

Drunkards Wash

Formation:

Navajo

Section:

18

Township:

15 s

Range:

10 e

County:

Carbon

State:

Utah

File References:

Set: RGU3

Run: 01

This information is presented in good faith, but no warranty is given by the licensee, and the licensee assumes no liability for advice or recommendations made concerning results to be obtained from the use of any product or services. The results given are estimates based on calculations produced by a computer model including various assumptions on the well, reservoir and treatment. The results depend on the input data provided by the Operator. Estimates as to unknown data can be no more accurate than the model, the assumptions, and such input data. The information presented is the licensee's best estimate of the actual result that may be achieved and should be used for comparison purposes rather than absolute values. The quality of input data, and hence results, may be improved through the use of certain tests and procedures which the licensee can assist in selecting. The Operator has superior knowledge of the well, the reservoir, the field and the conditions affecting them. If the Operator is aware of any conditions whereby a neighboring well or wells might be affected by the treatment proposed herein, it is the Operator's responsibility to notify the owner or owners of the well accordingly.

Prices quoted are estimates only and are good for 30 days from the date of issue. Actual charges may vary depending upon time, equipment, and material ultimately required to perform these services.

Freedom from infringement of patents of the licensee or others is not to be inferred.





Input Array of Formation Properties

-445 Ft	Layer	Poisson's Ratio	Young's Modulus (psi)	Net Closure Stress (psi)	Tensile Strength (psi)	Permeability (md)	Porosity (Fraction)	Reservoir Pore Pressure (psi)	Cw Sqrt(min)
	11	0.25	7.60E+06	1973.98	436.20	0.000	0.00	2129.40	0.0000
	2	0.21	6.95E+06	1672.47	436.20	0.000	0.00	2137.20	0.0000
	3	0.27	8.10E+06	2154.90	436.20	0.000	0.00	2145.00	0.0000
	4	0.30	9.40E+06	2472.23	436.20	0.000	0.00	2152,80	0.0000
	5	0.24	1.02E+07	2251.07	436.20	0.000	0.00	2160.60	0.0000
	6	0.20	8.40E+06	1850.53	436.20	5.000	0.15	2168.40	0.0019
	7	0.21	6.20E+06	1591.19	436.20	37.500	0.15	2176.20	0.0019
	8	0.22	5.80E+06	1590.56	436.20	15.000	0.15	2184.00	0.0019
	9	0.19	7.70E+06	1722.43	436.20	0.000	0.00	2191.80	0.0000
	10	0.19	7.30E±06	1673.38	436.20	0.000	0.00	2199.60	0.0000
	11	0.21	8.30E+06	1877.16	436.20	5.000	0.15	2207.40	0.0019
	12	0.22	6.00E+06	1630.33	436.20	0.000	0.00	2215.20	0.0000
	13	0.25	4.30E+06	1595.09	436.20	50.000	0.15	2223.00	0.0019
	14	0.26	4.80E+06	1691.83	436.20	20.000	0.15	2230.80	0.0019
	15	0.25	5.60E+06	1718.19	436.20	0.000	0.00	2238.60	0.0000
	16	0.27	4.00E+06	1653.11	436.20	10.000	0.15	2246.40	0.0019
	17	0.22	7.50E+06	1842.53	436.20	0.000	0.00	2254.20	0.0000
	18	0.25	4.40E+06	1628.97	436.20	5.000	0.15	2262.00	0.0019
	19	0.28	4.00E+06	1695.94	436.20	10.000	0.15	2269.80	0.0019
	20	0.28	4.30E+06	1739.57	436.20	5.000	0.15	2277.60	0.0019
	21	0.28	4.10E+06	1778.47	436.20	20.000	0.15	2285.40	0.0019
	22	0.25	5.70E+06	1814.67	436.20	10.000	0.15	2293.20	0.0019
	23	0.26	4.00E+06	1655.35	436,20	0.000	0.00	2301.00	0.0000
	24	0.24	6.50E+06	1843.27	436.20	0.000	0.00	2308.80	0.0000
	25	0.23	7.30E+06	1896.90	436.20	0.000	0.00	2316.60	0.0000
	26	0.22	7.60E+06	1886.50	436.20	0.000	0.00	2324.40	0.0000
	27	0.24	7.80E+06	1996.33	650.00	0.000	0.00	2332.20	0.0000
	28	0.22	7.70E+06	1880.17	436.20	0.000	0.00	2340.00	0.0000
	29	0.28	4.20E+06	1830.37	436.20	0.000	0.00	2347.80	0.0000
15 Ft	30 Node Size	0.28 (ft) : 20	4.00E+06	1809.24	436.20	0.000	0.00	2355.60	0.0000

Node Size (ft): 20

Treatment Design

	T T					
STAGE NUMBER	SUBSTEP	PROPPANT NAME	PROPPANT CONC (lb/gal)	FLUID VOLUME (gallons)	FLUID NAME	SLURRY RATE (BPM)
1	5	20/40 Ottawa	0	4000	PCPPH3895 160 015 sp 01.00	10
2	5	20/40 Ottawa	11	3000	PCPPH3895 160 015 sp 01.00	10
3	5	20/40 Ottawa	2	3000	PCPPH3895 160 015 sp 01.00	10
4	5	20/40 Ottawa	3	3000	PCPPH3895 160 015 sp 01.00	10
5	5	20/40 Ottawa	4	6000	PCPPH3895 160 015 sp 01.00	10
6	5	20/40 Ottawa	6	2000	PCPPH3895 160 015 sp 01.00	10
7	100	20/40 Ottawa	0	120	PCPPH3895 160 015 sp 01.00	1

Fluid Properties

Fluid Name	Zero Shear Viscosity (cp)	n'	Oriset of Low Shear Plateau (1/sec)	Onset of High Shear Plateau (1/sec)
PCPPH3895 160 015 sp 01.00	1000	.41	20	1000000

Viscosity at Reservoir Temperature = 60 °F


Shear Rate (1/sec)	0.01	40	170	511
Apparent Viscosity (cp)	993	374	176	94

Proppant Properties


Proppant Name	Density (g/cc)	Size (in)
20/40 Ottawa	2.65	.03


Net Pressure (BHP - Closure) Pressure (PSI) vs Time (Minutes)

4017 PSI Closure Pressure





End of Pumping Fracture Width (inches)







End of Pumping Proppant Volume Fraction for Proppant #1 (pounds per gallon)







End of Simulation Fracture Width (inches)







End of Simulation Proppant Volume Fraction for Proppant #1 (pounds per gallon)





End of Simulation Proppant Concentration (pounds per square foot)





14. I hereby certify that the foregoing is true and corpe Name & Signature

Dennis Plowman

Title Reservoir Techniciamate 5/16/96

(State Use Only)

Utah Division of Oil, Gas and Mining

Attachment to Sundry Notice and Report on Wells dated May 16, 1996.

Subject: Request of River Gas Corp. for permission to perforate Navajo Formation (A zone) and swab sample.

D-3 Well

NW/SW, sec. 18, T15S, R10E, Carbon, County

API = 43-007-30290

Conditions of Approval:

- 1. Measure water sample conductivity at the well on each swab run.
- 2. Swab until conductivity of sample stabilizes and a good representative formation water sample can be taken and sent to a lab.
- 3. Check with the DOGM UIC section (if rep. not on site) before discontinuing swabbing operations.

schuppbeford

Wireline & Testing

Schlumberger Weil Services 6090 Greenwood Pizza Bivd Englewood CO 80111 (303) 843-9490

13 May 1996

To: John Hollingshead From: Garry Williams Subject: USIT on D-3 well

An overview interpretation of the Ultra Sonic Imager Cement Evaluation log on the above well is as follows;

0 to 462' - No fluid in casing to get a sonic signal.

462' to 2200' - Evidence of cement in place but of very low compressive strength.

Possibly contaminated lead cement.

2200' to 2900' - Cement in place is of better quality and higher compressive strength than above.

2900' to 3770' - Cement in place is of better quality and higher compressive strength than above.

3770' to 4090' - Lower compressive strength than the cement above. Looks like an over displacement of stage 2 through the DV tool (at 4090').

4090' to 6420' - Cement is in place with evidence of minor channels that consist of water and gas cut cement. An example of such channeling is from 5560' to 5760'.

From experience it would be very difficult to squeeze cement into such a channel of water & gas cut cement.

A standard CBL log, which has no radial definition, would indicate a high amplitude casing signal across this type of zone indicating poor to no bonding which people have attempted to squeeze without success.

The USIT has the ability to evaluate coment quality radially as opposed to

The USIT has the ability to evaluate cement quality radially as opposed to the standard CBL which is an average of the total 360 degrees.

I am also enclosing a diagram which shows the approximate mrayl cut-off values for the gas to liquid to cement interfaces.

Garry Williams


3034863285

05:37

88/38/1994

HCI Com

USI Cement Interpretation



AJH- SEP-94



AMERICAN WEST **ANALYTICAL LABORATORIES**

INORGANIC ANALYSIS REPORT

Client: State of Utah - Oil, Gas, and Mining

Date Sampled: May 22, 1996 Lab Sample ID.: 25984-01

Field Sample ID.: River Gas D-3

Contact: Dan Jarvis

Date Received: May 22, 1996 Received By: Laurie Hastings

Set Description: One Water Sample

	Analytical Results			
460 W. 42600 Same	TOTAL METALS	Method <u>Used:</u>	Reporting Limit: mg/L	Amount <u>Detected:</u> mg/L
463 West 3600 South Salt Lake City, Utah 84115	Calcium	6010	0.05	1,700.
	Magnesium	6010	0.05	350.
	Potassium	6010	0.1	2,200.
(801) 263-8686 Fax (801) 263-8687	Sodium	6010	0.1	57,000.
	OTHER CHEMISTRIES			
	Bicarbonate (as CaCO ₃)	310.1	10.	830.
	Chloride	4500 CLB	0.5	70,000.
	† Conductivity	120.1	10.	89,000.
	pН	150.1	0.1	6.0
	Sulfate	375.4	5.0	3,500.
	TDS	160.1	1.0	130,000.

Released by:

THIS REPORT IS PROVIDED POR THE EXCLUSIVE USE OF THE ADDRESSEE. PRIVILEGES OF SESTIONED ALSO HAVE AMENDED OF THIS COMPANY DEOLNY MEMBER OF ITS STAFF, OR REPRODUCTION OF THIS REPORT IN CONNECTION WITH THE ADVERTISEMENT, PROMOTION OR SALE OF ANY PRODUCT OR PROCESS OR IN CONNECTION WITH THE RE-PUBLICATION OF THIS REPORT FOR ANY PURPOSE THAN FOR THE ADDRESSEE WILL BE GRANTED ONLY ON CONTRACT. THIS COMPANY ACCEPTS NO RESPONSIBILITY EXCEPT FOR THE DUE PERFORMANCE OF INSPECTION AND/OR ANALYSIS IN GOOD FAITH AND ACCORDING TO THE RULES OF THE TRADE AND OF SCIENCE.

Conductivity reported in µmhos/cm @ 25 C.

LOGIN CHAIN OF CUSTODY REPORT (ln01) May 22 1996, 02:36 pm

Login Number: L25984 Account: OGM100 State of Utah - Oil, Gas, and Mining

Site : RIVER GAS D-3

Contact: Dan Jarvis

L25984-1		RIVER G		22-MAY-96 22-MAY-96 3	1-MAY-96
PO# 2004		KIVEK G	ns D+3		
Water	S	BICARB	Bicarbonate (as CaCO3)	Expires: 05-JUN-96	
Water	S	CA	Calcium	Expires:18-NOV-96	
Vater	s	CL	Chloride	Expires:19-JUN-96	
ater	s	COND	Conductivity (Specific)	Expires:19-JUN-96	
later	s	DIG-MET	Total Metal Digestion	Expires:18-NOV-96 may 22	1 Contain
later	s	K	Potassium	Expires:18-NOV-96	
later	s	MG	Magnesium	Expires: 18-NOV-96	
ater	s	NA.	Sodium	Expires:18-NOV-96	
ater	s	PH	рН	Expires:23-MAY-96	
ater	s	SO4	Sulfate	Expires:19-JUN-96	
iater	S	TDS	Total dissolved solids	Expires:29-MAY-96	

Page 1	
Signature:	
Date:	

ADDRESS 355 W. North	Temple 03 Tr	ad A	AMERICA WE: ANALYTICA LABORATORII 463 West 3600 Sou	IN WIND ST A	CHAIN	OF CUSTODY
5/c. Ut-8	-3940 -3940	14	LABORATORII 463 West 3600 Sou Salt Lake City, Ut	ES (801) 2 (801) 2	263-8686 LAB #_	25984
CONTACT DAN JARVIS				15 (1 Fax (801) 2	///////////////////////////////////////	
SITERIVEY FORS D-3 SAMPLER'S SIGNATURE	4-					TURN AROUND TIMES I = Priority I II = Priority II III = 5 Day Rush S = Standard
SAMPLE ID	SAMPLE MATRIX			Y////	//////\\\	S = Standard COMMENTS
River GAS D-3	5/22 10:53 UATE					
,	7,000			_		· · · · · · · · · · · · · · · · · · ·
Quote # /P.O. # 200472		Relinquished By Sig	Jan	Date/Time 5/22/96	Received By: Signature	Date/Time
Special Instructions:		PRINT NAME AWILL J. JAEVIC Relinquished By Signature Date/Time			PRINT NAME Received By: Signature Date/Time	
			•	Date I line	Accessed by . Signature	Date I line
		PRINT NAME			PRINT NAME	
		Dispatched By: Signa	ture	Date/Time	Received for Laboratory By:	
		PRINT NAME			PRINT NAME LAW	

Michael O. Leavitt
Governor
Ted Stewart
Executive Director
James W. Carter
Division Director

355 West North Temple 3 Triad Center, Suite 350 Salt Lake City, Utah 84180-1203 801-538-5340 801-359-3940 (Fax) 801-538-5319 (TDD)

June 12, 1996

River Gas Corporation 511 Energy Center Blvd. Northport, Alabama 35476

Re:

<u>Drunkards Wash Unit, Utah D-3 Well, Section 18, Township 15 South, Range 10 East, Carbon County, Utah</u>

Gentlemen:

Pursuant to Utah Admin. Code R649-5-3-3, the Division of Oil, Gas and Mining (the "Division") issues its administrative approval for conversion of the referenced well to a Class II injection well. Accordingly, the following stipulations shall apply for full compliance with this approval:

- 1. Compliance with all applicable requirements for the operation, maintenance and reporting for Underground Injection Control ("UIC") Class II injection wells pursuant to Utah Admin. Code R649-1 et seq.
- 2. Conformance with all conditions and requirements of the complete application submitted by River Gas Corporation.

Enclosed with this letter is the Underground Injection Control Permit for this well. If you have any questions regarding this approval or the necessary requirements, please contact Dan Jarvis at this office.

Sincerely,

Associated Director

lwp

cc: Dan Jackson, Environmental Protection Agency

Bureau of Land Management, Moab





Michael O. Leavitt
Governor
Ted Stewart
Executive Director
James W. Carter
Division Director

355 West North Temple 3 Triad Center, Suite 350 Salt Lake City, Utah 84180-1203 801-538-5340 801-359-3940 (Fax) 801-538-5319 (TDD)

UNDERGROUND INJECTION CONTROL PERMIT

Cause No. UIC-166

Operator:

River Gas Corporation

Well:

Utah D-3

Location:

Section 18, Township 15 South, Range 10 East,

County: Carbon

API No.:

43-007-30290

Well Type:

Disposal

Stipulations of Permit Approval

- 1. Approval for conversion to Injection Well issued on June 12, 1996
- 2. Maximum Allowable Injection Pressure: 850 psig (this limitation can be increased when additional supportive data is submitted)
- 3. Maximum Allowable Injection Rate: (restricted by pressure limitation)
- 4. Injection Interval: 5550 feet to 6100 feet (Navajo and Wingate Formations)

Approved by:

R.J. Firth

Associate Director, Oil and Gas

12 June 1996

Date



To: John Hollingshead, River Gas

Date: June 17, 1996


Re: Analysis of the Post-Frac Water Injection Test on Well D-3

Completion History of D-3 Prior to the Post-Frac Injection Test

Formation	Perforation Interval (ft)	Stimulation	Date	Top Packer (ft)
Wingate	5997-6058	Fracture	May 24, 1996	5906
Navajo E	5872-5896	Fracture	May 25, 1996	5713
Navajo D	5736-5763			
Navajo C	5663-5728	Fracture	May 26, 1996	5527
Navajo B	5619-5627			•
Navajo A	5566-5567			
Navajo A	5561-5602	Fracture	May 29, 1996	

On June 2, 1996 a water injection test was conducted with all the perforations open. A total of 2350 barrels of KCl water were injected at rates from 5 to 28 BPM. The surface pressures and rates are shown in figure 1. Using the recorded bottom hole pressure, the traditional analysis of the step rate shows a fracture extension pressure of 4106 psi (figure 2). This corresponds to a surface fracture parting pressure of 1475 psi. In this particular test, the fracture opening was very distinct and confirmed the results of the conventional analysis of pressure versus rate. The data in figure 3 shows a distinct fracture opening at 4110 psi which is in complete agreement with the analysis in figure 2.

Figure 1: Surface Pressure and Injection Rate for Post Frac Injection Test on Salt Water Disposal Well D-3







Figure 2: Post-Frac Step Rate Test in D-3





The fracture extension pressure determined from the initial water injection test in the Wingate was 4438 psi which is a frac gradient of 0.735 at 6035 ft. The same gradient applied to the top depth of the Navajo A at 5561 ft would predict a fracture extension pressure of 4087, which is within 20 psi or 99.5% of the observed pressure 4106 psi. This gives a difference of 332 psi in the measured fracture extension pressures.


These data were also compared to the closure stress computed from the logs. The average closure stress from 6037-6057 ft was 4245 psi and the average closure stress from 5563-5583 ft was 3870 psi. The 20 ft average was used because the stress must be distributed over the fracture process zone which is estimated to be from 10-30 ft for this size fracture. This gives a calculated difference of 375 psi, which is a phenomenal agreement based on the assumptions, which are required to compute stress from the logs. The log calculations were normalized based on the injection pressures observed in the Wingate and no other adjustments were made to the stress predictions.

STATE OF	- UTAH	
DEPARTMENT OF	URAL RE	SOURCES
DIVISION OF ONE	AS AND	MINING

DIVISION OF OL, GAS AND MININ	or todoo boolgitation and certai Hamber
SUNDRY NOTICES AND REPORTS C	enter plugged and abandoned wells. 8. Unit or Communitization Agreement
Use APPLICATION FOR PERMIT—for such proportion of Well 1. Type of Well Gas XX Other (specify) Dispo	Drunkards Wash UTU 67921X 9. Well Name and Number
2. Name of Operator River Gas Corporation	Utah D-3 10. API Well Number 43-007-30290
3. Address of Operator 511 Energy Center Blvd. Northport, AL 3547 5. Location of Well	4. Telephone Number 11. Field and Pool or Wildcat
Footage : 1600' FSL & 1126' FWL QQ. Sec. T., R., M. : NW/SW, Sec 18, T15S, R10E 12 CHECK APPROPRIATE BOXES TO INDICATE NA	County: Carbon State: UTAH AEMBEOENOEICE-REPORT OR OTHER DATA
NOTICE OF INTENT (Submit in Duplicate)	SUBSEQUENT REPORT (Submit Original Form Only)
Abandonment New Construction Casing Repair Pull or Alter Casing Change of Plans Recompletion Shoot or Acidize Fracture Treat Vent or Flare Multiple Completion Water Shut-Off Other Request change of injection pressure	Abandonment * New Construction Casing Repair Pull or Alter Casing Change of Plans Shoot or Acidize Conversion to Injection Vent or Flare Fracture Treat Water Shut-Off Other
Approximate Date Work Will Start	Date of Work Completion Report results of Multiple Completions and Recompletions to different reservoirs

13. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

River Gas Corporation requests that the maximum allowable injection pressure for the Utah D-3 be changed from 850 psi to 1475 psi based on the analysis of the attached report.



on WELL COMPLETION OR RECOMPLETION AND LOG form. Must be accompanied by a cement verification report.

4.	ì	perepà ceu	tify that	the	foregoing	is true	and	copf	69

Name & Signature

Dennis Plowman

Title Reservoir Technician Date

(State Use Only)

APPROVED BY THE STATE OF UTAH DIVISION OF OIL, GAS, AND MINING

DIVISION OF OIL, GAS AND MINING UNDERGROUND INJECTION CONTROL PROGRAM

PERMIT STATEMENT OF BASIS

Applicant:

River Gas Corporation

Well: Utah D-3

Location:

Sec. 18, T15S, R10E,

API: 43-007-30290

Carbon, County

Ownership Issues:

The well is located on land owned by the State of Utah and administered by the School and Institutional Trust Lands Administration (SITLA). Mineral ownership is the same as surface. The oil and gas lessee is River Gas Corp., coal lessee is Arjay Oil Company, no other mineral lessee of record according to affidavit of River Gas. Notice to all owners and surface owners within a half mile radius was given by River Gas. Notice was published in the Salt Lake Tribune, Deseret News, and the Sun Advocate. A copy of the notice was mailed to the BLM in Price, the EPA, and SITLA.

Well Integrity:

A 20" conductor pipe was set at 20 feet. A 17-1/2" hole was drilled to 530 feet, 13-3/8" casing was set at 526 feet and cemented to surface with 600 sks of class G. Drilled 12-1/4" hole to 3718 feet, 9-5/8" casing set at 3718 feet and cemented to surface with 1450 sks class G. Drilled a 8-3/4" hole to 6510 feet set 7" casing at 6508 feet cemented to surface with 49 sks 50/50 poz and 323 sks RFC. A Cement Bond Log was run on March 30, 1996, for the 9-5/8" casing. This log shows intermittent sections of excellent to good bonding up to about 2750 feet, above which bonding is fair to poor. An Ultra Sonic Imager Cement Evaluation log was run on April 3, 1996, for the 7" casing. It shows evidence of cement in place up to 462 feet which was the fluid level above which could not be logged. The cement quality varies with some channeling evident but should be more than adequate to isolate the injection interval. A pressure test was performed on the well on April 19, 1996, 2000+ psi was held for about 30 minutes with no bleed off.

Ground Water Protection:

Water contained in subsurface strata in the vicinity is of poor quality, as would be predicted, mostly due to distance from recharge and the presence of evaporites in adjacent and intervening formations. A sample of injection water from the Ferron producing zones provided in the application shows total dissolved solids level of 8,402 mg/l.

The quality of water in the Navajo Sandstone at the subject well location is in excess of 100,000 mg/l total dissolved solids (TDS). This was determined via swab samples taken May 22, 1996. The Navajo is a known fresh water aquifer at many locations in the state. In the general San Rafael Swell area, the quality of water in the Navajo is generally of higher quality nearer the outcrop and recharge areas and poorer with increased depth and distance from recharge (DNR Tech. Pub. 78). This premise has been verified with samples taken from the subject well and other wells along the flow path. The planned

Statement of Basis D-3 Well

injection of Ferron production water into the Navajo at this location will result in dilution of the more saline water contained in the Navajo. The Wingate Formation shows similar characteristics. A sample of water/was swabbed from the top portion of the Wingate on April 5, 1996, testing showed the TDS to be in excess of 200,000 mg/l. This well is some 25 miles further down the flow path from the Texaco SWD#1 well which (showed 23,000 mg/l TDS in the Navajo. This large increase in salinity may indicate flow of water from older formations below via faulting or some other undetermined source.

Injection of produced water into the Navajo/Wingate Sandstones at this location is predicted to have little effect on the overall hydrology of the aquifers because of their great extent compared to the volume of fluid that will likely be injected. According to USGS investigation (Tech. Pub. 78), the Navajo contains in the neighborhood of 94,000,000 acre-feet of water in transient storage. Injection at a rate of 15,000 barrels per day for 10 years would result in 6506 acre-feet of water being injected. This equates to about .007% of the water already in storage in the Navajo. At the Drunkards Wash Unit experience has shown that after injection into the Navajo/Wingate for almost three years (~ 3,000,000 barrels) a this well drilled approximately 3 miles away (south) showed negligible pressure increase in the Navajo attributable to the injection.

It is our conclusion after reviewing applicable information including the application submitted by River Gas, that injection into the Navajo and Wingate Sandstones at this location would result in some dilution of the saline water present in the aquifers and a pressure increase near the well which would dissipate after injection ceases. No long term negative impacts are anticipated as a result of injection of produced water into the subject well.

Oil/Gas & Other Mineral Resources Protection:

The Ferron coal/gas zone is protected by tubing, two strings of casing and cement. No other known potentially producible zones were encountered by the well. The injection zone is isolated some 3000 feet below the productive interval.

Bonding:

River Gas has a blanket bond posted with School and Institutional Trust Lands Administration which covers this well.

Actions Taken and Further Approvals Needed:

Proper notice was given as required and no objections were received. Approval of the application was recommended based on the information reviewed and summarized above.

Reviewer(s): G. Hunt	Date: 6-25-96

River Gas Corporation

511 Energy Center Blvd. • Northport, AL 35476 • (205) 759-3282 • (205) 349-3069 fax

June 18, 1996

Mr. Gil Hunt Division of Oil, Gas & Mining 1594 West North Temple, Suite 1210 Salt Lake City, Utah 84114-5801

Re: Analysis of Post-frac Water Injection Test on Utah D-3

Dear Mr. Hunt:

On June 17, 1996 I sent a sundry to the Division of Oil, Gas and Mining requesting a change in the Maximum Allowable Injection Pressure on the D-3. Attached was a fax copy of the Analysis of the Post-Frac Water Injection Test. I have included with this letter a binded copy for your files. It should be much easier to read.

Sincerely yours,

Dennis Plowman

Reservoir Technician


JUN 2 4 1996

DIV. OF OIL, GAS & MINING

ANALYSIS OF THE POST-FRAC WATER INJECTION TEST ON WELL D-3

PREPARED FOR:

RIVER GAS CORPORATION 3600 WATERMELON ROAD NORTHPORT, ALABAMA 35476



PREPARED BY:

STIM-LAB, INC. 7406 NORTH HWY 81 DUNCAN, OKLAHOMA 73534

P.O. Number: Verbal/John Hollingshead File Number: SL 4503

June 17, 1996

ALL INTERPRETATIONS ARE OPINIONS BASED ON INFERENCES FROM SAMPLES AND LOGS WHICH WERE SUPPLIED. WE CANNOT, AND DO NOT, GUARANTEE THE ACCURACY OR CORRECTNESS OF ANY INTERPRETATIONS, AND WE SHALL NOT, EXCEPT IN THE CASE OF GROSS OR WILLFUL NEGLIGENCE ON OUR PART, BE LIABLE OR RESPONSIBLE FOR ANY LOSS, COSTS, DAMAGES OR EXPENSES INCURRED OR SUSTAINED BY ANYONE RESULTING FROM ANY INTERPRETATION MADE BY ANY OF OUR OFFICERS, AGENTS OR EMPLOYEES. THESE INTERPRETATIONS ARE ALSO SUBJECT TO OUR GENERAL TERMS AND CONDITIONS AS SET OUT IN OUR CURRENT PRICE SCHEDULE.



same salidit

Completion History of D-3 Prior to the Post-Frac Injection Test

Formation	Perforation Interval (ft)	Stimulation	Date	Top Packer (ft)
Wingate	5997-6058	Fracture	May 24, 1996	5906
Navajo E	5872-5896	Fracture	May 25, 1996	5713
Navajo D	5736-5763			
Navajo C	5663-5728	Fracture	May 26, 1996	5527
Navajo B	5619-5627			
Navajo A	5566-5567			
Navajo A	5561-5602	Fracture	May 29, 1996	

On June 2, 1996 a water injection test was conducted with all the perforations open. A total of 2350 barrels of KCl water were injected at rates from 5 to 28 BPM. The surface pressures and rates are shown in figure 1. Using the recorded bottom hole pressure, the traditional analysis of the step rate shows a fracture extension pressure of 4106 psi (figure 2). This corresponds to a surface fracture parting pressure of 1475 psi. In this particular test, the fracture opening was very distinct and confirmed the results of the conventional analysis of pressure versus rate. The data in figure 3 shows a distinct fracture opening at 4110 psi which is in complete agreement with the analysis in figure 2.

Figure 1: Surface Pressure and Injection Rate for Post Frac Injection Test on Salt Water Disposal Well D-3




Figure 2: Post-Frac Step Rate Test in D-3





Figure 3: Post Fracture Injection Test in D-3



The fracture extension pressure determined from the initial water injection test in the Wingate was 4438 psi which is a frac gradient of 0.735 at 6035 ft. The same gradient applied to the top depth of the Navajo A at 5561 ft would predict a fracture extension pressure of 4087, which is within 20 psi or 99.5% of the observed pressure 4106 psi. This gives a difference of 332 psi in the measured fracture extension pressures.

These data were also compared to the closure stress computed from the logs. The average closure stress from 6037-6057 ft was 4245 psi and the average closure stress from 5563-5583 ft was 3870 psi. The 20 ft average was used because the stress must be distributed over the fracture process zone which is estimated to be from 10-30 ft for this size fracture. This gives a calculated difference of 375 psi, which is a phenomenal agreement based on the assumptions, which are required to compute stress from the logs. The log calculations were normalized based on the injection pressures observed in the Wingate and no other adjustments were made to the stress predictions.

FORM 8

STATE OF UTAH

DECEIVED

JUL 1 2 1996

S. LEASE DESIGNATION AND BERIAL NO. DIVISION OF OIL. GAS AND MINING ML-38666 6. IF INDIAN, ALLOTTES OR TRIBE HAME WELL COMPLETION OR RECOMPLETION VREPORT, GASOS WHINING N/A Water Disposal UNIT AGREEMENT FAME IN TYPE OF WELL: OIL | UTU 67921X A TYPE OF COMPLETION: S. FARM OR LEASE HAME BEEF. PLUG BESTR. WELL NORK UTAH S. WELL NO. River Gas Corporation 1 ADDRESS OF OFERATOR 10. FIELE AND POOL, OR WILDCAT 1305 S. 100 E., Price, UT 84501 DRUNKARDS WASH 4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements) 11. SEC. T. S. M., OR SLOCK AND SURVEY OR AREA 1600' FSL, 1126' FWL, SECTION 18, T15S, R10E
At top prod. interval reported below NW/SW SECTION 18, T15S, R10E, SLB&M At total depth DATE ISSUED 14. AFE 10. **UTAH CARBON** 43-007-30290 2/14/96 19. ELEY. CASINGWEAD 18. ELEVATIONS (DF. RES, RT. GR. ETC.) 17. DATE COMPL. (Ready to prod.) 15. BATE SPUBBED IS BATE T.D. BEACHED (Plue & AMA) 5691' GR 6/14/96 3/27/96 2/27/96 BOTARY TOOLS CABLE TOOLS IF MULTIPLE COMPL. 23. INTERVALE IL PLUS SACK T.S., MS & TVS HOW MANT DEILLED SY TO TD N/A N/A N/A 6510' WAS DESCRIBATE WAS DESCRIBED 24. PRODUCING INTERVAL(S), OF THIS COMPLETION—TOP, NOTION, NAME (MB AND TVD) N/A YES TIPE ELECTRICIAND OTHER LOCA ROW DIPOLESONIC, CRM TAS VELL CORED YES NO CELL CORED TEST DENSITY NEUTRON, FMI, & BOND & SIDEWALL CORES EMILA STEN TEST - VEST - MISSTeller sidel CASING RECORD (Report all strings set in well) 24. CEMENTING RECORD AMOUNT PELLED HOLE SIZE SEPTE SET (MD) WEIGHT, LA./FT. CARING BIZE 600 sks Class G, 2% S-1, 1/4#/sk D-29 20' 17 - 1/2'48 ppf 13-3/8 12-1/4" 1250 sks 50/50 Poz/G, 8% D20, 10% D44, 2% S1 + 200 sks Class G, 2% S1, 1/4#/sk D29 3718' 9-5/8 36 & 40 ppf 323 sx 10-1 RFC; 49 sx 50/50 POZ, 8% D20, 10% D44 + D35; 8-3/4" 6508! 7" 26 ppt 320 sx 50/50 POZ, 8% D20, 10% D44 + D35, 2% S1 TUBING RECORD LINER RECORD PACKER SET (MO) SIZZ DEFTH SET (MO) SACES CEMENT SCREEK (MO) BOTTOM (MD) **6122** TOP (MD) ACID. SHOT. FRACTURE, CEMENT SQUEEZE ETC. II. PERFORATION BECORD (Interval, sure and number) AMOUNT AND EINS OF MATERIAL CREO 5561'-5602', 5619'-27', 5635'-47', 5663'-5728', SEPTE INTERTAL (MD) 5736'-63', 5784'-5872', 5888'-96', 5997'-6029', & 6041'-58' PRODUCTION WELL STATUS (Freducing or shul-in) PRODUCTION METROD (Flewing, gas lift, pumping-BATE FIRST PRODUCTION GAR-OIL BATH GAS-MEF. WATER-SEL Oller SEL 2300'X. 708 EGUAS TESTED DATE OF TEST TEST PERIOD GIL CRAVITT-API (CREE.) WATCH-ABL CAS-MCF. 01L----CALCULATED 24-EOUS BATE PLOW, TUBING PRIME. CASING PRESSURE IS CHESKIW TERT 34. SIRPORITION OF GAR (Sold, west for fuel, rented, etc.) 33. LIST OF ATTACHMENTS that the foresping find stacked information is complete and correct as determined from all available records 36. I bereof certif DATE July 8, 1996 TITLE Regulatory Manager SICHED

INSTRUCTIONS

and in item 24 show the producinginterval, or intervals, top(s), bottom(s) and name(s) for only the interval reported in item 33. Submit a separate report (page) on this form, adequately identified, for each additional interval to be separately produced, showing the additional data This form should be completed in compliance with the Utah Oil and Gas Conservation General Rules. If not filed prior to this time, all logs, ITEMS 22 and 24: If this well is completed for separate production from more than one interval zone (multiple completion), so state in item 22, ITEM 18: Indicate which elevation is used as reference for depth measurements given in other spaces on this form and on any attachments. tests, and directional surveys as required by Utah Rules Should be attached and submitted with this report.

ITEM 29: "Sacks Cement": Attached supplemental records for this well should show the details of any multiple stage cementing and the location of

ITEM 33: Submit a separate completion report on this form for each interval to be separately produced (see instruction for items 22 and 24 above).

	10000		38.	GEOLOGIC MARKERS
 SUMMARY OF POROUS ZONES: Show all important zone and all drill-stem test 	OROUS ZONES: portant zones 11-stem tests,	of porosity a , including de	UMPIARY OF POROUS ZONES: Show all important zones of porosity and contents thereof; cored intervals; and all drill-stem tests, including depth interval tested, cushion used,	
time tool o	pen. Clowing	nd shut-in or	time tool open. flowing and shut-in pressures, and recoveries.	
Formation	Top	Bottom	Description, contents, etc.	Meas, Depth True Vert. Depth.
Navajo Sandstone	. 5550'	5915'	Description: Lt. tan, finegrained, crossbedded sandstone. Perforations: 5561'-5602', 5619'-27', 5635'-47', 5663'-5728', 5736'-63', 5784'-5872', & 5888'-96'.	
Wingate Sandstone	,0009	.9509	Description: Lt. tan to pink, finegrained, crossbedded sandstone. Perforations: 5997'-6029', 6041'-58'.	

DERANDICHT DE TORK RESOURCES
DIVIDION OF BIL, GAS AND MINING

DEIRATDICATION OF SIL, GAS AND MIN SUNDRY NOTICES AND REPORTS So not use that form for proposals to drill now wells, dropen existing wells, critically and applications of the surface o	ING ON WELLS	filesta Chargestian and File 131-150, ML - 38666 7. Indian Allottee of Tribe Name 8. Unit of Communitization Agreement
Name of Operator River Gas Corporation Address of Operator	1 Well	UTU67921X - Wolf rame and Number Utah D-3 10.AF: Well Number 43-007-30290
511 Energy Center Blvd. Northport, AL 35476 Location of Well Footage : 1600' FSL & 1126' FWL GG. Sac. T. R. M. : NW/SW Sec 18, T155, RIOE	(205) 759-3282	Drunkards Wash Carbon UTAH
NOTICE OF INTERIOR New Construction Casing Repair Change of Plans Conversion to Injection Fracture Treat Multiple Completion Mother Linguage in Surface Injection Page 101 New Construction Pull or Alter Casing Recompletion Shoot or Acidize Fracture Treat Water Shut-Off Other Linguage in Surface Injection Page 111 Nother Linguage in Surface Injection New Construction Water Shut-Off Other Linguage in Surface Injection Page 111 New Construction	Abandonment * Casing Repair Change of Plans Conversion to Injection Fracture Treat Other	UENT REPORT Ginal Form Only) New Construction Pull or Alter Casing Shoot or Acidize Vent or Flare Water Shut-Off
Approximate Date Work Will Start 10/25/96 - 11/08/96	Must be accompanied by a temen	t verification renne
Describe Proposed OR COMPLETED OPERATIONS (Clearly state all pertino locations and measured and true vertical depths for all markers and zones pertino River Gas requests a surface injection pressu Utah D-3 well.	ant defails, and give pertinent dates. If	well is directionally drilled, give subsurface

APPROVED BY THE STATE OF UTAH DIVISION OF OIL, GAS, AND MINING DATE:

For our week test period.

I narudy duriny	met the larequing terrile and c	7700		
me & Signature	Dennis Plowman	Vennis Planna	TmaReservoir Techni	ician - in/aula
ale Use Chiy)			The state of the s	CTAM Date 10/24/9

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES 8. Lease Designation and Serial Number DIVISION OF OIL AS AND MINING ML - 38666 7. Indian Allottee or Tribe Name SUNDRY NOTICES AND REPORTS ON WELLS Co not use this form for proposals to drill new walls deepen existing wells; or to reenter plugged and abandoned wells. 8. Unit or Communitization Agreement Use APPLICATION FOR PERMIT - for such proposals UTU67921X . Type of Weil 9. Well Name and Number Cther(specify) Disposal Well Utah D-3 . Name of Operator 10. APı 'Yell Number River Gas Corporation 43-007-30290 . Address of Operator Telephone Number 11. Field and Pool, or Wildcat 511 Energy Center Blvd. Northport, AL (205) 759-3282 Drunkards Wash . Location of Well : 1600' FSL & 1126'FWL Footage county : Carbon CQ. Sec. T. R. M. : NW/SW Sec 18, T15S, R10E State : UTAH CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE: REPORT, OR OTHER DATA NOTICE OF INTENT SUBSEQUENT REPORT (Submit in Duplicate) (Submit Original Form Only) Abandonment **New Construction** Abandonment * New Construction Casing Repair Pull or Alter Casing Casing Repair Pull or Alter Casing Change of Plans Recompletion Change of Plans Shoot or Acidize Conversion to Injection Shoot or Acidize Conversion to Injection Vent or Flare Fracture Treat Vent or Flare Fracture Treat Water Shut-Off Multiple Completion Water Shut-Off Other Other Date of Work Completion Approximate Date Work Will Start Report results of Multiple Completions and Recompletions to different reservoirs ON WELL COMPLETION OR RECOMPLETION AND LOG form. Must be accompanied by a tement verification report. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

River Gas Corp. requests permission to acidize the D-3 Disposal Well to correct any gel damage that may exist as a result from prior stimulation work. The job will consist of 5000 gallons of 15% HCl, 2800 barrels of produced water, and 1400 perf balls. Pump rates should range between 20 to 25 bpm. A junk basket run will be made after the job to make sure all balls have unseated.

I hereby certify that the foregoing is true and car ne & Signature Tille Reservoir Technician Date 16/21 (دنم) جدل عند

OCT 2 4 1996

DIV. OF OIL, GAS & MINING

See Instructions on Reverse Side

OCT-24-96 THU 09	STATE UP UTAH		P. 02
	PARTMENT OF THAL RESOUR		Lease Opergnation and Serial Number
U	VISION OF GAS AND MIN	ING	ML - 38666
SUNDRY	OTICES AND REPORTS		7, Indian Alighae or Tribe Name
Gnotes Charlotta for proposals to	O LICES AND REPORTS it is now wells, deepen existing wells, or to a PPLICATION FOR PERMIT— for Settings	senor purget and statemed with	8. Unit or Communitization Agreement UTU67921X
Cil Cil Cil Gaa	Cther(specify) Dispose	al Well	9, Well Name and Number Utah D-3
Name of Operator		,	10, AFI Weil Number
liver Gas Corporation	•		43-007-30290
Address of Operator		4. Telephone Number	11. Field and Pool, or Wildeat
Tocation of Mett	d. Northport, AL 35476	(205) 759-3282	Drunkards Wash
CC. Sac. T., R., M. : NW/SW	FSL & 1126'FWL Sec 18, T155, R10E RIATE:BOXES:TOINDICATEN	State	: Carbon : utah
NOTICE	OF INTENT in Cupicate)	SUBSE	HIGOROTHER DATA (1986) QUENT REPORT Original Form Only)
Abandonment Casing Repair Change of Plans Conversion to Injection Fracture Treat Multiple Completion Other	New Construction Pull or Alter Casing Recompletion Shoot or Acidize Vent or Fiare Water Shut-Off	Abandonment * Casing Repair Change of Plans Conversion to Injection Fracture Treat Other Data of Work Completion	New Construction Pull or Alter Casing Shoot or Acidize Vant or Flare Water Shut-Off
		Fecon results of Multiple Completing on WELL COMPLETION OR RECO	
05344.4			

CESCRIBE FROPOSED OR COMPLETED OFFRATIONS (Clearly state all perfinent details, and give perdisent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and comes pertinent to this work.)

River Gas Corp. requests permission to acidize the D-3 Disposal Well to correct any gel damage that may exist as a result from prior stimulation work. The job will consist of 5000 gallons of 15% HCl, 2800 barrels of produced water, and 1400 perf balls. Pump rates should range between 20 to 25 bpm. A junk basket run will be made after the job to make sure all balls have unseated.

reasery density that the loregoing is true and contect

10 A Signature Dennis Plouman Dennis Plouman Dennis Dueso TipeReservoir Technician Oare 16/21/40

2 Use Only)

See Instructions on Reverse Side

Accepted by the State of Utah Division of Oil, Gas and Mining

Date: 10-24-96

By: 47

STATE OF UTAH DEPARTMENT OF TURAL RESOURCES 6. Lease Designation and Serial Number DIVISION OF OIL, GAS AND MINING ML - 38666 7. Indian Allottee or Tribe Name SUNDRY NOTICES AND REPORTS ON WET SUNDRY NOTICES AND REPORTS ON WELLS Co not use this form for proposals to drill new wells, deepen existing wells; anto reember plugged and abandoned wells. 8. Unit or Communitization Agreement Use APPLICATION FOR PERMIT - RESIGN PROPOSELE. UTU67921X . Type of Weil 9. Well Name and Number Cil Weil Cther(specify) Disposal Well Utah D-3 L Name of Operator 10. API 'Yell Number River Gas Corporation 43-007-30290 . Address of Operator 4. Telephone Number 11. Field and Pool, or Wildcat 511 Energy Center Blvd. Northport, AL 35476 (205) 759-3282 Drunkards Wash Location of Well : 1600' FSL & 1126'FWL Footage County : Carbon CQ. Sec. T. R. M. : NW/SW Sec 18, T15S, R10E State : UTAH 2 CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE: REPORT OR OTHER DATA NOTICE OF INTENT SUBSEQUENT REPORT (Submit Original Form Only) (Submit in Duplicate) Abandonment New Construction Abandonment * **New Construction** Casing Repair Pull or Alter Casing Casing Repair Pull or Alter Casing Change of Plans Recompletion Change of Plans Shoot or Acidize Conversion to Injection Shoot or Acidize Conversion to Injection Vent or Flare Fracture Treat Vent or Flare Fracture Treat Water Shut-Off Multiple Completion Water Shut-Off Other Other INCREASE IN MAXIMUM INJECTION PRESSURE

 DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Date of Work Completion

Please see the attached.

Approximate Date Work Will Start When approved

APPROVED BY THE STATE
OF UTAH DIVISION OF
OIL, GAS, AND MINING
DATE: 15-76
BY:

NOV | 4 1996

DIV OF OIL, GAS & MINING

. I hereby certify that the foregoing is true and carrect

ame & Signature Dennis Plowman Wennis Co

ਜਗਵReservoir Technician Care 11/12/96

Report results of Multiple Completions and Recompletions to different reservoirs

on WELL COMPLETION OR RECOMPLETION AND LOG form.


Must be accompanied by a tement verification report.

ate Use Chiy)

River Gas Corporation request that the surface injection pressure for the D-3 disposal well be increased from 1475 psi. to 1550 psi. This pressure change would maximize the surface equipment capability and allow more water disposal.


To help justify our request, refer to the September 20, 1996 Stim-Lab report which analyzes the stress profile in the Drunkards Wash injection wells. In reference to the D-3 disposal well, the report summation was that the maximum injection pressure could be safely raised to 2500 psi. This pressure would be contained by the shale barriers and the two anhydrite stringers from 5184'-5207' and 5270'-5304'. This containment was illustrated in the enclosed "Tracer Log" which was run after the post frac steprate test. You can see that upward fracture growth did not occur during this test even though a 28 bpm rate was realized. The pressures at this rate were approximately 1715 psi.. A rate versus pressure plot of the test also has been included for your reveiw.


Please look over this information at your earliest convenience and let us know what you think. If you should need additional help, contact the Alabama office.




RIVER GAS CORPORATION

D-3 DISPOSAL WELL







6. Lease Designation and Serial Number
ML - 38666


Cil Weil Gas Weil Cher(specify) Disposal Well Utah D-3 Name of Operator River Gas Corporation Address of Operator 511 Energy Center Blvd. Northport, AL 35476 Cther(specify) Disposal Well Utah D-3 10. API Weil Number 43-007-30290 11. Field and Pool, or Wildcat (205) 759-3282 Drunkards Wash	DIVISION OF SIL, GAS AND MINI		6. Lease Designation and Serial Number ML - 38666 7. Indian Allonee or Tribe Name
Type of Well	Co not use this form for proposals to drill new wells, deepen existing wells, or to re	enter plugged and abandoned wells.	8. Unit or Communitization Agreement
Gil			UTU67921X
River Gas Corporation 43-007-30290 Address of Operator 511 Energy Center Blvd. Northport, AL 35476 (205) 759-3282 Drunkards Wash Location of Well Footage : 1600' FSL & 1126' FWL County : Carbon GC, Sec. T. R. M. : NW/SW Sec 18, T15S, R10E State : UTAH CHECK APPROPRIATE BOXES TO INDICATE NATURE: OF NOTICE REPORT, OR OTHER, DATA NOTICE OF INTENT (Submit in Duplicate) Abandonment New Construction Abandonment Subscience Pull or Alter Casing Change of Plans Recompletion Change of Plans Recompletion Change of Plans Not or Acidize Conversion to Injection Shoot or Acidize Multiple Completion Water Shut-Off Other Approximate Date Work Will Start Recompletion Date of Work Completion Nowember: 5, 1996 Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION AND LOG form.	. Type of Weil Cit Gas Cther (specify) Disposa	l Well	
Address of Operator 511 Energy Center Blvd. Northport, AL 35476 (205) 759-3282 Drunkards Wash Location of Well Footage : 1600' FSL & 1126' FWL CQ. Sec. T., R.M.: NW/SW Sec 18, T15S, R10E NOTICE OF INTENT (Submit in Duplicate) Abandonment New Construction Casing Repair Pull or Alter Casing Change of Plans Recompletion Conversion to Injection Shoot or Acidize Fracture Treat Vent or Flare Multiple Completion Water Shut-Off Other Approximate Date Work Will Start 4. Telepnone Number (205) 759-3282 Drunkards Wash County: Carbon State: UTAH County: Carbon State: UTAH SUBSECUENT REPORT (Submit Original Form Only) Abandonment New Construction Abandonment New Construction Casing Repair Pull or Alter Casing Change of Plans KX Shoot or Acidize Conversion to Injection Vent or Flare Fracture Treat Water Shut-Off Other Date of Work Completion November 5, 1996 Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION ON RECOMPLETION AND Log form.	Name of Operator		10. API 'Yell Number
S11 Energy Center Blvd. Northport, AL 35476 (205) 759–3282 Drunkards Wash Location of Well Footage : 1600' FSL & 1126' FWL County : Carbon State : UTAH CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA NOTICE OF INTENT (Submit in Duplicate) Abandonment New Construction Casing Repair Pull or Alter Casing Change of Plans Recompletion Conversion to Injection Shoot or Acidize Fracture Treat Vent or Flare Multiple Completion Water Shut-Off Cother Approximate Date Work Will Start Recont results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION AND LOG form.	River Gas Corporation		43-007-30290
Footage : 1600 FSL & 1126 FWL County : Carbon CC, Sec, T. R.M.: NW/SW Sec 18, T155, R10E CC, Sec, T. R.M.: NW/SW Sec 18, T155, R10E CHECK APPROPRIATE BOXES TO INDICATE NATURE. OF NOTICE, REPORT, OR OTHER DATA NOTICE OF INTENT (Submit in Duplicate) New Construction Abandonment New Construction Casing Repair Pull or Alter Casing Change of Plans Recompletion Conversion to Injection Shoot or Acidize Conversion to Injection Fracture Treat Vent or Flare Multiple Completion Other Date of Work Completion Recompletion Shoot or Acidize Casing Repair Conversion to Injection Change of Plans Conversion to Injection Conversion	311 211016, 1011011 21111 110111111111111111111111	,	, i
CC, Sec, T. R. M.: NW/SW Sec 18, T15S, R10E CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE. REPORT, OR OTHER DATA NOTICE OF INTENT (Submit in Duplicate) Abandonment New Construction Abandonment New Construction Casing Repair Pull or Alter Casing Change of Plans Recompletion Conversion to Injection Shoot or Acidize Conversion to Injection Fracture Treat Vent or Flare Water Shut-Off Other Date of Work Completion November 5, 1996 Recompletion Approximate Date Work Will Start Recompletion Approximate Completion And Log form.	. Location of Well		
CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA NOTICE OF INTENT (Submit in Duplicate) Abandonment New Construction Abandonment Pull or Alter Casing Casing Repair Pull or Alter Casing Change of Plans Recompletion Conversion to Injection Shoot or Acidize Conversion to Injection Fracture Treat Vent or Flare Water Shut-Off Other Date of Work Completion November 5, 1996 Recompletions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION AND LOG form.		•	
NOTICE OF INTENT (Submit in Duplicate) Abandonment New Construction Casing Repair Pull or Alter Casing Change of Plans Recompletion Conversion to Injection Shoot or Acidize Fracture Treat Vent or Fiare Multiple Completion Other Approximate Date Work Will Start New Construction Casing Repair Pull or Alter Casing Change of Plans Start Change of Plan			
(Submit in Duplicate) Abandonment New Construction Casing Repair Pull or Alter Casing Change of Plans Recompletion Conversion to Injection Shoot or Acidize Conversion to Injection Shoot or Acidize Fracture Treat Vent or Flare Multiple Completion Water Shut-Off Cother Approximate Date Work Will Start (Submit Onginal Form Only) (Submit Onginal Form Only) (Abandonment New Construction Casing Repair Pull or Alter Casing Change of Plans K Shoot or Acidize Conversion to Injection Vent or Flare Fracture Treat Water Shut-Off Cother Date of Work Completion November 5, 1996 Recom results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION AND LOG form.			
Casing Repair			
Most be accompanied by a centent verification report.	Casing Repair Pull or Alter Casing Change of Plans Recompletion Conversion to Injection Shoot or Acidize Fracture Treat Vent or Flare Multiple Completion Water Shut-Off Other	Casing Repair Change of Plans Conversion to Injection Fracture Treat Other Date of Work Completion Report results of Multiple Completion WELL COMPLETION OR RECO	Pull or Alter Casing XX Shoot or Acidize Vent or Flare Water Shut-Off November 5, 1996 Ions and Recompletions to different reservoirs CMPLETION AND LOG form.
		7	M. W. C.

locations and measured and true vertical depths for all markers and zones pertinent to this work.)

On November 5, 1996, the D-3 disposal well was acidized with 5000 gallons of 15% HCL acid and 2678 barrels of produced fluid. 1400 ball sealers were used to divert the acid and fluid across the perforated intervals. The average rate and treating pressure during the job was 24 bpm and 2000 psi respectively. The ISIP was 1670 psi.

I hereby centry t	-	•	()	01
ime & Signature	Dennis	Plowman	Wennis	Louman
(ate Use Corv)				

TueReservoir Technician Care



DEPARTM	STATE OF THE AH SENT OF NATURAL RESOURCE N OF OIL, GAS AND MINING	S 3	6. Congnation and Serial Number ML - 38666 7. Indian Aliades of Tribe Name
SUNDRY NOTIC	CES AND REPORTS OF	her plubbed and abandoned wells.	8. Unit of Communication Agreement UTU67921K
I, Type of West	Cther(steely) Disposal	Vell	2. Weil Neme and Number
☐ G₁ ☐ G₂s	Traposar	# C.L.A	Utah D-3 10, API Weil Number
Iname or Coeracer River Gas Corporation			43-007-30290
F. Ydoleaz of Chelaton		4. Talephone Number	11. Field and Pool, or Wildest
511 Energy Center Blvd. N	orthport, AL 35476	(205) 759-3282	Drunkards Wash
Footage : 1600' FSL co. Sec. T., R. M. : NW/SW Sec	18, T155, RIOE	STATE OF NOTICE REPO	: Carbon : VTAH RTZOR-OTHER DATAMORIZADEM
NOTICE OF II		SUBSE	QUENT REPORT Original Form Only)
Abandonment	New Construction Full or Alter Casing Recompletion Shoot or Acidize Vent or Flare Water Shut-Cit	Abandonment Casing Repair Change of Plens Conversion to Injection Fracture Treat Other Date of Work Completion	New Construction Pull or After Casing Shoot or Acidize Vent or Fiare Water Shut-Off
Approximate Date Work Will Start A	s soon as approved	Accord Yestelts of Multiple Cample on WELL COMPLETION OR REC	
osturies Proposti on completed locations and measured and the vertical of See Attached.	CPERATIONS (Clearly state at! pertin- ceptes for all markers and cones pertin	ent detalls, and give perdnent dates, ent to mis work.)	If well is directionally drilled, give subsurface
m 2*	,	, , , , , , , , , , , , , , , , , , , ,	
	Post-it* Fax Note 7671 To Gil Hunt Co./Dept. Phone # Fax #	Dato # of pages ► From Dennis Plowman Co. RGC. Phone # Fax #	
i narazy zanity wat ita tarageing iz tiba i ima 2 Signatura — Demnis Blownat		nueReserv	oir Technician cass 11/19/96
ine 2 Signature Demmis Siowmal	Numi Louis		

See instructions on howers side

APPROVED BY THE STATE
OF UTAH DIVISION OF
OIL, GAS, AND MINING
DATE:
BY:

River Gas Corporation request that the surface injection pressure for the D-3 disposal well be increased from 1550 psi. to 1700 psi. This pressure change should allow an additional 1000 barrels per day of water disposal while not jeopardizing zone containment as stated below.

To help justify our request, refer to the September 20, 1996 Stim-Lab report which analyzes the stress profile in the Drunkards Wash injection wells. In reference to the D-3 disposal well, the report summation was that the maximum injection pressure could be safely raised to 2500 psi. This pressure would be contained by the shale barriers and the two anhydrite stringers from 5184'-5207' and 5270'-5304'. This containment was illustrated by the Schlumberger "Tracer Log" on file with your office. This log was run after the post frac steprate test, and you can see that upward fracture growth did not occur during this test even though a 28 bpm rate at 1710 psi. was realized. However, we feel our operating rate & pressure will be about 5.2 bpm at 1680 psi, respectively. A copy of the service company job report has been included for your review.

Also, six months from the day of the pressure increase, if approved, River Gas will run a tracer survey under normal operating rates and pressures. This operation should help insure that the injection fluids are being contained within the perforated intervals. After this first test, a follow-up tracer survey will be conducted on an annual basis.

Please look over this information at your earliest convenience and let us know what you think. If you should need additional help, contact the Alabama office.

JUN-12-96 MED 14:0 SCHLUMBERGE.

FAX NO. 801 7890138 P. 02 DS VERNAL UTAH) JUN-12-96 WED 12:35 Skill and Designation of the State of the St WELL THEATMENT REPORT Dowel BATE DOWELL SCHLUMBERGER INCORPORATED 5-31-96 DIFARTO PRINTED IN USA ITIEATMENT MUMBER PEDMUN OHA SMAN JISH Wernau HOUSE PERATURE ACE OF WELL
TOM HOLE I ACE OF WELL
ACE OF WEL 15-63-0-12-7

ON GAS OF WATER

CI CI CI T 155 BIDE INLL Drukard wash PERFORATED INTERVALS cse: 1820 10 BOYTOM \$8,25 TYPE OF SERVICE

MATRIX TREATMENT CASING SIZE -70 SAND CONTROL 711. 5.561 10 1055 1 % Kel - GENCTURINO YUBING SIZE d OPERATOR NAME Cas River TO PACKER DEPTH 10 Pome ב פאטיקל ומפדהעקדומאם ... 10 70 STEP In Julian PERF. DIAMETER- T DEN HOLE CASING YOL. PERFORATED WIEDVAL 238 TOTAL FT. CASING ANNULUS DISPLACEMENT FOR CONVERSION PURPOSES 24 BBLS EQUALS 1000 GALLONS BOTH C. TOG. ואופטד ן 38 ARRIVED ON LOCATION: 10 100 LEFF LOCATION: NOTATIONS INJECTION RECORD PRESSURE TIME TYPE OF FLUID THATE BEM COLLEGE VOLUME VOLUME PROP TYPE Cso. Pre-Job S dely Meeting 0800 OKAS Arrive . n/x . kcc in 12:00 Done Art my BC DACK 14 Morning 16:00 Armye ibe his warr on Tool He & HALING Trouble Setting of Table on Order Company of the Bridge of Sound Security -1 80:00 15:00 19:00 Cool is suicked Arefuel oc wast to set took 807100 t Toker ς, STIANTI Lugina CXIXO 120 0820 11 11 210 100 0834 11 ~~ OBAT 11 150 380 0844 LA. 11 250 540 10.3 0853 300 0858 11 3.51 11 0901 1014 730 400 41 10,4 0908 Att Poi 450 7*\$*0 11 10.4 0913 16 900 Change RATE 0914 940 RATE + PSA 11 15 500 0916 نځک RATTHIST 11 7.5 1020 0919 BITM AVERAGE INJECTION RATES
NITROGEN | QARBON DIOXIDE WATERIACIO 2507 BELS CARGON DIGNIOE YOYAL WATROP FLUTO COUNTITY PROPERTY TELACER INA PHESSURE BUMMARY, S.D.P. TOTAL INVECTED 1 15 MIN 6.I.P. 15.50 CBS PRODUCTION PRIOR TO THIS THEATMENT Test GALS NO PAD PAD YOLUMB . 🔲 Slamiland PRACTURE ORACIENT CUSTOMER REPRUSENTATIVE OS SERVICE SUPERVISOR

Robert I Fu

MITCH BITCHELL

echrimmrekae.

JUN-12-96 WED 12:38 DS VERNAL UTAH

FAX NO. 801 7890138

P. 03

יי אַנוֹאַעּרנּלַ <u>־</u>	ao web it				1. 19								37	
WELL TRE	ATMENT OF	EPORT .	. (1).		in i		, ,2,				DATE	1.12	Sec. Sec.	2505
CUPPLEME	NIAL LUG	,	" ;	DOWE	L SCH	LUMBERGE	R INC	ORPOR	ATED	1	¥05.2	MENT NUMBE	9 O 7	2000
OUSTOMER WELL	אום טאום		L.C	CATION (LEGA		5 R10	I P	COULERS		BARL	FAOR	.:) • 0	7 077 7 3	PACES
Swn.	~ 本 り_て			Sec. 18	T15	(\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \		Oruni	URE 1	437		TIONS :		
F	1, 2, 3, 4, 5, 5, 1, 1	ATE SPM	VIECTION	I RECORD	La N P	PUP TYPE	POSE N	Kongrill .	/TBG (/			4	Angele Ball	100
		1.0		- G		· \\		1040		Ratet			<u> </u>	
0923 (11	"		- 6				1100	,	Roser				
0926	11	15			00	م يسب		1120	ام مسود <u>د</u>	Rates				
0929	1/	15			50			11.50	بشبس	Rates		, ,		
0911	-11	15	-	- 80		٠ سيب	[اسد.]	1181	<u>ئز ا</u>	Robert	_			
0436	11	15-			50			1200		RATES				''
0940	11	1		~ 9.	80			oc.cl		RATEX	<u> </u>			
0942	-17				00			1330		[Acres	.: Laic	<u> </u>		
-0945		20			50		<u> </u>	2350	2	Rate		,	·	
0946	11	20		3 4"	000	··	7	1410		RATES	126			
0948		20			50			1440	<u></u>	Rates				. 4
0.95/	11	20	~		00	,		1460) ===	Paret		<u> </u>		<u> </u>
0453	71	20			器		<u> </u>	1500		RATE				4
0956	11	20			200			1500		RATE				
0959		20	2		250		<u>.</u>	1510			11			
10:01	11	20			300			1520		11	1, -			
10,07	11	20		7	350			1520	_		<u> </u>			
10:00		+			400		T -	1520			11		. ,	<u></u>
10:08	11	20			450		7	1,52	0 =		11			
10:11	11	20			500	·		1510		1	11			
10:13		20				, ,,,,,,,,	مــ ا	1577	1	. 111	7_			
10:16	11	20			550		1	4-67		- Incar	m R	tre	,	
10,18	10	125			650			160		1 ^ _				
10:20	11	24.7			1700	,	1-	162		11	()	·		<u></u>
10:22	11	24.9			7.50			T-14-		. le	41			
10:24	11	24.9			1800					(1	1/	· · · · · · · · · · · · · · · · · · ·	* .	
10:26	11	249		_			-	1	1		4			
10:28	1	25			1850		-							1
10:30	11	25		-	1900		1.			- 11	7		,	·
10131	11	25_	-	┿╾╌┪			_ -	- 11,0		- 16	1			<u> </u>
10:34	11	25	1-	+=-	2000		1-	- 160		- Itu	ا اعلاما	RAL		<u> </u>
16:37		28	-	T 1	2650 2100	-			01			15	144	CAL MANAGE
10:38	(/	28	1	-	2/50				10	- 144	<u>化</u>	1300		Crack March
10:40		28.4	~- 	-	2200	 			(0)	77	12	V vale	9.5.7.1	1
(0:42		28.4		-	2750	 		17	· 1 '	- 10	10	1		
10,44		28,5	4		2360			- 17	I '	169	,		100	
115145	1 11.	280	1		(1)	-					24	E J.J	THE NAME OF SEC.	

FAX NO. 801 7890138

JUN-12-98 WED 12:38

DS VERNAL UTAH

IELL TREATMENT REPORT DOWELL SCHLUMBERGER INCORPORATED UPPLEMENTAL LOG Thosa Thosa PAGE DETOMER WELL HAME AND NUMBER SWD-0-3 TYPE OF PLUID PLATE HEM CONTROL TO THE PROP TYPE CALL PHOTATIONS 2350 61 6:41 . 11 10:49 2450 0:50 1710 2500 28.4 10:53 STI 1550 Shortown 15.5% 2503 10:53

,	FIELD REP	PORT	TYPE	op service LLDUP-FALLOFF	DATE 11-JUN	-1996 VHRN	À.		
Schlumberger				SHRVYCE ORDER NUMBER: 143823					
WILL OWNER: RIVER GAS									
REPORTS APPRESS:			PIHI	D:	Brasei				
WELL NIME & NO.1			COUN		GTATU:	UTAR			
LOCATION:					FI		· 		
TEST NO. ONE		INTERVAL FRO	2		EQUIPMENT :	FOURNCE			
	SURFACE DA	A'A			op.	10	PENGTH	DEFTH	
DESCRIPTION	DATE	TIME OF DAY	PRESSURE	COMPONENTS			·		
START PUMPING-RATE S.1	. 02=5UN	00:13							
SING UP RATE-10.3		08144							
SIEP UP RATE-15		09;14		·					
STEP UP RATH-20		09:45							
STEP UP RATE-25		10:16		<u></u>			1		
STEP UP RATE-29		10:37		<u> </u>				T	
SKOT KN		10:55							
<u></u>					WELL BOY	E DATA			
				A SAME AND ADDRESS					
				PORMATION TRETED	tt. Ét	BOT, PORO	YXX		
						DEDTH HEA		KB	
				BI, GVATION		····		<u> </u>	
				TOTAL MENAUARD DEATH	in in				
\	•			OH SIZE	7			,	
				CASING SIZE	·· ·		·····/· · · · · · · · · · · · · · · · ·		
				PERS INTERVAL FROM	£t:	TQ.	£e.		
			<u> </u>	SHOT DENGITA	INSTRU	MENT DAT	A .		
				INSTRUMENT NO. 9245	(942			- K	
l			<u> </u>						
1-11-11 - 11-11-11-11-11-11-11-11-11-11-					·				
· · · · · · · · · · · · · · · · · · ·				INSIDE-COTSIDE OUT					
				11	TRONIC	· · · · · ·			
				TEMPERATURE *F 131					
			_l	ISUDEMINIONS -1 734			,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		

REMARKS:

SCRVICE ORDER NUMBER:

142623

SCHEUMBERGER BNGINGER/TECHNICINN MIKE MCCURDY



RIVER GAS CORPORATION

511 Energy Center Blvd.
Northport, Alabama 35476
Phone (205) 759-3282
Fax (205) 759-3188 (Accounting)
Fax (205) 758-5309 (Corporate)

November 22, 1996

Vickey Dyson Production Group Supervisor State of Utah Division of Oil, Gas and Mining 1594 West North Temple Suite 1210 Box 145801 Salt Lake City, Utah 84114-5801



Ms. Dyson:

Included are copies of logs that were ran on the Utah D-3 well. Our Price Office said that you had requested them. Please let me know if there is anything else that you need.

Thanks,

Dennis Plowman

Reservoir Technician

43 007 30290

155 IDE 18

INJECTION WELL - INSPECTION RECORD

Well Name: D-3 API Number: 43-007-30290 Qtr/Qtr: NW/SW Section: 18 Township: 15S Range: 10E Company Name: River Gas Corporation							
Lease: State Fee Federal Indian							
Inspector: Dennis L. Ingram Date: 04/06/00							
Injection Type:							
Disposal: WDW Enhanced Recovery: Other:							
Injecting: Yes Shut-In:							
Rate:							
Gauges: Tubing: Yes							
Casing: No Casing Pressure: (psig)							
Tubing Pressure: 1701 (psig) Housekeeping: Good, is clean							
Equipment Condition: Good.							
COMMENTS: Barton recorder with chart is inking. Lined evaporation pit with 3 to 4' freeboard. Cellar is full of water around wellhead. Spoke to Billy Vigor 820-8205 and ask him to check for leak in api ring on wellhead. He claims its rainwater?							

FO	RM 9		STATE OF UTAH		•			
	Di	VISIO	N OF OIL, GAS AND MINI	NG	[5. Lease Designation	and Serial Number:	
	SUNDRY NOT	ICES	AND REPORTS ON	WE	LLS	6. If Indian, Allottee or	Tribe Name:	
			lls, deepen existing wells, or to reenter plug ITTTO DRILL OR DEEPEN form for such pi		abandoned wells.	7. Unit Agreement Na	me:	_
1. Ty _l	pe of Well: OIL 🗆 GAS 🖾 C	THER				8. Well Name and Nu	mber:	_
2. Na	me of Operator: River C	as Coi	poration			9. API Well Number:		-
	ddress and hone Number: 6825 S. 5300 W.	P.O. E	Box 851 Price, Utah 84501 (4	35) 6		10. Field or Pool, or W	fildcat:	_
Fo	cation of Well cotages: Q, Sec., T., R., M.: SLB & M					County: Carbo State: Utah	n County	
11.	CHECK APPROPR	ATE	BOXES TO INDICATE NA	TUR	E OF NOTICE, RE	PORT, OR C	THER DATA	
	NOTICE (Submit i	OF INT				UBSEQUENT RI Submit Original For		
	Abandon		New Construction		Abandon *		New Construction	
	Repair Casing		Pull or Alter Casing		Repair Casing		Pull or Alter Casing	
	Change of Plans		Recomplete		Change of Plans		Reperforate	
	Convert to Injection		Reperforate		Convert to Injection		Vent or Flare	
	Fracture Treat or Acidize		Vent or Flare		Fracture Treat or Acidi	ize □	Water Shut-Off	
	Multiple Completion		Water Shut-Off		Other			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical deaths for all markers and zones pertinent to this work.)

Date of work completion

* Must be accompanied by a cement verification report.

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION REPORT AND LOG form.

Please be advised that River Gas Corporation is transferring ownership of the attached list of wells to Phillips Petroleum Company 9780 Mt. Pyramid Court, Englewood, CO 80112.

Please direct all correspondence and reports to: Phillips Petroleum Company P.O. Box 3368, Englewood, CO 80155-3368.

Effective 1/1/01.

Approximate date work will start

Change of Operator

D Other

13.	011-11		.1./
Name & Signature: Cal Hurtt	(al docum	Title: Development Manager	Date: <u>12/19/90</u>

(This space for state use only)

RGC/Phillips Merger

List of Affected BLM Leases and Rights-of-Way

A. Oil & Gas Leases

UTU-47157	UTU-70219	UTU-75016
UTU-49631	UTU-70400	UTU-75019
UTU-50645	UTU-71390	UTU-75021
UTU-51584	UTU-72003	UTU-75022
UTU-53872	UTU-72004	UTU-76332
UTU-57821	UTU-72350	UTU-76334
UTU-60402	UTU-72355	UTU-77351
UTU-60925	UTU-72358	UTU-77353
UTU-61154	UTU-72377	UTU-77354
UTU-61155	UTU-72470	UTU-78408
UTU-61158	UTU-72477	UTU-78409
UTU-61547	UTU-72624	UTU-78410
UTU-61548	UTU-72723	UTU-78411
UTU-62145	UTU-72724	UTU-78412
UTU-62276	UTU-72746	UTU-78413
UTU-65298	UTU-73004	UTU-78782
UTU-65300	UTU-73075	UTU-78783
UTU-65302	UTU-73330	UTU-79150
UTU-65303	UTU-73331	UTU-79151
UTU-67621	UTU-73523	UTU-79152
UTU-67839	UTU-73752	UTU-79153
UTU-67906	UTU-73884	UTU-79154
UTU-68314	UTU-74376	UTU-79155
UTU-69449	UTU- 75 015	UTU-79159
		•

B. Rights-of-Way

LITE 72226	IITI I 771 41	TIMIL GGOGE
UTU-73226	UTU-77141	UTU-77976
UTU-74319	UTU-77141-01	UTU-77989
UTU-74320	UTU-77151	UTU-77989-01
UTU-76610	UTU-77151-01	
UTU-76629	UTU-77154	



TRANSFER (TRANSFER OF AUTHORITY TO INJECT						
Well Name and Number See Attached		API Number					
Location of Well		Field or Unit Name					
Footage:	County:	Lease Designation and Number					
QQ, Section, Township, Range:	State: UTAH	Lease Designation and Number					
EFFECTIVE DATE OF TRANSFER: 1/1/01]						
CURRENT OPERATOR							
Company: River Gas Corporation	Name: Ca	1 Hurtt					
Address: 1300 McFarland Blvd. NE,		a Postt					
city Tuscaloosa state AL zip 35		eveloquent Euperizor					
Phone: (205) 759-3282	Date: /	17/19/19					
Comments:		9.40					
Change in operatorship due to r Petroleum Company effective 12,	merger of River Gas Co /31/00 at 11:59 p.m.	rporation into Phillips					
NEW OPERATOR							
Company: Phillips Petroleum Compa		Billy Stacy					
Address: 9780 Mt. Pyramid Court	Signature:	Billy Mory					
city Englewood state CO zip 801	.12 Title:	Asset Mangor					
Phone: (720) 344-4984	Date:	2-6-01					
Comments: Please send all reports a Phillips Petroleum Compan P.O. Box 3368		to:					

(This space for State use only)

Transfer approved by: . 🗷

Englewood, CO 80155-3368

Approval Date: Z-Z1-8/

Comments:

Disposal Wells to be transferred from RGC to Phillips Petroleum Company

Well#	API#	Location	Section	Township	Range
American Quasar D1	4300730040	999FSL, 1552 FWL	31	14S	10E
Arcadia-Telonis D2	4300730093	465 FSL, 560 FEL	19	148	09E
Utah D3	4300730290	1600 FSL, 1530 FEL	18	15S	10E
Utah D4	4300730314	600 FNL, 500 FWL	24	14S	09E
Fausett D5	4300730351	467 FNL, 1461 FWL	16	148	09E
Drew D6	4300730100	1300 FSL, 830 FWL	34	14S	09E
Utah D7	4301530338	1371 FSL, 1530 FEL	2	148	09E
Utah D8	4300730431	1342 FNL, 350 FWL	12	15S	09E
Utah D9	4300730438	1960 FNL, 1487 FWL	32	14S	09E
RGC D10	4300730520	162 FNL, 1557 FEL	28	15S	09E
USA D11	4301530356	1513 FNL, 2437 FEL	13	16S	09E
Sampinos D14	4300730567	1695 FSL, 2133 FEL	16	15S	10E

LAW OFFICES

PRUITT, GUSHEE & BACHTELL

SUITE 1850 BENEFICIAL LIFE TOWER
SALT LAKE CITY, UTAH 84111-1495
(801) 531-8446

TELECOPIER (801) 531-8468 E-MAIL: mail@pgblaw.com SENIOR COUNSEL:

ROBERT G. PRUITT, JR. OLIVER W. GUSHEE, JR.

OF COUNSEL:

ROBERT G. PRUITT, III BRENT A. BOHMAN

. C .

January 29, 2001

HAND DELIVERED

Mr. Jim Thompson Utah Division of Oil, Gas & Mining 1594 W. North Temple Salt Lake City, UT 84116

Re: River Gas/Phillips Merger

Dear Mr. Thompson:

THOMAS W. BACHTELL A. JOHN DAVIS, III

JOHN W. ANDERSON

ANGELA L. FRANKLIN

MICHAEL S. JOHNSON

JOHN S. FLITTON

WILLIAM E. WARD

FREDERICK M. MACDONALD GEORGE S. YOUNG

As you may know, River Gas Corporation ("RGC") merged into Phillips Petroleum Company ("Phillips") effective December 31, 2000 at 11:59 p.m. I have enclosed a Certificate of Articles of Merger issued by the Utah Department of Commerce and, although duplicative, a sundry notice formally evidencing the merger for your records, and a list of all wells, including injection wells, formerly operated by RGC.

Please change the Division's records to reflect the change in operator of these wells from RGC to Phillips. All operational questions should be directed to Phillips at the following address:

Phillips Petroleum Company Attn: Billy Stacy, Operations Manager P.O. Box 3368 Englewood, CO 80155-3368 Telephone No.: (720) 344-4984

Phillips currently has a bond on file with the Division (a copy of which is enclosed for your reference), but I understand an \$80,000 Letter of Credit is in the process of being substituted.

Mr. Jim Thompson January 29, 2001 Page 2

On behalf of Phillips, I thank you for your cooperation. Should you have any further questions or concerns, please do not hesitate to contact me.

Yours very truly,

Frederick M. MacDonald

FMM:cs 2078.16 Enclosures

cc: W. H. Rainbolt Billy Stacy



Utah Department of Commerce Division of Corporations & Commercial Code

160 East 300 South, 2nd Floor, Box 146705 Salt Lake City, UT 84114-6705 Phone: (801) 530-4849

Toll Free: (877) 526-3994 Utah Residents

Fax: (801) 530-6438

Web site: http://www.commerce.state.ut.us

Registration Number: 562960-0143

01/12/01

Business Name:

PHILLIPS PETROLEUM COMPANY


Registered Date:

JUNE 14, 1946

CERTIFICATE OF ARTICLES OF MERGER

THE UTAH DIVISION OF CORPORATIONS AND COMMERCIAL CODE ("DIVISION") HEREBY CERTIFIES THAT

ARTICLES OF MERGER WERE FILED WITH THIS OFFICE ON DECEMBER 12, 2000 MERGING RIVER GAS CORPORATION, A CORPORATION OF THE STATE OF ALABAMA, INTO PHILLIPS PETROLEUM COMPANY, THE SURVIVING CORPORATION WHICH IS OF THE STATE OF DELAWARE, AS APPEARS OF RECORD IN THE OFFICE OF THE DIVISION.



Pi Carpbell

Ric Campbell

Acting Division Director of

Corporations and Commercial Code

12-12-00P04:02 RCVD

State of Delaware

PAGE 1

Office of the Secretary of State



I, EDWARD J. FREEL, SECRETARY OF STATE OF THE STATE OF DELAWARE, DO HEREBY CERTIFY THE ATTACHED IS A TRUE AND CORRECTED OF COPY OF THE CERTIFICATE OF OWNERSHIP, WHICH MERGES:

"RIVER GAS CORPORATION", A ALABAMA CORPORATION,

WITH AND INTO "PHILLIPS PETROLEUM COMPANY" UNDER THE NAME OF "PHILLIPS PETROLEUM COMPANY", A CORPORATION ORGANIZED AND EXISTING UNDER THE LAWS OF THE STATE OF DELAWARE, AS RECEIVED AND FILED IN THIS OFFICE THE SIXTH DAY OF DECEMBER, A.D. 2000, AT 10 O'CLOCK A.M.

AND I DO HEREBY FURTHER CERTIFY THAT THE EFFECTIVE DATE OF THE AFORESAID CERTIFICATE OF OWNERSHIP IS THE THIRTY-FIRST DAY OF DECEMBER, A.D. 2000, AT 11:59 O'CLOCK A.M.

A FILED COPY OF THIS CERTIFICATE HAS BEEN FORWARDED TO THE NEW CASTLE COUNTY RECORDER OF DEEDS.

TAF

DEC 12 2000

Liter Blv. Of Corp. & Corner, Code

State of Utch
Department of Commerce
Division of Corporations and Commercial Code
I Hereby certify that the (oregoing has been filed and approved on this Lag day of Lago.

in the office of this Division and hereby issue this Certificate thereof.

Examiner_

RIC CAMPSE ACTING DIRE



Edward J. Freel, Secretary of State
AUTHENTICATION: 0837738

DATE: 12-07-00

0064324 8100M

001609453

STATE OF DELAWARE SECRETARY OF STATE DIVISION OF CORPORATIONS FILED 10:00 AM 12/06/2000 001609453 - 0064324

CERTIFICATE OF OWNERSHIP AND MERGER

OF

RIVER GAS CORPORATION

(an Alabama corporation)

into

Phillips Petroleum Company

(a Delaware corporation)

It is hereby certified that:

- 1. Phillips Petroleum Company [hereinafter sometimes referred to as the "Corporation"] is a business corporation of the State of Delaware.
- 2. The Corporation is the owner of all of the outstanding shares of each class of stock of River Gas Corporation, which is a business corporation of the State of Alabama.
- 3. The laws of the jurisdiction of organization of River Gas Corporation permit the merger of a business corporation of that jurisdiction with a business corporation of another jurisdiction.
- 4. The Corporation hereby merges River Gas Corporation into the Corporation.
- 5. The following is a copy of the resolutions adopted on November 21, 2000 by the Board of Directors of the Corporation to merge the said River Gas Corporation into the Corporation:
 - "1. Phillips Petroleum Company, which is a business corporation of the State of Delaware and is the owner of all of the outstanding shares of River Gas Corporation, which is a business corporation of the State of Alabama, hereby merges River Gas Corporation into Phillips Petroleum Company pursuant to the provisions of the Alabama Business Corporation Act and pursuant to the

provisions of Section 253 of the General Corporation Law of Delaware.

- "2. The separate existence of River Gas Corporation shall cease at the effective time and date of the merger pursuant to the provisions of the Alabama Business Corporation Act; and Phillips Petroleum Company shall continue its existence as the surviving corporation pursuant to the provisions of Section 253 of the General Corporation Law of Delaware.
- "3. The Articles of Incorporation of Phillips Petroleum Company are not amended in any respect by this Plan of Merger.
- "4. The issued shares of River Gas Corporation shall not be converted or exchanged in any manner, but each said share which is issued immediately prior to the effective time and date of the merger shall be surrendered and extinguished.
- "5. Each share of Phillips Petroleum Company outstanding immediately prior to the effective time and date of the merger is to be an identical outstanding share of Phillips Petroleum Company at the effective time and date of the merger.
- "6. No shares of Phillips Petroleum Company and no shares, securities, or obligations convertible into such shares are to be issued or delivered under this Plan of Merger.
- "7. The Board of Directors and the proper officers of Phillips Petroleum Company are hereby authorized, empowered, and directed to do any and all acts and things, and to make, execute, deliver, file, and/or record any and all instruments, papers, and documents which shall be or become necessary, proper, or convenient to carry out or put into effect any of the provisions of this Plan of Merger or of the merger herein provided for."
- "This Company approves that the effective time and date of the merger herein provided for in the State of Alabama shall be 11:59 p.m. on December 31, 2000."
- "Any Vice President, the Treasurer, any Assistant Treasurer, the Secretary, any Assistant Secretary, and each of them severally, be and hereby is authorized to make, execute,

DEC-66-2666 60.10

deliver, file, and/or record any and all instruments, papers, and documents which shall be or become necessary, proper, or convenient to carry out or put into effect any of the provisions of these resolutions and to do or cause to be done all such acts as are necessary to give effect to the purpose and intent of the approval herein set forth."

6. This Certificate of Ownership and Merger shall be effective at 11:59 p.m. on December 31, 2000.

Executed on November 27, 2000

Phillips Petroleum Company

N A Loffic Assistant Secretary



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office P.O. Box 45155 Salt Lake City, UT 84145-0155

In Reply Refer To: 3106 UTU-47157 et al (UT-932)

JAN 3 0 2001

NOTICE

Phillips Petroleum Company Attn: W. H. Rainbolt, Rocky Mtn. Region-Land Box 1967 Houston. TX 77251-1967

Oil and Gas

Merger Recognized

Acceptable evidence has been filed in this office concerning the merger of River Gas Corporation into Phillips Petroleum Company with Phillips Petroleum Company being the surviving entity.

The oil and gas lease files and rights-of-way files identified on the enclosed exhibit have been noted as to the merger. The exhibit is the list supplied by the representative of the companies, and verified by our computerized records. We have not adjudicated the case files to determine if the entity affected by the merger holds an interest in the leases identified, nor have we attempted to identify leases where the entity is the operator on the ground, maintaining no vested record title or operating rights interest. We are notifying the Minerals Management Service and all applicable BLM offices of the merger by a copy of this notice. If additional documentation for a change of operator is required by our Field Offices, you will be contacted by them.

By recognition of the merger the obligor is automatically changed by operation of law from River Gas Corporation to Phillips Petroleum Company on Letter of Credit No. P-207337 (BLM Bond No. UT0829). A rider to BLM Bond No. ES0048 assuming any and all liabilities of BLM Bond No. UT0829 must be submitted for approval to the Eastern States Office, Attn: Bill Forbes, 7450 Boston Boulevard, Springfield, VA 22153. After the rider is approved, the Letter of Credit will be returned to the financial institution that issued it.

ROBERT LOPEZ

Robert Lopez Chief, Branch of Minerals Adjudication

Enclosure

Exhibit of Leases

TED 0.2 2001

DIVISION OF OIL, GAS AND MIMITIA cc: Moab Field Office Vernal Field Office

Price Field Office

MMS-Reference Data Branch, MS 3130, P.O. Box 5860, Denver, CO 80217

State of Utah, DOGM, Attn: Jim Thompson (Ste. 1210), Box 145801, SLC, UT 84114

The Chase Manhattan Bank, Attn: Standby Letter of Credit Dept., 4 Chase Metrotech Center, 8th Floor Brooklyn, NY 11245

Teresa Thompson (UT-931)

LaVerne Steah (UT-942)

Pruitt, Gushee & Bachtell, Attn: Frederick M. MacDonald, Suite 1850 Beneficial Life Tower,

Salt Lake City, Utah 84111-1495

BLM, Eastern States Office (Attn: Bill Forbes)

Division of Oil, Gas and Mining

OPERATOR CHANGE WORKSHEET

ROUTING						
1. GLH	4-KAS					
2. CDW	558/10/					
3. JLT	6-FILE					

Enter date after each listed item is completed

Change of Operator (Well Sold)

Designation of Agent

Operator Name Change (Only)

X Merger

PHILLIPS PETROLEUM COMPANY Address: P. O. BOX 3368
Address: P. O. BOX 3368
ENGLEWOOD, CO 80155-3368
Phone: 1-(720)-344-4984
Account N1475

CA No.

Unit: DRUNKARDS WASH

WI	EL	L	(S)

	API	ENTITY	SEC. TWN	LEASE	WELL	WELL
NAME	NO.	NO.	RNG	TYPE	TYPE	STATUS
FAUSETT D5	43-007-30351	12165	16-14S-09E	Fee	SWD	A
ARCADIA-TELONIS 1 (D-2)	43-007-30093	99990	19-14S-09E	Fee	SWD	A
UTAH D-4	43-007-30314	11256	24-14S-09E	State	SWD	A
UTAH M-1	43-007-30199	11256	26-14S-09E	State	SWD	A
UTAH D-9	43-007-30438	12771	32-14S-09E	State	SWD	A
USA D6	43-007-30100	12466	34-14S-09E	Federal	SWD	A
DRUNKARDS WASH 31-1 (D-1)	43-007-30040	11256	31-14S-10E	State	SWD	A
UTAH D8	43-007-30431	11256	12-15S-09E	State	SWD	A
RGC D-10	43-007-30520	12545	28-15S-09E	Fee	SWD	A
UTAH M-2	43-007-30066	2889	34-15S-09E	Federal	TW	A
SAMPINOS D-14	43-007-30567	12729	16-15S-10E	Fee	SWD	Α
UTAH D-3	43-007-30290	11256	18-15S-10E	State	SWD	A
UTAH D7	43-015-30338	12404	02-16S-09E	State	SWD	A
D-11	43-015-30356	12572	13-16S-09E	Federal	SWD	A

OPERATOR CHANGES DOCUMENTATION

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on:

01/29/2001

2. (R649-8-10) Sundry or legal documentation was received from the NEW operator on:

01/29/2001

3. The new company has been checked through the Department of Commerce, Division of Corporations Database on:

02/15/2001

4.	Is the new operator registered in the State of Utah: YES Business Number: 562960-0143
5.	If NO , the operator was contacted on:
6.	Federal and Indian Lease Wells: The BLM and or the BIA has approved the (merger, name change, or operator change for all wells listed on Federal or Indian leases on: 01/30/2001
7.	Federal and Indian Units: The BLM or BIA has approved the successor of unit operator for wells listed on: N/A
8.	Federal and Indian Communization Agreements ("CA"): The BLM or the BIA has approved the operator change for all wells listed involved in a CA on: N/A
9.	Underground Injection Control ("UIC") Pro! The Division has approved UIC Form 5, Transfer of Authority to Inject, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: 02/22/2001
DA	ATA ENTRY:
1.	Changes entered in the Oil and Gas Database on: 02/20/2001
2.	Changes have been entered on the Monthly Operator Change Spread Sheet on: 02/20/2001
3.	Bond information entered in RBDMS on: N/A
4.	Fee wells attached to bond in RBDMS on: N/A
ST	ATE BOND VERIFICATION:
1.	State well(s) covered by Bond No.: 5952189
FF	E WELLS - BOND VERIFICATION/LEASE INTEREST OWNER NOTIFICATION:
1.	(R649-3-1) The NEW operator of any fee well(s) listed has furnished a bond: P-207328
	The FORMER operator has requested a release of liability from their bond on: N/A N/A
3.	(R649-2-10) The FORMER operator of the Fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: N/A
	LMING: All attachments to this form have been MICROFILMED on: フ・フン・ロー
	LING: ORIGINALS/COPIES of all attachments pertaining to each individual well have been filled in each well file on:
CC	MMENTS:

INSPECTION FORM 6

STATE OF UTAH DIVISION OF OIL GAS AND MINING

INJECTION WELL - PRESSURE TEST

Well Name: Utah \$ D-3 API Number: 43-007-30290 Qtr/Qtr: Section: Township: Range: Range:
Lease: State X Fee Federal Indian Date: 8/7/02
Tubing - Rate: Pressure: 1000 psi Casing/Tubing Annulus - Pressure: 1200 psi
Conditions During Test:
Time (Minutes) Annulus Pressure 1200 # 10 15 1200 # 1200 # 1000 # 1200 # 1200 # 1200 # 1200 # 1200 # 1200 # Results: Pass Fail
Tubing Pressure: 1200 psi Casing/Tubing Annulus Pressure: psi COMMENTS: 1750 permitted psi
Mike Ward, Johnny Damion Operator Representative



Re:

Notice of Address Change, Merger and Name Change

Address Change effective December 2, 2002

Merger and Name Change effective December 31, 2002

Divisions of Oil, Gas, and Mining Attn: Mr. John Baza 1594 West North Temple, Suite 1210, P. O. Box 145801 Salt Lake City, UT 84114-5801

) [36] (전 역 : 아니라 (Time Head) [27] (제)

Gentlemen:

- 1. Effective December 2, 2002, Phillips Petroleum Company will close its Englewood, Colorado Rocky Mountain Region office. After that time, all correspondence, notices and invoice for Land related matters should be directed to the address(es) noted below. Note that until December 31, 2002, all properties in which Phillips held an interest will continue to be operated by Phillips Petroleum Company, a wholly-owned subsidiary of ConocoPhillips.
- 2. On December 31, 2002, Phillips Petroleum Company and Conoco Inc. will merge, and the surviving corporation will be renamed "ConocoPhillips Company".

In accordance with the notice provisions of the Operating Agreements and other agreements, if any, between our companies, please adjust your company/organization records, effective for address purposes as of December 2, 2002, and for company name purposes, as of January 1, 2003, to reflect the following information for addressing and delivery of notices, invoicing and payment, and communications with ConocoPhillips Company. This will also apply to Lease Sale notices and other lease-related correspondence and notifications.

U.S. Mail Address:

ConocoPhillips Company P.O. Box 2197 Houston, Texas 77252 Attn: Chief Landman, San Juan/Rockies

Physical Address & Overnight Delivery:

ConocoPhillips Company 550 Westlake Park Blvd. Three Westlake Park 3WL, Room WL 9000 Houston, Texas 77079 Attn: Chief Landman, San Juan/Rockies

All ballots and official notices/responses sent by facsimile transmission should be sent to the following contact:

Attn: Chief Landman,

San Juan/Rockies

Weilian Painbai

Fax No.: 832-486-2688 or 832-486-2687

Please contact the undersigned immediately if you have any questions. This notice does not apply to royalty inquiries, joint interest billings, or revenue remittances. Please continue to use the same addresses you are currently using for these matters

Sincerely,

RECLIVED

DEC 0 2 2002

DIVISION OF OIL, GAS AND MINING

STATE OF UTAH

DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING

TRANSFER OF AUTHORITY TO INJECT							
Well Name and Number See Attached List		API Number See List					
Location of Well		Field or Unit Name					
Footage: See Attached List	County:	Lease Designation and Number					
QQ, Section, Township, Range:	State: UTAH						

EFFECTIVE DATE OF TRANSFER: 1/1/2003

Company:	Phillips Petroleum Company	Name:	Steve de Albuquerque
Address:	980 Plaza Office	Signature:	Lyle ally-
	city Bartlesville state OK zip 74004	_ Title:	HSE & Regulatory Supervisor
Phone:	(918) 661-4415	Date:	12/30/2002

NEW OPERA	TOR		
Company:	ConocoPhillips Company	Name:	Yolanda Perez
Address:	P. O. Box 2197, WL3 4066	Signature:	Yolanda Perez
	city Houston state TX zip 77252	Title:	gr. Regulatory Analyst
Phone:	(832) 486-2329	Date:	12/30/2002
Comments:	Conoco Inc. and Phillips Petroleum Company me	erged to form Co	nocoPhillips Company. Please see attached

(This space for State use only)

Approval Date: 2-3-03

Transfer approved by: Startes Manager

Title: Texti. Seartes Manager

Comments: D5, D2 + D3 ARE due for MIT.

RECEIVED JAN 0 8 2003

UIC Well List

SWD WELLS							
api	well_name	section	township	range	well_type	well_status	lease_type
4300730093	ARCADIA-TELONIS 1 (D-2)	19	140S	090E	WD	Α	FEE
4301530356	D-11	13	160S	090E	WD	Α	FEDERAL
4300730040	DRUNKARDS WASH 31-1 (D-1)	31	140S	100E	WD	Α	STATE
4300730351	FAUSETT D5	16	140S	090E	WD	Α	FEE
4301530531	PPCO D13	30	160S	090E	WD	DRL	FEE
4300730520	RGC D-10	28	150S	090E	WD	Α	FEE
4300730567	SAMPINOS D-14	16	150S	100E	WD	Α	FEE
4300730100	USA D6	34	140S	090E	WD	Α	FEDERAL
4300730819	UTAH D15	34	130S	090E	WD	APD	STATE
4300730290	UTAH D-3	18	150S	100E	WD	Α	STATE
4300730314	UTAH D-4	24	140S	090E	WD	Α	STATE
4301530338	UTAH D7	02	160S	090E	WD	Α	STATE
4300730431	UTAH D8	12	150S	090E	WD	Α	STATE
4300730438	UTAH D-9	32	140S	090E	WD	Α	STATE
	UTAH M-1	26	140S	090E	TW	Α	STATE
4300730066	UTAH M-2	34	150S	090E	TW	Α	FEDERAL

JAN 0 8 2003

List of Produced Water Ponds/Pits

	Permit/	State/F	ederal		ate Name Required		nmediate Required*		Agency Contact	Agency
L	License No.	S	F	Υ	N	Υ	N	Agency	Name	Contact Number
1	EVAPORATION POND	Χ		X				Utah Dept of Natural Resources, Dept. of Oil Gas and Mining		(801) 538-5340
2	D-1 POND	X		X				Utah Dept of Natural Resources, Dept. of Oil Gas and Mining		(801) 538-5340
3	D-2 (C-2) POND	Х		X				Utah Dept of Natural Resources, Dept. of Oil Gas and Mining		(801) 538-5340
4	D-3 POND	Х		Х				Utah Dept of Natural Resources, Dept. of Oil Gas and Mining		(801) 538-5340
* [* Describe: OPERATIONAL PERMITS FOR PRODUCED WATER PONDS									

RECEIVED
JAN 0 8 2003

DIV. OF OIL, GAS & MINING

STATE OF UTAH

DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING	5. LEASE DESIGNATION AND SERIAL NUMBER:
OUNDRY NOTICES AND DEPORTS ON WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
SUNDRY NOTICES AND REPORTS ON WELLS	
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL OIL WELL GAS WELL OTHER All	8. WELL NAME and NUMBER:
2. NAME OF OPERATOR:	See Attached List 9. API NUMBER:
Phillips Petroleum Company	See List
3. ADDRESS OF OPERATOR: 980 Plaza Office CITY Bartlesville STATE OK ZIP 74004 PHONE NUMBER: (918) 661-4415	10. FIELD AND POOL, OR WILDCAT:
4. LOCATION OF WELL	
FOOTAGES AT SURFACE: See Attached List	COUNTY:
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:	STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPO	RT, OR OTHER DATA
TYPE OF SUBMISSION TYPE OF ACTION	
NOTICE OF INTENT	REPERFORATE CURRENT FORMATION
(Submit in Duplicate) ALTER CASING FRACTURE TREAT	SIDETRACK TO REPAIR WELL
Approximate date work will start: CASING REPAIR LINEW CONSTRUCTION	TEMPORARILY ABANDON
CHANGE TO PREVIOUS PLANS OPERATOR CHANGE	TUBING REPAIR
CHANGE TUBING PLUG AND ABANDON	VENT OR FLARE
SUBSEQUENT REPORT CHANGE WELL NAME PLUG BACK (Submit Original Form Only)	WATER DISPOSAL
Date of work completion: CHANGE WELL STATUS PRODUCTION (START/RESUME)	WATER SHUT-OFF
COMMINGLE PRODUCING FORMATIONS RECLAMATION OF WELL SITE	OTHER:
CONVERT WELL TYPE RECOMPLETE - DIFFERENT FORMATION	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volume	es, etc.
Conoco Inc. was merged into Phillips Petroleum Company, the surviving corporation, on De with this merger and effective on the same date, the name of the surviving corporation was Company". We are requesting that a new Operator Number be assigned to ConocoPhillips	changed to "ConocoPhillips
Please send production reporting forms to Herb Henderson at ConocoPhillips Company, 31 Bartlesville, OK 74004. Herb's phone number is 918-661-4415.	5 S. Johnstone, 980 Plaza Office,
Current Operator Phillips Petroleum Company ConocoPhillips Company ConocoPhillips Company	RECEIVED
Ally yolanda Perez	JAN 0 8 2003
Steve de Albuque Yolanda Perez	
VV	DIV. OF OIL, GAS & MINING
NAME (PLEASE PRINT) Yolanda Perez TITLE Sr. Regulatory Ar	nalyst
SIGNATURE Wolanda Pure DATE 12/30/2002	

(This space for State use only)



SECRETARY'S CERTIFICATE

I, the undersigned, Jennifer M. Garcia, Assistant Secretary of ConocoPhillips Company, formerly Phillips Petroleum Company, organized and existing under and by virtue of the laws of the State of Delaware (the "Corporation"), hereby certify that:

- As Assistant Secretary I am authorized to execute this certificate 1. on behalf of the Corporation.
- 2. The attached photocopy of the Certificate of Amendment to the Restated Certificate of Incorporation of Phillips Petroleum Company (to be renamed ConocoPhillips Company) is a true and correct copy as filed in the office of the Secretary of State of Delaware on the 12th day of December 2002, with an effective date of January 1, 2003 and such Certificate of Amendment has not been modified, amended, rescinded or revoked and is in full force and effect as of the date hereof.
- 3. The attached photocopy of the Certificate of Merger of Conoco Inc. with and into ConocoPhillips Company is a true and correct copy as filed in the office of the Secretary of State of Delaware on the 12th day of December 2002, with an effective date of December 31, 2002 and such Certificate of Merger has not been modified, amended, rescinded or revoked and is in full force and effect as of the date hereof.

IN WITNESS WHEREOF, I have hereunto set my hand as Assistant Secretary and affixed the corporate seal of the Corporation this 7th day of January 2003.

ocoPhillips Company

STATE OF TEXAS

COUNTY OF HARRIS

This instrument was acknowledged before me on January 7, 2003, by Jennifer M. Garcia, Assistant Secretary of ConocoPhillips Company, a Delaware corporation, on behalf of said Corporation

RECEIVED

JAN n 8 2003

DIV. OF OIL, GAS & MINING



The First State

I, HARRIET SMITH WINDSOR, SECRETARY OF STATE OF THE STATE OF DELAWARE, DO HEREBY CERTIFY THE ATTACHED IS A TRUE AND CORRECT COPY OF THE CERTIFICATE OF AMENDMENT OF "PHILLIPS PETROLEUM COMPANY", CHANGING ITS NAME FROM "PHILLIPS PETROLEUM COMPANY" TO "CONOCOPHILLIPS COMPANY", FILED IN THIS OFFICE ON THE TWELFTH DAY OF DECEMBER, A.D. 2002, AT 1:41 O'CLOCK P.M.

AND I DO HEREBY FURTHER CERTIFY THAT THE EFFECTIVE DATE OF THE AFORESAID CERTIFICATE OF AMENDMENT IS THE THIRTY-FIRST DAY OF DECEMBER, A.D. 2002, AT 11 O'CLOCK P.M.

> **RECEIVED** JAN 0 8 2003

DIV. OF OIL, GAS & MINING

Harriet Smith Windsor, Secretary of State

AUTHENTICATION: 2183360

DATE: 01-02-03

0064324 8100

030002793

STATE OF DELAWARE

(THU) 12. 12' 02 13:32/ST. 13:34/JACK 446/647/6749EP 5

DIVISION OF CORPORATIONS

FILED 01:41 PM 12/12/2002

020763238 - 0064324

CERTIFICATE OF AMENDMENT

to the

RESTATED CERTIFICATE OF INCORPORATION

οf

PHILLIPS PETROLEUM COMPANY (to be renamed ConocoPhillips Company)

Phillips Petroleum Company ("Phillips"), a corporation organized and existing under the General Corporation Law of the State of Delaware (the "DGCL"), hereby certifies that:

- 1. The amendments to Phillips' Restated Certificate of Incorporation set forth below were duly adopted in accordance with the provisions of Section 242 of the DGCL and have been consented to in writing by the sole stockholder of Phillips in accordance with Section 228 of the DGCL.
- 2. Phillips' Restated Certificate of Incorporation is hereby amended by deleting Article I thereof and replacing in lieu thereof a new Article I reading in its entirety as follows:

"The name of the corporation (which is hereinafter referred to as the "Corporation") is ConocoPhillips Company."

- 3. Phillips' Restated Certificate of Incorporation is hereby amended by deleting Section 1 of Article IV thereof and replacing in lieu thereof a new Section 1 reading in its entirety as follows:
 - "Section 1. The Corporation shall be authorized to issue 2,100 shares of capital stock, of which 2,100 shares shall be shares of Common Stock, \$.01 par value ("Common Stock")."
- 4. Pursuant to Section 103(d) of the DGCL, this amendment will become effective at 11:00 p.m., Eastern time, on December 31, 2002.

RECEIVED

JAN 0 8 2003

DIV. OF OIL, GAS & MINING

HOU03:884504.1

IN WITNESS WHEREOF, Phillips has caused this certificate to be executed this 12th day of December, 2002.

PHILLIPS PETROLEUM COMPANY

By:

Name: Rick A. Harrington

Title: Senior Vice President, Legal,

and General Counsel

HOU03:884504.1

RECEIVED

JAN 0 8 2003

DIV. OF OIL, GAS & MINING



The First State

I, HARRIET SMITH WINDSOR, SECRETARY OF STATE OF THE STATE OF DELAWARE, DO HEREBY CERTIFY THE ATTACHED IS A TRUE AND CORRECT COPY OF THE CERTIFICATE OF MERGER, WHICH MERGES:

"CONOCO INC.", A DELAWARE CORPORATION,

WITH AND INTO "CONOCOPHILLIPS COMPANY" UNDER THE NAME OF "CONOCOPHILLIPS COMPANY", A CORPORATION ORGANIZED AND EXISTING UNDER THE LAWS OF THE STATE OF DELAWARE, AS RECEIVED AND FILED IN THIS OFFICE THE TWELFTH DAY OF DECEMBER, A.D. 2002, AT 1:44 O'CLOCK P.M.

AND I DO HEREBY FURTHER CERTIFY THAT THE EFFECTIVE DATE OF THE AFORESAID CERTIFICATE OF MERGER IS THE THIRTY-FIRST DAY OF DECEMBER, A.D. 2002, AT 11:59 O'CLOCK P.M.

RECEIVED

JAN 0 8 2003

DIV. OF OIL, GAS & MINING

Warriet Smith Windson, Secretary of State

AUTHENTICATION: 2183370

DATE: 01-02-03

0064324 8100M

030002793

CERTIFICATE OF MERGER

of

Conoco Inc.
(a Delaware corporation)

with and into

ConocoPhillips Company (a Delaware corporation)

Phillips Petroleum Company, a Delaware corporation to be renamed ConocoPhillips Company prior to the effective time of this certificate of merger (the "Surviving Corporation"), in compliance with the requirements of the General Corporation Law of the State of Delaware (the "DGCL") and desiring to effect a merger of Conoco Inc., a Delaware corporation formerly incorporated under the name Du Pont Holdings, Inc. (the "Merging Corporation," and together with the Surviving Corporation, the "Constituent Corporations"), with and into the Surviving Corporation, and acting by its duly authorized officer, DOES HEREBY CERTIFY that:

First: As of the date hereof, the name and state of incorporation of each of the Constituent Corporations of the merger are as follows:

NAME

STATE OF INCORPORATION

PHILLIPS PETROLEUM COMPANY

Delaware

CONOCO INC.

Delaware

Second: An agreement and plan of merger has been approved, adopted, certified, executed and acknowledged by each of the Constituent Corporations in accordance with the requirements of Section 251 of the DGCL;

Third: The name of the Surviving Corporation will be ConocoPhillips Company;

Fourth: The Certificate of Incorporation of ConocoPhillips Company immediately prior to the merger shall be the Certificate of Incorporation of the Surviving Corporation until such time as it may be amended in accordance with applicable law and the provisions thereof;

Fifth: The executed agreement and plan of merger is on file at an office of the Surviving Corporation, the address of which is 600 North Dairy Ashford, Houston, Texas 77079;

RECEIVED

JAN 0 8 2003

Sixth: A copy of the agreement and plan of merger will be furnished by the Surviving Corporation, on request and without cost, to any stockholder of any Constituent Corporation; and

Seventh: Pursuant to Section 103(d) of the DGCL, this certificate of merger will become effective at 11:59 p.m., Eastern time, on December 31, 2002.

Dated: December 12, 2002

PHILLIPS PETROLEUM COMPANY

(a Delaware corporation)

7

Name: Rick A. Harrington

Title: Senior Vice President, Legal, and General Counsel

RECEIVED
JAN 0 8 2003



CONOCOPHILLIPS COMPANY

Corporation - Foreign - Profit 562960-0143

REFERENCE NUMBER(S). CLASSIFICATION(S) & DETAIL(S)

EFFECTIVE 06/14/1946

EXPIRATION *RENEWAL

UNITED STATES CORP CO
CONOCOPHILLIPS COMPANY
GATEWAY TOWER EAST STE 900
10 EAST SOUTH TEMPLE
SLC UT 84133

RECEIVED
JAN 0 8 2003

DIV. OF OIL, GAS & MINING

STATE OF UTAH DEPARTMENT OF COMMERCE DIVISION OF CORPORATIONS & COMMERCIAL CODE

REGISTRATION

EFFECTIVE DATE:

06/14/1946

EXPIRATION DATE:

*RENEWAL

ISSUED TO:

CONOCOPHILLIPS COMPANY



REFERENCE NUMBER(S), CLASSIFICATION(S) & DETAIL(S)

562960-0143

Corporation - Foreign - Profit

*RENEWAL

You will need to renew your registration each anniversary date of the effective date. Exceptions: DBAs and Business Trusts renew every three (3) years from the effective date.



United States Department of the Interior

BUREAU OF LAND MANAGEMENT Eastern States Office 7450 Boston Boulevard Springfield, Virginia 22153

IN REPLY REFER TO 3106.8(932.34)WF

January 16, 2003

NOTICE

ConocoPhillips Company : Oil & Gas Leases

P.O. Box 7500

Bartlesville, Oklahoma 74005 :

Merger/Name Change Recognized

Acceptable evidence was received in this office on January 14, 2003, concerning the change of name of Phillips Petroleum Company to ConocoPhillips Company and the merger of Conoco Incorporated into ConocoPhillips Company on Federal oil and gas leases, with ConocoPhillips Company being the surviving entity.

The Secretary of the State of Delaware certified the effective date of this merger effective December 31, 2002.

The oil and gas lease files identified on the enclosed exhibit have been noted to the merger. The exhibit was compiled from a list of leases obtained from your list of leases. Eastern States has not abstracted the lease files to determine if the entities affected by this merger hold an interest in the leases identified nor have we attempted to identify leases where the entities are the operator on the ground maintaining no vested record title or operating rights interest. We are notifying the Minerals Management Service and all applicable Bureau of Land Management offices of this merger and name change by a copy of this notice. If additional documentation for changes of operator are required by our Field Offices, you will be contacted by them.

If you identify other leases in which the merging entity maintain an interest, please contact this office and we will appropriately document those files with a copy of this Notice.

By Operation of law the name of the principal on Nationwide Oil and Gas Bond held by Conoco Incorporated (ES0085) has been changed to ConocoPhillips Company.

If you have any questions, please contact Bill Forbes at 703-440-1536.

Shullet B. Fisher

Wilbert B. Forbes
Land Law Examiner
Branch of Use Authorization
Division of Resources Planning, Use
and Protection

OPERATOR CHANGE WORKSHEET

ROUTING

1. GLH

2. CDW 3. FILE

Change of Operator (Well Sold)

Designation of Agent/Operator

Operator Name Change

5. If **NO**, the operator was contacted contacted on:

X Merger

The operator of the well(s) listed below has changed, of	enecuve:	12-31-02				
FROM: (Old Operator):		TO: (New Operator):				
PHILLIPS PETROLEUM COMPANY	}	CONOCOPHILLIPS COMPANY				
Address: 980 Plaza Office]	Address: P O BOX 2197, WL3 4066				
Bartlesville, OK 74004]	HOUSTON, T	X 77252			
Phone: 1-(918)-661-4415		Phone: 1-(832)	-486-2329			
Account No. N1475		Account No.	N2335			
CA No.	7.1	Unit:	-			
WELL(S)					 	
	SEC TWN	API NO	ENTITY	LEASE	WELL	WELL
NAME	RNG		NO	TYPE	TYPE	STATUS
UTAH D-15	34-13S-09E	43-007-30819		STATE	SWD	APD
FAUSETT D-5	16-14S-09E	43-007-30351	12165	FEE	SWD	A
ARCADIA-TELONIS 1 (D-2)	19-14S-09E	43-007-30093	99990	FEE	SWD	A
UTAH D-4	24-14S-09E	43-007-30314	11256	STATE	SWD	A
UTAH M-1	26-14S-09E	43-007-30199	11256	STATE	TW	A
UTAH D-9	32-14S-09E	43-007-30438	12771	STATE	SWD	A
USA D-6		43-007-30100			SWD	A
UTAH D-8	12-15S-09E	43-007-30431	11256	STATE	SWD	A
RGC D-10	28-15S-09E	43-007-30520	12545	FEE	SWD	A
UTAH M-2	34-15S-09E	43-007-30066	2889	FEDERAL	TW	A
DRUNKARDS WASH 31-1 (D-1)		43-007-30040		STATE	SWD	A
SAMPINOS D-14	16-15S-10E	43-007-30567	12729	FEE	SWD	A
UTAH D-3	18-15S-10E	43-007-30290	11256	STATE	SWD	A
UTAH D-7	02-16S-09E	43-015-30338	12404	STATE	SWD	A
D-11	13-16S-09E	43-015-30356	12572	FEDERAL	SWD	A
PPCO D13	30-16S-09E	43-015-30531	99999	FEE	SWD	DRL
OPERATOR CHANGES DOCUMENTATION Enter date after each listed item is completed 1. (R649-8-10) Sundry or legal documentation was received fi			on: 01/08/2003	01/08/2003		
3. The new company has been checked through the Departme	ent of Comm	erce, Division o	f Corpora	tions Databa	ise on:	02/03/2003
4. Is the new operator registered in the State of Utah:	YES	Business Numb	er:	562960-0143	}	

6. (R649-9-2)Waste Management Plan has been received on:	IN PLACE	
7. Federal and Indian Lease Wells: The BLM and or operator change for all wells listed on Federal or Indian		the merger, name change,
8. Federal and Indian Units: The BLM or BIA has approved the successor of unit operations.	rator for wells listed on:	01/14/2003
9. Federal and Indian Communization Agreeme The BLM or BIA has approved the operator for all wells	` ,	01/14/2003
10. Underground Injection Control ("UIC") for the enhanced/secondary recovery unit/project for the w		UIC Form 5, Transfer of Authority to Inject, on: 02/04/2003
DATA ENTRY: 1. Changes entered in the Oil and Gas Database on:	02/03/2003	· · · · · · · · · · · · · · · · · · ·
2. Changes have been entered on the Monthly Operator Cha	ange Spread Sheet on:	02/03/2003
3. Bond information entered in RBDMS on:	N/A	
4. Fee wells attached to bond in RBDMS on:	N/A	
STATE WELL(S) BOND VERIFICATION: 1. State well(s) covered by Bond Number:	8140-60-24	
FEDERAL WELL(S) BOND VERIFICATION: 1. Federal well(s) covered by Bond Number:	8015-16-69	
INDIAN WELL(S) BOND VERIFICATION: 1. Indian well(s) covered by Bond Number:	N/A	
FEE WELL(S) BOND VERIFICATION:		
1. (R649-3-1) The NEW operator of any fee well(s) listed cov	vered by Bond Number	6196922
2. The FORMER operator has requested a release of liability for The Division sent response by letter on:	rom their bond on: N/A	N/A
LEASE INTEREST OWNER NOTIFICATION: 3. (R649-2-10) The FORMER operator of the fee wells has be of their responsibility to notify all interest owners of this characteristics.		oy a letter from the Division
COMMENTS:		

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES

DIVISION OF OIL, GAS AND MINING	5. LEASE DESIGNATION AND SERIAL NUMBER: ML-38666
SUNDRY NOTICES AND REPORTS ON WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	7. UNIT OF CA AGREEMENT NAME: UTU-67921X
1. TYPE OF WELL OIL WELL GAS WELL OTHER Water Disposal	8. WELL NAME and NUMBER: Utah D-3
2. NAME OF OPERATOR:	9. API NUMBER: 4300730290
ConocoPhillips Company 3. ADDRESS OF OPERATOR: PHONE NUMBER:	10. FIELD AND POOL, OR WILDCAT:
P. O. Box 51810 CITY Midland STATE TX ZIP 79710-1810 (432) 688-6943	Drunkards Wash
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1600' FSL & 1126' FWL	COUNTY: Carbon
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWSW 18 15S 10E	STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPO	RT, OR OTHER DATA
TYPE OF SUBMISSION TYPE OF ACTION	
✓ NOTICE OF INTENT ☐ ACIDIZE ☐ DEEPEN	REPERFORATE CURRENT FORMATION
(Submit in Duplicate) ALTER CASING FRACTURE TREAT	SIDETRACK TO REPAIR WELL
Approximate date work will start: CASING REPAIR NEW CONSTRUCTION	TEMPORARILY ABANDON
☐ CHANGE TO PREVIOUS PLANS ☐ OPERATOR CHANGE	TUBING REPAIR
CHANGE TUBING PLUG AND ABANDON	VENT OR FLARE
SUBSEQUENT REPORT CHANGE WELL NAME PLUG BACK (Submit Original Form Only)	WATER DISPOSAL
Date of work completion: CHANGE WELL STATUS PRODUCTION (START/RESUME)	WATER SHUT-OFF
COMMINGLE PRODUCING FORMATIONS RECLAMATION OF WELL SITE	OTHER: Install tbg
CONVERT WELL TYPE RECOMPLETE - DIFFERENT FORMATION	******
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volum	es, etc.
ConocoPhillips Company respectfully requests that the attached procedure to install a 3 1/2 csg be approved. The procedure is submitted to meet the requirement that a tubing string be shallow water contamination from casing leaks.	" tbg string inside the 7" production be inside a casing string to protect
NAME (PLEASE PRINT) Donna Williams TITLE Sr. Regulatory A	nalyst
SIGNATURE DATE 2/5/2007	
(This space for State use only)	
APPROVED BY THE STATE	RECEIVED
APPROVED BY THE STATE OF UTAH DIVISION OF OIL, GAS, AND MINING	RECEIVED

A Contact Mark Tones w/ Down prior to conductory mit



Drunkard's Wash Utah D-3 SWD) Well **Install Tubing Procedure**

Revised Friday, February 02, 2007

Location:

1600' FSL & 1126' FWL (NWSW), Sec. 18, T15S, R10E Carbon, Utah

Spud Date: **API Number:** 2/27/1996 43-007-30290

Original TD:

6.510'

Packer Depth:

7" Arrow-Pak Wireline Set Tubing Retrievable Packer set @ 5,508' (Below pkr. 1,3 1/2"

tubing sub, 3 1/2" X Nipple, 1, 3 1/2" tubing sub, XN Nipple) See wellbore sketch.

TOC:

Surface (Circulated cement to surface).

KBE: GLE: 5707' 5691'

KBM:

16' above GL

Tubulars

Csg/Tubing Size	Depth (ft)	Wt (lb/ft)	Grade	Drift ID	Burst (psl)	Coll ((psi)
13-3/8	0 – 526'	48	H-40			
9-5/8	0 - 3718'	40	K-55			
7	0 – 6491'	26	J-55	6.151	4980	4320

Project Overview:

The intent of this procedure will be to install a tubing string in the D-3 active SWD well, as required by the State of Utah Department of Natural Resources. Currently the well is an active SWD well with disposal water being injected via 7" casing. Within recent years the State of Utah has required water injection & disposal be contained within a tubing string inside a casing string to protect shallow water contamination from casing leaks.

In April, 1996 the D-3 well was converted to a Navajo (5561' to 5896') & Wingate Sandstone (5997' to 6058') formation SWD well. The D-3 SWD well serves as the water disposal well for the Drunkard Wash field and disposes of approximately 2,000 bbls per day of produced water from the Ferron formation.

Currently the well has a 7" permanent packer set at 5,508' with 3 1/2" tubing subs and a X and XN profile nipples below. This procedure will consist of rigging up and running 5,500 of 3 1/2" tubing, landing into the existing packer, performing a MIT test and placing back on injection.

This project is considered as non-discretionary as it is required by the State of Utah for continued operation.

 Drunkard's Wash D-3 SWD Well Install Tubing Procedure Page 2

Existing Perforations:

Navajo:

5561-5602, 5566-5567', 5619-27', 5635-47', 5663-5728', 5736-63', 5784-5872', 5888-

5896'

Wingate Sandstone

5997-6029', 6030-6040', 6041-6058'

Well Control Requirements:

Well Control: Well Control equipment and procedures will be in accordance with the ConocoPhillips Well Control Manual, Second Edition, Revision Two, dated August 1994.

Well Category: The D-2 SWD well is expected to be dead once the well is shut-in. If required the well will be flowed back or killed with 10 ppg kill weight fluid. Since this is a SWD well and is not expected to flow at any time during the operation, this well is to be considered a **Category 1** well.

BOPE Class 2: Standard procedures for the area requires a Class 2 or Hydraulic operated BOP stack. The actual stack will consist of a hydraulic operated 5M PSIG BOP stack with 3 ½" tubing rams on top and blinds below. NU shop tested BOP stack on top of companion flange. Test as per SOP.

Workover Fluid: Use treated 10.0 ppg brine water for duration of operations. Use dynamic head kill procedure if required to maintain control of the well during tripping and installation / removal of BOP's.

Note: All depths referenced to 16' RKB.

Procedure

Notify the State of Utah representatives a minimum of 24 hours prior to moving in to inform them of ConocoPhillips plans and timing.

- Shut the well in and allow the well to bleed off surface pressure. Load casing with 10 ppg brine water if required. Lay bleed line from tubing head to frac tank or steel lined pit. Leave bleed line open while installing BOP stack.
- 2. MIRU workover rig. Insure well is dead prior to removing wellhead. Install a minimum of a 5,000 PSI WP BOP with 3 ½" pipe rams on top and blinds on bottom. Test BOP as per SOP.
- 3. PU and TIH with Weatherford Completion Systems seal stack assembly on approximately 5,508' of 3 ½", 9.2 ppf, J-55 tubing. See attached sketch.
- 4. Latch into the 7" packer at 5,508'. Load the casing and test to 500 PSIG for 15 minutes.
- 5. Release from the packer, PU and space out. RU pump truck and pump packer fluid via casing.
- 6. Drop down and latch onto the packer. Install tubing hanger and land tubing. ND the BOP stack and reinstall existing injection wellhead valves. RD pulling unit.
- Perform MIT test as per State requirements.

Drunkards Wash Emergency Contact Information

Utah D-3 SWD: Location: GPS Coordinates: 513009 E, 4374074 N

DIAL 911 for all emergency services

ConocoPhillips	Office:	(435) 613 -977 7	Fax:	(434) 613-97	82
Jim Weaver	Operations	Superintendent		820-6379	cell
Jeff Sandoval	Health / Sa	fety / Environment		<u>820-6576</u>	cell
Russell Getman	Southern C	Operations Supervisor		820-8524	Cell
Steve Lessar	Northern C	perations Supervisor		<u>636-5027</u>	cell
Colby Guest	Project and	d operations lead		636-6888	cell
Mike Greenan	Project and	d operations lead		<u>820-8325</u>	cell

Contractors

Weatherford Oil Tools	Office	(435) 789-712 <u>1</u>
Tracy Nielson	cell	(435) 828-779 4
Nelco Construction	Office	<u>(435) 637-3495</u>
<u>Garth</u>	cell	(435) 636-7000
Noyes Trucking	Office	<u>(435) 613-0430</u>
Wes Noves	cell	<u>(435) 820-8832</u>
Graco tool rental	Office	(435) 789-6804
Lowell Aycock	cell	(435) 790-0745
Rain for Rent Tanks	Office	<u>(801) 292-9996</u>
<u>Lin Bell</u>	cell	<u>(801) 541-1661</u>
Halliburton <u>Barry Winter</u>	Office Office	<u>(435 789-2550</u>
Basic Energy/Energy Air <u>Mike Sexton</u> <u>Bob Delong</u>	Office Cell Cell	(970) 241-6029 (970) 260-3856 (970 858-7826
Wood's Group Wellhead, <u>Garth George</u>	Cell	(435) 828-2598
Waste Logistics, <u>Jesse Mccourt</u>	Office Cell	(435) 472-2580 (435) 636-5422

STATE OF UTAH DIVISION OF OIL GAS AND MINING

RBOMSV

INJECTION WELL - PRESSURE TEST

Well Name: Utah 0-3 Qtr/Qtr: NWSW Section: 18 Company Name: Conoca Phili,	API Number: Township:	/3067 30 Z 9 0 S Range:
Lease: State Fee Fee	Federal Date: <u>5/3</u>	Indian
Initial Conditions:		
Tubing - Rate:	Pressure:_	psi
Casing/Tubing Annulus - Pressure:	O psi	
Conditions During Test:		
Time (Minutes) Annu	llus Pressure	Tubing Pressure
0	1000+	-0 #
5		
10		<u></u>
15	1000 F	
20		
25		
30 _	1000 #	0 #
Results: Pass/Fail	***************************************	
Conditions After Test:		
Tubing Pressure: psi		
Casing/Tubing Annulus Pressure:		_
COMMENTS: Packer and	tuling insta	elled in wellbore
Parker @ 5523'.	Tested w/a	ulled in wellbore wiveline set plug
in XN nipple below	Packer.	
that		
Operator Representative		

Operator Representative

RECEIVED
MAY 1 4 2007

STATE OF UTAH

DEPARTMENT OF NATURAL RESOURCES	
DIVISION OF OIL, GAS AND MINING	5. LEASE DESIGNATION AND SERIAL NUMBER: ML-38666
SUNDRY NOTICES AND REPORTS ON WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	7. UNIT OF CA AGREEMENT NAME: UTU-67921X
1. TYPE OF WELL OIL WELL GAS WELL OTHER Water Disposal	8. WELL NAME and NUMBER: Utah D-3
2. NAME OF OPERATOR: ConocoPhillips Company	9. API NUMBER: 4300730290
3. ADDRESS OF OPERATOR: P.O. Box 51810 CITY Midland STATE TX ZIP 79710-1810 (432) 688-6943	10. FIELD AND POOL, OR WILDCAT: Drunkards Wash
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1600' FSL & 1126' FWL	COUNTY: Carbon
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWSW 18 15S 10E	STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPO	RT, OR OTHER DATA
TYPE OF SUBMISSION TYPE OF ACTION	
NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: CASING REPAIR CHANGE TO PREVIOUS PLANS DEEPEN FRACTURE TREAT NEW CONSTRUCTION OPERATOR CHANGE	REPERFORATE CURRENT FORMATION SIDETRACK TO REPAIR WELL TEMPORARILY ABANDON TUBING REPAIR
SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: 5/3/2007 CHANGE WELL NAME CHANGE WELL NAME CHANGE WELL STATUS PRODUCTION (START/RESUME) RECLAMATION OF WELL SITE CONVERT WELL TYPE RECOMPLETE - DIFFERENT FORMATION	VENT OR FLARE WATER DISPOSAL WATER SHUT-OFF OTHER: Install tbg, MIT
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volume 5/1/07: SIRU. Hook up hard line to pit, SICP 824#. Monitor flowing water for H2S. No sign in, build up to 700#. 5/2/07: ND WH to master valve, rig up wireline. PU 2.75 XN nipple. RIH w/wireline, tag pa w/wireline. Open well to pit. Well bled off. RD wireline. ND master valve, NU new tbg spo assemly and TIH w/3.5" tbg. Sting into packer @ 5520'. Fill hole, test to 1000# for 15 minut fluid, space out tbg and land at 5520'. 5/3/07: ND BOP, NU WH, Rig down. Perform successful MIT, 1000# for 30 minutes. Test	n. Flow well back to 46#. Shut well acker, set plug in XN nipple. POOH ol. NU BOP, RU floor, PU seal tes. Sting out of packer, circ packer
NAME (PLEASE PRINT) Donna Williams TITLE Sr. Regulatory S	pecialist

(This space for State use only)

SIGNATURE

RECEIVED

MAY 1 5 2007

DATE 5/10/2007

STATE OF UTAH

DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL. GAS AND MINING

		DIVISION OF OIL	., GAS AND I	MINING		5. LEASE DESIGNATION AND SERIAL NUMBER: ML38666
	SUNDR	Y NOTICES AN	D REPOR	TS ON WEL	LS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
Do n	not use this form for proposals to drill drill horizontal	new wells, significantly deeper	n existing wells below	current bottom-hole dep	oth, reenter plugged wells, or to	7. UNIT or CA AGREEMENT NAME: Drunkards Wash
	PE OF WELL OIL WELL			Disposal We		8. WELL NAME and NUMBER: Utah D-3
	AME OF OPERATOR:					9. API NUMBER:
	nocoPhillips Company	<u>'</u>			I DUONE NUMBER	4300730290 10. FIELD AND POOL, OR WILDCAT:
		TY Midland	STATE TX	_{ZIP} 79710	PHONE NUMBER: (432) 688-6943	Drunkards Wash
	DOTAGES AT SURFACE: 1600	FSL & 1126 FWL				COUNTY: Carbon
QT	TR/QTR, SECTION, TOWNSHIP, RA	NGE, MERIDIAN: NWSW	/ 18 15S	10E		STATE: UTAH
11.	CHECK APF	ROPRIATE BOXE	S TO INDICA			ORT, OR OTHER DATA
	TYPE OF SUBMISSION				YPE OF ACTION	
1	NOTICE OF INTENT	ACIDIZE		DEEPEN		REPERFORATE CURRENT FORMATION
	(Submit in Duplicate) Approximate date work will start:	ALTER CASING		FRACTURE		SIDETRACK TO REPAIR WELL
		CASING REPAIR	OUG BLANC		STRUCTION	TEMPORARILY ABANDON
	7/1/2008	CHANGE TO PREVI	OUS PLANS	OPERATOR		TUBING REPAIR
	SUBSEQUENT REPORT	CHANGE TUBING CHANGE WELL NAI	ME	PLUG AND		VENT OR FLARE WATER DISPOSAL
	(Submit Original Form Only)	CHANGE WELL STA		_	` ON (START/RESUME)	WATER SHUT-OFF
	Date of work completion:		DUCING FORMATION		TION OF WELL SITE	OTHER: Add Formation
		CONVERT WELL TO			ETE - DIFFERENT FORMATIO	
12.	DESCRIBE PROPOSED OR C					
Co pro	nocoPhillips Company	respectfully reque the D8 to a Dakota	st to add the well. The Da	Dakota format kota formation	ion to the disposal is a unitized forma	authorization. We are currently in the ation of the Drunkards Wash Unit.
				A	d but the	
				Approve	d by the	
				Oldin Di	vision of nd Mining	
				Oli, Gas a	100 11111	
				v/a-	77 EV7	
			D	late: 07	455	
				Jan K	Vill I	
			E	ly:		

		1				
	_{E (PLEASE PRINT)} Donna W	/illiams		-	Sr. Regulatory	Specialist
NAM	E (PLEASE PRINT)			TITI		
SIGN	IATURE	wit		DA1	6/26/2008	
(This sp	pace for State use only)					RECEIVED

COPY SENT TO OPERATOR

7.23.2008

(See Instructions on Reverse Side)

JUN 2 7 2003



Customer: ConocoPhillips

Date Sampled: 18-Apr-08

Address:

Date Reported: 21-Apr-08

City: Price

Date Received: 21-Apr-08

State: UT

Field: Drunkards Wash Unit Lease: Drunkards Wash Unit

Attention:

Location: D-8 SWD

cc1:

cc2:

Sample Point: wellhead

Comments: CO2 at default value. 1ST RUN

Postal Code:

Salesman: Scott Harbison

Analyst: Karen Hawkins Allen

CATIONS

ANIONS

Calcium:

182 mg/l Chloride:

22,540 mg/l

mg/l

Magnesium:

mg/l

Carbonate:

mg/l

Barium:

mg/l

Bicarbonate:

1,022

Strontium:

mg/l

Sulfate:

590 mg/l

Iron:

4.0 mg/l

Manganese: Sodium:

mg/l 14997 mg/l

CO2 in Water:

300 mg/l

pH (field): Temperature: 7.00

CO2 in Gas:

0.03

mole %

Specific Gravity:

degrees F

grams/ml

H2S in Water:

mg/l

TDS:

39,377

ppm

Dissolved Oxygen:

ppm

Ionic Strength:

0.66

Resistivity:

ohm/meters

SI calculations based on Tomson-Oddo parameters

Calcite (CaCO3) SI:

-1.18

Calcite PTB:

N/A

-1.02

Calcite (CaCO3) SI @ 100 F: Calcite (CaCO3) SI @ 120 F:

-0.81

Calcite PTB @ 100 F: Calcite PTB @ 120 F: N/A N/A

Calcite (CaCO3) SI @ 140 F: Calcite (CaCO3) SI @ 160 F: -0.59 -0.37-0.14 Calcite PTB @ 140 F: Calcite PTB @ 160 F: Calcite PTB @ 180 F: N/A N/A

Calcite (CaCO3) SI @ 180 F: Calcite (CaCO3) SI @ 200 F:

0.10 -1.75 Calcite PTB @ 200 F:

N/A 22.4

Gypsum (CaSO4) SI: Barite (BaSO4) SI:

Celestite (SrSO4) SI:

N/A N/A

Barite PTB:

Gypsum PTB:

Celestite PTB:

N/A N/A

N/A



Manganese:

Water Analysis Report

Customer: ConocoPhillips Date Sampled: 18-Apr-08

Date Reported: 21-Apr-08
Address: Date Received: 21-Apr-08

City: Price

State: UT Postal Code: Field: Drunkards Wash Unit Lease: Drunkards Wash Unit

Attention: Location: D-8 SWD

cc1: Sample Point: wellhead cc2:

Comments: CO2 at default value. 3RD RUN

Analyst: Karen Hawkins Allen

<u>CATIONS</u> <u>ANIONS</u>

Calcium: 266 mg/l **Chloride:** 26,760 mg/l

 Magnesium :
 13 mg/l
 Carbonate :
 0 mg/l

 Barium :
 mg/l
 Bicarbonate :
 749 mg/l

Strontium: mg/l Sulfate: 603 mg/l

Iron: 2.0 mg/l

Sodium : 17595 mg/l

pH (field): 7.00 CO2 in Water: 300 mg/l

Temperature:85 degrees FCO2 in Gas:0.03 mole %

Specific Gravity: 1.035 grams/ml H2S in Water: mg/l

T D S: 45,988 ppm Dissolved Oxygen: ppm

Ionic Strength: 0.78 Resistivity: ohm/meters

SI calculations based on Tomson-Oddo parameters

mg/l

Calcite (CaCO3) SI: -1.36Calcite PTB: N/A Calcite PTB @ 100 F: N/A Calcite (CaCO3) SI @ 100 F: -1.20 Calcite (CaCO3) SI @ 120 F: -0.99 Calcite PTB @ 120 F: N/A -0.78 Calcite PTB @ 140 F: N/A Calcite (CaCO3) SI @ 140 F: Calcite PTB @ 160 F: N/A Calcite (CaCO3) SI @ 160 F: -0.55

Gypsum (CaSO4) SI: -1.62 Gypsum PTB: N/A

Barite (BaSO4) SI: N/A Barite PTB: N/A

Celestite (SrSO4) SI: N/A Celestite PTB: N/A

Confidential
Champion Technologies Inc.

Champion Technologies, Inc. Vernal District Technical Services



Customer: ConocoPhillips

Date Sampled: 18-Apr-08

Date Reported: 21-Apr-08

Address:

Date Received: 21-Apr-08

City: Price

State: UT

Field: Drunkards Wash Unit

Postal Code:

Lease: Drunkards Wash Unit

Attention:

Location: D-8 SWD

cc1:

cc2:

Sample Point: wellhead

Comments: CO2 at default value. 8TH RUN

Salesman: Scott Harbison

Analyst: Karen Hawkins Allen

CATIONS

ANIONS

Calcium:

200 mg/l Chloride:

27,100 mg/l

Magnesium:

mg/l

Carbonate:

0 mg/l

mg/l

Barium:

mg/l

Bicarbonate:

368 mg/l

Strontium:

mg/l

Sulfate:

633

Iron: 1.0 mg/l

Manganese:

mg/l

Sodium:

17672 mg/l

pH (field):

CO2 in Water:

300

mg/l

Temperature:

degrees F

CO2 in Gas:

0.03

mole %

Specific Gravity: TDS: 1.035 grams/ml H2S in Water:

mg/l

46,035

7.00

Dissolved Oxygen:

ppm

Ionic Strength:

0.78

Resistivity:

ohm/meters

SI calculations based on Tomson-Oddo parameters

Calcite (CaCO3) SI:

-2.10

Calcite PTB:

N/A

Calcite (CaCO3) SI @ 100 F:

-1.95 -1.73

-1.06

-0.82

Calcite PTB @ 100 F: Calcite PTB @ 120 F: N/A

Calcite (CaCO3) SI @ 120 F: Calcite (CaCO3) SI @ 140 F: Calcite (CaCO3) SI @ 160 F:

-1.52 -1.29

Calcite PTB @ 140 F: Calcite PTB @ 160 F: Calcite PTB @ 180 F:

Calcite PTB @ 200 F:

N/A N/A N/A N/A

N/A

Calcite (CaCO3) SI @ 180 F: Calcite (CaCO3) SI @ 200 F: Gypsum (CaSO4) SI:

-1.73 N/A Gypsum PTB:

N/A N/A

Barite (BaSO4) SI: Celestite (SrSO4) SI:

N/A

Barite PTB: Celestite PTB:

N/A



Iron:

Sodium:

2.0 mg/l

Water Analysis Report

Date Sampled: 18-Apr-08 Customer: ConocoPhillips

Date Reported: 21-Apr-08 Address: Date Received: 21-Apr-08

City: Price Field: Drunkards Wash Unit State: UT Postal Code: Lease: Drunkards Wash Unit

Attention: Location: D-8 SWD Sample Point: wellhead cc1:

cc2:

Salesman: Scott Harbison Comments: CO2 at default value. 13TH RUN

Analyst: Karen Hawkins Allen

CATIONS ANIONS

Calcium: 255 mg/l Chloride: 26,500 mg/l

Magnesium: mg/l Carbonate: 0 mg/l **Bicarbonate:** 381 Barium: mg/l mg/l

Strontium: mg/l Sulfate: 650 mg/l

mg/l Manganese: 17295 mg/l

7.00 CO2 in Water: 300 pH (field): mg/l

degrees F CO2 in Gas: 0.03 mole % Temperature:

H2S in Water: Specific Gravity: grams/ml mg/l

TDS: Dissolved Oxygen: ppm 45,111 ppm

Resistivity: ohm/meters **Ionic Strength:**

SI calculations based on Tomson-Oddo parameters

Calcite (CaCO3) SI: -1.96Calcite PTB: N/A Calcite PTB @ 100 F: N/A Calcite (CaCO3) SI @ 100 F: -1.80 Calcite (CaCO3) SI @ 120 F: -1.59Calcite PTB @ 120 F: N/A Calcite PTB @ 140 F: N/A Calcite (CaCO3) SI @ 140 F: -1.37 Calcite (CaCO3) SI @ 160 F: -1.15 Calcite PTB @ 160 F: N/A Calcite (CaCO3) SI @ 180 F: -0.92 Calcite PTB @ 180 F: N/A

Calcite (CaCO3) SI @ 200 F: Calcite PTB @ 200 F: N/A -0.68 Gypsum PTB: Gypsum (CaSO4) SI: -1.61 N/A

Barite (BaSO4) SI: Barite PTB: N/A N/A

Celestite (SrSO4) SI: N/A Celestite PTB: N/A



Customer: ConocoPhillips

Date Sampled: 18-Apr-08 Date Reported: 21-Apr-08

Address:

City: Price

Date Received: 21-Apr-08

State: UT

Postal Code:

Field: Drunkards Wash Unit Lease: Drunkards Wash Unit

Attention:

cc1:

Location: D-8 SWD

cc2:

Sample Point: wellhead

Comments: CO2 at default value. 14TH RUN

Salesman: Scott Harbison

Analyst: Karen Hawkins Allen

ANIONS

CATIONS

250 mg/l Chloride:

27,680 mg/l

Magnesium:

Calcium:

mg/l

Carbonate:

mg/l

mg/l

Barium:

mg/l

Bicarbonate:

320 mg/l

Strontium:

mg/l

Sulfate:

575

Iron: 1.0 mg/l

Manganese:

mg/l

Sodium:

17888 mg/l

CO2 in Water:

300 mg/l

pH (field):

7.00

CO2 in Gas:

0.03 mole %

Temperature: **Specific Gravity:**

degrees F 85

grams/ml

H2S in Water:

mg/l

TDS:

46,805 ppm Dissolved Oxygen:

ppm

Ionic Strength:

0.80

Resistivity:

ohm/meters

SI calculations based on Tomson-Oddo parameters

Calcite (CaCO3) SI:

-2.14

Calcite PTB:

N/A

Calcite (CaCO3) SI @ 100 F:

-1.98

Calcite PTB @ 100 F:

N/A

Calcite (CaCO3) SI @ 120 F: Calcite (CaCO3) SI @ 140 F:

-1.77 -1.55 -1.33 Calcite PTB @ 120 F: Calcite PTB @ 140 F: Calcite PTB @ 160 F: N/A N/A

Calcite (CaCO3) SI @ 160 F: Calcite (CaCO3) SI @ 180 F: Calcite (CaCO3) SI @ 200 F:

-1.10 -0.86 Calcite PTB @ 180 F: Calcite PTB @ 200 F: N/A N/A N/A

Gypsum (CaSO4) SI:

Barite (BaSO4) SI:

Celestite (SrSO4) SI:

-1.68 N/A N/A

Gypsum PTB: Barite PTB:

Celestite PTB:

N/A N/A

N/A

Confidential



Customer: ConocoPhillips

Date Sampled: 18-Apr-08 Date Reported: 21-Apr-08

Address:

City: Price

Date Received: 21-Apr-08

State: UT

Postal Code:

Field: Drunkards Wash Unit Lease: Drunkards Wash Unit

Attention:

Location: D-8 SWD

cc1: cc2: Sample Point: wellhead

Comments: CO2 at default value. 15TH RUN

Salesman: Scott Harbison

Analyst: Karen Hawkins Allen

CATIONS

ANIONS

Calcium:

206 mg/l Chloride:

27,820 mg/l

Magnesium:

mg/l

Carbonate:

0 mg/l

Barium:

mg/l

Bicarbonate:

305 mg/l

mg/l

Strontium:

mg/l

Sulfate:

555

Iron: 1.0 mg/l

Manganese:

mg/l

Sodium:

18095 mg/l

300

pH (field):

7.00

CO2 in Water:

mg/l

Temperature:

degrees F

ppm

CO2 in Gas: **H2S in Water:** 0.03

mole % mg/l

Specific Gravity: TDS: grams/ml

ppm

Dissolved Oxygen:

Ionic Strength:

47,030 0.80

Resistivity:

ohm/meters

SI calculations based on Tomson-Oddo parameters

Calcite (CaCO3) SI:

-2.26

Calcite PTB:

N/A

Calcite (CaCO3) SI @ 100 F:

-2.11

Calcite PTB @ 100 F:

N/A

Calcite (CaCO3) SI @ 120 F:

-1.90-1.68 Calcite PTB @ 120 F: Calcite PTB @ 140 F: N/A

Calcite (CaCO3) SI @ 140 F: Calcite (CaCO3) SI @ 160 F:

-1.45 -1.22 Calcite PTB @ 160 F: Calcite PTB @ 180 F:

N/A N/A

N/A

Calcite (CaCO3) SI @ 180 F: Calcite (CaCO3) SI @ 200 F:

-0.98 -1.78 Calcite PTB @ 200 F: Gypsum PTB:

N/A N/A

Gypsum (CaSO4) SI: Barite (BaSO4) SI:

Celestite (SrSO4) SI:

N/A N/A

Barite PTB: Celestite PTB: N/A N/A



Customer: ConocoPhillips

Date Sampled: 18-Apr-08

Date Reported: 21-Apr-08

Address:

Date Received: 21-Apr-08

City: Price

State: UT

Field: Drunkards Wash Unit

Lease: Drunkards Wash Unit

Attention:

Location: D-8 SWD

cc1:

cc2:

Sample Point: wellhead

Comments: CO2 at default value. 16TH RUN.

Postal Code:

Salesman: Scott Harbison

Analyst: Karen Hawkins Allen

CATIONS

ANIONS

Calcium: 173 mg/l

Chloride:

27,540 mg/l

Magnesium:

25 mg/l

Carbonate:

0 mg/l mg/l

Barium:

mg/l

Bicarbonate:

283

Strontium:

mg/l

Sulfate:

575

1.0 mg/l

Iron:

mg/l

Manganese: Sodium:

17996 mg/l

CO2 in Water:

300

mg/l

mg/l

pH (field): Temperature:

degrees F

CO2 in Gas:

0.03 mole %

Specific Gravity:

grams/ml

H2S in Water:

mg/l

TDS:

1.035 46,593 ppm

7.00

Dissolved Oxygen:

ppm

Ionic Strength:

0.79

Resistivity:

ohm/meters

SI calculations based on Tomson-Oddo parameters

Calcite (CaCO3) SI:

-2.40

Calcite PTB:

N/A

Calcite (CaCO3) SI @ 100 F: Calcite (CaCO3) SI @ 120 F: -2.24 -2.03 Calcite PTB @ 100 F: Calcite PTB @ 120 F: N/A

Calcite (CaCO3) SI @ 140 F: Calcite (CaCO3) SI @ 160 F:

-1.81 -1.59 -1.36

-1.12

Calcite PTB @ 140 F: Calcite PTB @ 160 F: N/A N/A N/A

Calcite (CaCO3) SI @ 180 F: Calcite (CaCO3) SI @ 200 F: Calcite PTB @ 180 F: Calcite PTB @ 200 F:

N/A N/A

Gypsum (CaSO4) SI:

-1.83N/A Gypsum PTB: Barite PTB: N/A N/A

Barite (BaSO4) SI: Celestite (SrSO4) SI:

N/A

Celestite PTB:

N/A



Customer: ConocoPhillips

Date Sampled: 18-Apr-08

Address:

Date Reported: 21-Apr-08

Date Received: 21-Apr-08

City: Price

State: UT

Field: Drunkards Wash Unit

Lease: Drunkards Wash Unit

Attention:

Location: D-8 SWD

cc1:

cc2:

Sample Point: wellhead

Salesman: Scott Harbison

Comments: CO2 at default value. 17TH RUN.

Postal Code:

Analyst: Karen Hawkins Allen

CATIONS

ANIONS

Calcium:

178 mg/l Chloride:

25,980 mg/l

Magnesium:

30 mg/l Carbonate:

0 mg/l

Barium:

mg/l

Bicarbonate:

312

mg/l

Strontium:

mg/l

Sulfate:

590

mg/l

Iron:

Sodium:

1.0 mg/l

Manganese:

mg/l

pH (field):

16988 mg/l

7.00

CO2 in Water:

300

mg/l

Temperature:

85 degrees F

CO2 in Gas:

0.03 mole %

Specific Gravity:

1.035 grams/ml H2S in Water:

mg/l

TDS:

44,079 ppm **Dissolved Oxygen:**

Ionic Strength:

0.75

Resistivity:

ohm/meters

SI calculations based on Tomson-Oddo parameters

Calcite (CaCO3) SI:

-2.28

Calcite PTB:

N/A

Calcite (CaCO3) SI @ 100 F: Calcite (CaCO3) SI @ 120 F: -2.12-1.91 Calcite PTB @ 100 F:

N/A

Calcite (CaCO3) SI @ 140 F:

-1.69-1.47 Calcite PTB @ 120 F: Calcite PTB @ 140 F: Calcite PTB @ 160 F: N/A N/A

Calcite (CaCO3) SI @ 160 F: Calcite (CaCO3) SI @ 180 F: Calcite (CaCO3) SI @ 200 F:

-1.24 -1.00 Calcite PTB @ 180 F: Calcite PTB @ 200 F: N/A N/A N/A

N/A

N/A

Gypsum (CaSO4) SI:

Barite (BaSO4) SI:

Celestite (SrSO4) SI:

-1.79 N/A

N/A

Gypsum PTB: Barite PTB:

Celestite PTB:

N/A

UTAH DIVISION OF OIL, GAS AND MINING

NOTICE OF REPORTING PROBLEMS

Operator: Conocophillips Company		Account: N2335	Today's D	ate: 09/16/2008
Problems: Late Report(s) Inaccurate Report(s) Incomplete Report(s) Other: No Subsequent Reports		complete man Violation by th result in the outlined in Rul Se	ner may result in e Division of Oil, Division pursuin e R649-10, Admi ction 40-6-11 of t	hese reporting problem
Send reports to: Utah Division of Oil, Gas and Mining 1594 West North Temple, Suite 1210 P.O. Box 145801 Salt Lake City, Utah 84114-5801		<u>Fax to:</u> (801) 359-	3940 $\mathcal U$	007 30290 tah D3 10E 18
Type of Report		Month(s) of Problem Re	port
Production – Form 10				
☐ Disposition – Form 11				
Gas Plant – Form 13				
Enhanced Recovery – UIC Form 2				
Injection – UIC Form 3				
Other				
Type of Report	Well N	ame(s)	API Number(s)	Drilling Commence
Spud Notice – Form 9				
Drilling Reports – Form 9				
Well Completion Report Form 8				
✓ Other Subsequent Sundry	✓ List Attacl	ned		
Description of Problem: Operator has submitted sundry of intents or a subsequent report shall be submitted on F show workover results, well status, work con	Form 9, Sundry	Notice, with in 30	days after comp	DOGM. Per Rule 649-3-2 letion. The report should
If you have questions or concerns regarding	this matter, plea	ise contact Rac	hel Medina at	(801) 538-5260 .

cc: Compliance File RAM Well File CHD

UTAH DIVISION OF OIL, GAS AND MINING

NOTICE OF REPORTING PROBLEMS

ATTACHMENT

Operator:	Conocophillips Company	Account: N2335	Todav's Date:	09/16/2008

Well Names	API Numbers	Drilling Commenced
Pinnacle Peak 19-171	4300730117	
Utah D-6	4300730100	
Arcadia Telonis 1 (D2)	4300730093	
Utah D3	4300730290	
Utah D8	4300730431	

STATE OF UTAH

DEPARTMENT OF NATURAL RESOURCES					
DIVISION OF OIL, GAS AND MINING				5. LEASE DESIGNATION AND SERIAL NUMBER: ML38666	
SUNDRY NOTICES AND REPORTS ON WELLS				6. IF INDIAN, ALLOTTEE OR TRIBE NAME:	
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.				7. UNIT or CA AGREEMENT NAME: Drunkards Wash	
1. TYPE OF WELL OIL WELL GAS WELL OTHER Disposal Well				8. WELL NAME and NUMBER: Utah D-3	
2. NAME OF OPERATOR:				9. API NUMBER:	
ConocoPhillips Company				4300730290	
			PHONE NUMBER: (432) 688-6943	10. FIELD AND POOL, OR WILDCAT: Drunkards Wash	
4. LOCATION OF WELL	SL & 1126 FWL			COUNTY: Carbon	
FOOTAGES AT SURFACE: 1600 F	COUNTY: Cal Doil				
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWSW 18 15S 10E				STATE: UTAH	
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA					
TYPE OF SUBMISSION		Τ	YPE OF ACTION		
NOTICE OF INTENT	ACIDIZE	DEEPEN		REPERFORATE CURRENT FORMATION	
(Submit in Duplicate)	ALTER CASING	FRACTURE	TREAT	SIDETRACK TO REPAIR WELL	
Approximate date work will start:	CASING REPAIR	NEW CONS	TRUCTION	TEMPORARILY ABANDON	
	CHANGE TO PREVIOUS PLANS	OPERATOR	CHANGE	TUBING REPAIR	
	CHANGE TUBING	PLUG AND	ABANDON	VENT OR FLARE	
SUBSEQUENT REPORT (Submit Original Form Only)	CHANGE WELL NAME	PLUG BACK	<	WATER DISPOSAL	
Date of work completion:	CHANGE WELL STATUS	PRODUCTION	ON (START/RESUME)	WATER SHUT-OFF	
11/9/2008	COMMINGLE PRODUCING FORMATIONS	RECLAMAT	ION OF WELL SITE	✓ OTHER: Liner	
11/9/2000	CONVERT WELL TYPE	RECOMPLE	TE - DIFFERENT FORMATION		
12. DESCRIBE PROPOSED OR CO	MPLETED OPERATIONS. Clearly show all p	pertinent details inc	cluding dates, depths, volume	es, etc.	
Please be advised that the	pond liner on the above referen	ced location	was replaced this fa	ll. The work began on or about	
October 1, 2008 and was o	completed on November 9, 2008	3.			
		•			
•					
•					
NAME (PLEASE PRINT) DONNA WI	liams	TITL	F Sr. Regulatory S	pecialist	
NAME (PLEASE INTIVI)		1111	·		
SIGNATURE		DAT	E 12/10/2008		

RECEIVED

DEC 1 1 2008

(This space for State use only)

STATE OF UTAH

ML 38666	
SUNDRY NOTICES AND REPORTS ON WELLS 6. IF INDIAN, ALLOTTEE OR T	RIBE NAME:
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. 7. UNIT or CA AGREEMENT NUTU67921X	AME:
1. TYPE OF WELL OIL WELL GAS WELL OTHER Disposal 8. WELL NAME and NUMBER: Utah D 3	
2. NAME OF OPERATOR: ConocoPhillips Company 9. API NUMBER: 4300730290	h 1
3. ADDRESS OF OPERATOR: P.O. Box 51810 CITY Midland STATE TX ZIP 79710 PHONE NUMBER: (432) 688-6943 Drunkards Wash	DCAT:
4. LOCATION OF WELL	Jerninence, i ciaemi i ciar
FOOTAGES AT SURFACE: 1600 FSL & 1126 FWL COUNTY: Carbon	
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWSW 18 15S 10E STATE:	
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DAT	A
TYPE OF SUBMISSION TYPE OF ACTION ACIDIZE DEEPEN REPERFORATE CURP	SENT FORMATION
NOTICE OF INTENT (Submit in Duplicate) ACIDIZE DEEPEN L REPERFORATE CURF SIDETRACK TO REPA SIDETRACK TO REPA	
Approximate date work will start: CASING REPAIR NEW CONSTRUCTION TEMPORARILY ABANI	
9/22/2009 CHANGE TO PREVIOUS PLANS OPERATOR CHANGE TUBING REPAIR	
CHANGE TUBING PLUG AND ABANDON VENT OR FLARE	
SUBSEQUENT REPORT CHANGE WELL NAME PLUG BACK WATER DISPOSAL	
(Submit Original Form Only) CHANGE WELL STATUS PRODUCTION (START/RESUME) WATER SHUT-OFF	
Date of work completion: COMMINGLE PRODUCING FORMATIONS RECLAMATION OF WELL SITE OTHER: Addition	al Source
CONVERT WELL TYPE RECOMPLETE - DIFFERENT FORMATION	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.	
As per the discussion with Brad Hill w/DOGM on 9/16/2009, ConocoPhillips Company respectfully request the following	llowing:
Bill Barrett Corp. is currently making plans to complete in the Manning Canyon the recently drilled State 16H-32-COP is a 50% owner of this well, we are respectfully requesting to dispose of the flowback fluid (3% KCI + format from the upcoming completion work into the above referenced SWD. This request is a temporary additional source occur for no longer than 4 weeks. Approved by the Utah Division of Oil, Gas and Mining	tion water)
Date: D9-21-09 Date: 1017: 20 Initials: K5	
NAME (PLEASE PRINT) Donna Williams TITLE Sr. Regulatory Specialist	
SIGNATURE DATE 9/17/2009	

RECEIVED

SEP 2 1 2009

(This space for State use only)